

# NEVADA COMMISSION FOR CULTURAL CENTERS & HISTORIC PRESERVATION (CCCHP) GRANT APPLICATION

	NEVADA <b>STATE HISTORIC                  PRESERVATION OFFICE</b>	<i>SHPO Use Only</i>
Initials: <u>CC</u> Received: <u>4-29-24</u>		
Postmarked: <u>N/A</u> Delivery Svc: <u>Hand Delivered</u>		

**APPLICATION COVER PAGE** This unaltered form must be submitted as the cover page for the application. Do not staple or bind application documents.

Grant Cycle Year(s) 2023-2024

Applicant Organization: Storey County  
 EIN (Taxpayer Identification Number): 88-6000134  
 Mailing Address: 26 South B Street PO Box 7  
 City: Virginia City County: NV ZIP: 89440  
 Project Contact: Sara Sturtz Title: Grants Manager  
 Daytime Phone: 775-350-9473 Evening Phone: NA  
 Fax: NA - please email Email: ssturtz@storeycounty.org

Historic Property Name: Piper's Opera House Date Built: 1885  
 Property Owner Name and Address: Storey County; see above address  
 Project Address: 12 North B Street  
 City: Virginia City County: Storey ZIP: 89440  
 Property Insured:  Yes; please enclose one copy of policy  No; please explain: \_\_\_\_\_

Project Title: Piper's Opera House Front Door Restoration Project  
 Project Type:  Rehabilitation/Construction  Planning/Construction  
 Architectural/Engineering Study/Construction

**Project Synopsis (Brief):**

Storey County will contract with Central Sierra Construction Inc (CSCI) to restore 12 existing wood doors on front (east) elevation of the Opera House and restore the five windows on the south wall of Piper's Opera House. CSCI will remove doors and windows from the site and transport to CSCI's shop for restoration work. Door hardware will be replaced as needed. CSCI has estimated that this project will take 10 weeks to complete and the County is ready to begin the project. The proposed start date is reflective of when the County believes the SHPO will be able to obligate the funds and can easily be modified, especially if the weather conditions do not allow for work. Thank you for your time and consideration.

Proposed Start Date: 11/31/24

Proposed End Date: 3/31/25

<b>Project Budget Summary:</b>	
Amount Requested:	<u>\$107,375.00</u>
Proposed Match:	
Cash:	<u>\$20,000.00</u>
In-Kind/Donations:	_____
<b>Total Project Budget:</b>	<u>\$127,375.00</u>
If Applicable, Minimum Amount Requested	<u>\$107,375.00</u>


<b>Applicant's Authorized Signature*</b>
Name: <u>Sara Sturtz</u>
Title: <u>Grants Manager</u>
Date: <u>4/29/2024</u>

**\*Sign in blue or black ink. Application packets without original signatures will be considered incomplete.**

NEVADA COMMISSION FOR CULTURAL  
CENTERS & HISTORIC PRESERVATION (CCCHP)  
**GRANT APPLICATION**



NEVADA  
**STATE HISTORIC  
PRESERVATION OFFICE**

---

APPLICATION COVER PAGE Cont.

### Handbook Verification Form

- I HAVE READ THE CCCHP GRANT HANDBOOK, AND
- I HAVE COMPLETED THIS CCCHP GRANT APPLICATION, AND
- I CERTIFY THE INFORMATION CONTAINED HEREIN IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE.

A handwritten signature in black ink, appearing to read 'Sara Sturtz', written over a horizontal line.

Applicant's Authorized Signature\*

Name: Sara Sturtz

Title: Grants Manager

Date: 4/29/2024

\*Sign in blue or black ink. Application packets without original signatures will be considered incomplete.

NEVADA COMMISSION FOR CULTURAL  
CENTERS & HISTORIC PRESERVATION (CCCHP)  
**GRANT APPLICATION**



NEVADA  
**STATE HISTORIC  
PRESERVATION OFFICE**

APPLICATION COVER PAGE Cont.

## Application Checklist

**Directions:** Assemble the application in the following order and initial in blue or black ink on the lines to confirm that each of the required components are included in the application package.


### 1. Cover Pages

 \_\_\_\_\_ Application Cover Page


 \_\_\_\_\_ Handbook Verification Form


 \_\_\_\_\_ Application Checklist


### 2. Project Narrative


 \_\_\_\_\_ **A. Questions** (No more than 5 pages)

#### B. Supplemental Material

 \_\_\_\_\_ A paragraph (200 words maximum) describing the current or intended future use of the property and cultural center programming.

 \_\_\_\_\_ County Assessor print out showing the current owner of the property with the APN number

 \_\_\_\_\_ Photographs of all exterior elevations with views and all major rooms and project rooms, identified and keyed to a site plan


 \_\_\_\_\_ **Organization's information including:**

- Articles of incorporation, mission statement, length of time established, and history
- A list of current board members
- Long-range plan including information on how frequently the plan is updated
- **If applicable:**
- A list of activities for the past fiscal year
- A detailed report on current CCCHP grant status as well as the outcome of previous CCCHP grants
- A current list (last three years) of all grants and additional funding, including amounts the organization has or will receive


### 3. Budget

 \_\_\_\_\_ **Detailed Budget**


- Completed Budget Form
- Attached itemized lists and/or contractor quotes that break down labor and material costs

 \_\_\_\_\_ **Audit**


- Most recent audit for the organization. If there is no audit, provide an explanation of why an audit was not completed and how bookkeeping is managed.

 \_\_\_\_\_ **Insurance**

- Proof of insurance for the property or a justification for why there is no insurance

 \_\_\_\_\_ **Resumes**

- All principal professionals involved in planning, design and management of the proposed project

 \_\_\_\_\_ **Initial to confirm that the applicant understands that applications lacking any of the required information listed above are ineligible for review by the Commission.**

## CCCHP Grant FY23/24 Grant Application – Piper’s Opera House Front Doors

### 2.A – Questions

#### 1. Project Description:

- What building(s), prehistoric feature, historic feature, or culturally significant feature are you restoring/rehabilitating?
  - **The 12 front doors and frames/transoms at the front entry (east elevation) of Piper’s Opera House and the five windows on the south wall of Piper’s Opera House.**
- What is the historical significance of the property?
  - **Piper’s Opera House is in Virginia City, which earned its place on the map after the discovery of gold in 1859. Shortly after, a mining boom gave Virginia City the title of “The Richest Place on Earth.” Throughout the following decades people came from all over the world to earn their chance of striking it rich. Silver was the predominant ore body that was mined, with gold being a consequential side mineral. Through its riches, Comstock, which is comprised of Virginia City, Gold Hill, Silver City, and parts of Dayton, contributed to billions of dollars being injected into the National economy. In the late 1800’s the mining boom slowed and Virginia City, which had seen populations of up to 25,000 people, lost many of its residents. Subsequent mining booms occurred over the next decades and briefly people would flock once again to the region, but never in the amount as the first big boom of the 1860s and 1870s.**

**Throughout the rise and fall of the residential population, Virginia City managed to remain entrenched on the hillside of Mt. Davidson. In the 1960’s Virginia City once again was put in the spotlight with the arrival of the television show, “Bonanza”. Since then, tourism has been as important to the towns success as mining had once been. Annually one million people visit Virginia City, and the number continues to grow. Registered as a National Historic Landmark and listed on the National Register of Historic Places, historic structures, such as Piper’s Opera House, are vital to the County’s tourism.**

**The current Piper’s Opera House was constructed in 1885, after two other iterations of the Opera House were burned to the ground (Great Fire of 1875 and another fire in 1883). At its height, the Opera House was one of the finest theater houses in the Western United States. The theater attracted many famous performers such as but not limited to Buffalo Bill, Maude Adams, Edwin Booth, and Al Jolson.**

The Opera House was condemned in 1920 and reopened as a museum in the 1940s. After undergoing significant renovations by Louise Zimmer Driggs (Piper's great granddaughter), the Opera House reopened in the 1970s and was an active theater through the mid-1980s. The theatre was once again forced to close its doors in the mid-1980s; however, under new ownership, the Opera House was able to open again as a museum in 1999. Today the Opera House is a fully functioning Performing Arts Theater.

- How do you propose to restore/rehabilitate it?
  - **Our Public Works department and contractor Central Sierra Construction, Inc. (CSCI) met with the Comstock Preservation and History Officer (Kristen Brown) to discuss the best approach for the rehabilitation of the front doors and the south wall windows at Piper's. Kristen explained that the doors and windows can be restored through a specific epoxy material (Advance Repair Technology) and molding/hardware for the doors can be replaced with like materials where needed. After this meeting, CSCI provided a cost estimate<sup>1</sup> that has been included in this application (Attachment A). Storey County will consult with Kristen Brown and Carla Cloud throughout the restoration process to ensure work meets the *Secretary of the Interior Standards for Rehabilitation*.**
  
- Who will be doing the work?
  - **Storey County currently has a bid from CSCI for all the materials and labor for this project.**
  
- What is the timeline for the project?
  - **CSCI estimates a total of 10 weeks for the project. Storey County estimates it may take ~12 weeks (dependent on weather).**
  
- Who holds title to the property?
  - **Storey County**

## 2. Building Use/Community Involvement:

- How and by whom will the facility be used?
  - **Piper's Opera House is a Performing Arts Center that is open to the public. It hosts theatrical performances, concerts, non-profit events, and more to the community and visitors year-round.**

---

<sup>1</sup> Please note that the cost estimate CSCI provided for the windows includes restoring eight windows and this application only includes the restoration of the south wall windows, as SHPO has notified Storey County staff it is critical to get the windows restored within this current construction season. The County does plan to restore all eight windows as soon as feasible and will continue to pursue funding and grant opportunities. If the County is awarded CCCHP funds, and there are funds available for all eight windows, please let us know.

- Who will be responsible for management of the building and its programs/activities?
  - **Storey County and the Virginia City Tourism Commission (department within the County) will be responsible for the management of the building and its programs/activities.**
  
- How has the community been involved in your project?
  - **The continual preservation of Piper's Opera House is a collective goal of the community and Piper's Opera House is within the Comstock Historic District. This project was brought to the County's attention through the 2020 amended Historic Structures Report (**Attachment B**) and the Public Works department, who conduct routine inspections of the historic resources in our County.**
  
- How will the community continue to be involved in your project?
  - **The community will not be directly involved with the project. The County will work with a contractor that has technical expertise working with historic buildings. The community will be able to use the front entry doors when they visit Piper's Opera House after the project is complete.**
  
- How will the community continue to be involved in the use of the building?
  - **The door and window rehabilitation project will ensure the continued use of this historic building. As mentioned above, Piper's Opera House is open to the public. It hosts theatrical performances, concerts, non-profit events, and more to the community and visitors year-round.**
  
- How are your restoration/rehabilitation plans related to the uses of the building?
  - **The rehabilitation of the doors and south wall windows will help Storey County preserve the historic features of this building. Additionally, as the front entry doors are the main entrance to the building, they are one of the first features of the building that the casual observer notices.**
  
- What importance to tourism (cultural or otherwise) will the facility have?
  - **One million people visit Virginia City annually, and historic buildings such as Piper's Opera House attract a lot of attention as many of the tourists' main activities are visiting and photographing the historic buildings. Additionally, as stated above, the Opera House hosts theatrical performances, concerts, non-profit events, and more to the community and visitors year-round. These year-round events make the Opera House a vital cultural center for the Comstock.**

### 3. Project Support/Financial:

- What specific contributions (cash, land, labor, materials, etc) have been provided toward the project from the community and/or other sources?
  - **Currently, the Storey County Public Works Building and Grounds Manager (B&G Manager) and the Grants Manager have provided their staff time for this project. The B&G Manager has assessed the need to restore the doors, solicited bids, met with the Comstock Preservation and History Officer on the project, and reviewed the proposed work with the contractor. The Grants Manager has compiled the CCCHP grant application.**
- What grants and additional funding (last three years), including amounts, has the organization received or will receive for this project?
  - **Although Piper’s Opera House has numerous rehabilitation and maintenance projects that need to be completed in the future, the County believes that we will be able to complete the proposed project in its entirety with the requested funds from CCCHP.**
- What additional contributions are projected to complete the project?
  - **Storey County Staff (B&G Manager and Grants Manager) will dedicate staff time to ensuring the successful completion of this project. Storey County will also provide a \$20,000 cash match to ensure the successful completion of this project.**
- How will your facility sustain itself financially in the future?
  - **Storey County will continue to sustain itself through current means of revenue generated by business, property, and sales tax; licensing fees and permits; and through grant funding for the preservation of its historic buildings.**
- Please provide evidence that you can implement the project and maintain a viable program in the future.
  - **Storey County has received numerous grant awards through SHPO for the rehabilitation and maintenance of Piper’s Opera House and have successfully completed the awarded grant projects. The successful completion of these projects demonstrates that County employees are knowledgeable of County endeavors, including the preservation of its historic structures, and can maintain a viable program in the future.**

### 4. Planning:

- If your project includes planning, please describe the process.

- **A 2020 amended Historic Structures Report (HSR) for Piper's Opera House (Attachment B) provided the County with the preservation and maintenance needs of the building.**
  
- Who will participate in the planning?
  - **The need for this project was previously identified in the 2020 amended HSR.**
  
- Who will coordinate it?
  - **The need for this project was previously identified in the 2020 amended HSR.**
  
- How will the community be involved?
  - **The need for this project was previously identified in the 2020 amended HSR.**
  
- If your project is based on previous planning, please describe.
  - **The need for this project was previously identified in the 2020 amended HSR.**



## **CCCHP Grant FY23/24 Grant Application – Piper’s Opera House Project**

### **2.B.1 – Paragraph describing use of property and cultural center programming**

The current Piper’s Opera House was constructed in 1885, after two other iterations of the Opera House were burned to the ground (Great Fire of 1875 and another fire in 1883). At its height, the Opera House was one of the finest theater houses in the Western United States. The theater attracted many famous performers such as Buffalo Bill, Maude Adams, Edwin Booth, and Al Jolson.

Today Piper’s Opera House is still a fully functioning performing art theater. The Opera House hosts numerous cultural programs such as, but not limited to, theatrical performances, comedy shows, concerts, non-profit events, and dances. These year-round events make the Opera House a vital cultural center for the Comstock.

Property Information

Parcel ID	001-082-14	Parcel Acreage	0.2200
Tax Year	2024	Assessed Value	206,920
Land Use Group	COM	Tax Rate	0.0000
Land Use	400 - General Commercial	Tax Cap	High Cap
Zoning	CR	Tax Cap Returned	
Tax District	010	Total Tax Fiscal Year (2024 - 2025)	\$0.00
Site Address	12 N B ST VIRGINIA CITY	Total Unpaid All Years	\$0.00
Neighborhood	VCMP - Virginia City Mid Town Public		

CCCHP Grant FY23/24 Grant Application  
- Piper's Opera House Project

2.B.2 - County Assessor Print out

Assessments

Taxable Value	Land	Building	Per. Property	Totals
Residential	0	0	0	0
Com / Ind.	0	0	0	0
Agricultural	0	0	0	0
Exempt	58,560	532,639	0	591,199
Pers. Exempt				0
<b>Total</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>

Assessed Value	Land	Building	Per. Property	Totals
Residential	0	0	0	0
Com / Ind.	0	0	0	0
Agricultural	0	0	0	0
Exempt	20,496	186,424	0	206,920
Pers. Exempt				0
<b>Total</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>

	New Land	New Const.	New P.P.
Residential	0	0	0
Com / Ind.	0	0	0
Agricultural	0	0	0
Exempt	0	0	0
<b>Totals</b>	<b>0</b>	<b>0</b>	<b>0</b>

Assessor Descriptions

Year	Assessor Descriptions	Subdivision	Section	Township	Range	Block & Lot
Current Year 2024						
2024	PARCEL MAP ID : LOT : BLOCK : 83 L17-22, BLK 83, RNG A TOWN : VIRGINIA CITY					

No Billing Information

**Payment History**

	Fiscal Year	Total Due	Total Paid	Amount Unpaid
+	(2017 - 2018)	\$2,328.97	\$2,328.97	\$0.00
+	(2016 - 2017)	\$5,110.09	\$5,110.09	\$0.00
+	(2015 - 2016)	\$5,057.82	\$5,057.82	\$0.00
+	(2014 - 2015)	\$601.81	\$601.81	\$0.00
+	(2013 - 2014)	\$4,020.44	\$4,020.44	\$0.00

Show 2 More (2)

**Related Names**

**CURRENT OWNER FOR 2024 (2024 - 2025)**

<b>Name</b>	STOREY COUNTY
<b>Mailing</b>	PO BOX 176
<b>Address</b>	VIRGINIA CITY, NV, 89440
<b>Status</b>	Current

No Personal Property

Structure 1 of 2

Structure 2 of 2

**Sales History**

Year	Document #	Document Type	Sale Date	Sold By	Sold To	Price
2017	126900	GRANT BARGAIN SALE DEED	12/20/2017	STOREY COUNTY SCHOOL DISTRICT	STOREY COUNTY	\$300,500
2014	119867	GRANT BARGAIN SALE DEED	1/22/2014	PIPERS OPERA HOUSE PROGRAMS INC	STOREY COUNTY SCHOOL DISTRICT	\$282,310

No Genealogy

No Taxing Bodies Information


### Disclaimer

Storey County presents the information on this web site as a service to the public. We have tried to ensure that the information contained in this electronic document is accurate. Storey County makes no warranty or guarantee concerning the accuracy or reliability of the content at this site or any other sites to which we link. Determining the accuracy and reliability of this information is the responsibility of the user. Storey County shall not be liable for errors contained herein or for any damages in connection with the use of the information contained herein. Due to data update schedules, the information on this web site may not reflect the most recent changes to property information.

For questions about property assessment information please contact 775-847-0961

# Photo Points for Piper's – 2.B.3 Photographs

CCCHP FY23/24 Grant Application



Legend  
Photo

100 ft

Google Earth

CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs



Photo 1: East elevation (front entrance) of Piper’s Opera House




Photo 2: South elevation

PLEASE NOTE: ADDITIONAL PHOTOS, INCLUDING THE INTERIOR ARE INCLUDED IN ATTACHMENT B (HSR REPORT)

CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs



Photo 3: West elevation



Photo 4: North elevation

CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs




Photo 5: East elevation – 2 of 12 doors to be restored  
(doors are presented here from the south to north)




Photo 6: East elevation – 4 of 12 doors to be restored



CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs



Photo 7: East elevation – 6 of 12 doors to be restored



Photo 8: East elevation – 8 of 12 doors to be restored

CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs



Photo 9: East elevation – Close up – 8 of 12 doors to be restored



Photo 10: East elevation – 10 of 12 doors to be restored

CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs



Photo 11: East elevation – Close up – 10 of 12 doors to be restored




Photo 12: East elevation – 12 of 12 doors to be restored

CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs



Photo 13: Overview of the three south wall windows over ballroom



Photo 14: Window 1 of 5 (windows are presented here from the west to east)

CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs



Photo 15: Window 2 of 5



Photo 16: Window 3 of 5

CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs



Photo 17: Overview of two south wall windows over Corner Bar




Photo 18: Window 4 of 5

CCCHP Grant Application – Piper’s Opera House Front Doors  
2.B.3 – Photographs




Photo 19: Window 5 of 5

## CCCHP Grant FY23/24 Grant Application – Piper’s Opera House Project

### 2.B.4– Organization Information

#### 1. Storey County Mission Statement:

From the first discovery of gold in 1859, through the silver mining boom in the 1860s and 70s, to this day, Storey County claimed its place on the map and is firmly entrenched in the importance of U.S. History. Established as a county in 1861, Storey was recognized as a National Historic Landmark in 1961 and then listed on the National Register of Historic Places (Comstock Historic District).

Annually Virginia City sees one million visitors and tourism is vital to the county's stability and growth. Preservation of the historic structures is a high priority, ensuring that future generations may be able to enjoy and learn of the Historic Comstock Lode.

The County is also home to the Tahoe-Reno Industrial Center (TRIC), which is the largest industrial center of its kind in the world. The continued growth and prosperity of the TRIC, contributes to the rich history of Storey County.

As such, Storey County's mission is the welfare of its residents and visitors through historic preservation and industrial growth which has made the county famous.

#### 2. Storey County Board of Commissioners:

- Julian "Jay" Carmona, Chairman
- Clay Mitchell, Vice Chairman
- Lance Gilman, Commissioner

#### 3. Long Range Plan:

- The published Capital Improvement Plan (CIP) is included as **Attachment C**. The CIP shows the projects that the Board of Commissioners has approved for Piper’s Opera House (highlighted in yellow in Attachment C).
  - The 2020 amended HSR report contains a multitude of vital preservation projects for Piper’s that will cumulatively cost upwards of \$20 million or more. As the County is within the Comstock Historic District, but does not have a historic preservation specialist position, we recognize the need to include the SHPO/Comstock Historic District Commission in the future for the long-range planning of Piper’s. The County believes this collaboration will help us prioritize the preservation needs of the building and the County will be able to better incorporate important preservation projects for Piper’s into the County’s CIP (taking into consideration available funding).

#### 4. Activities for the past fiscal year

Piper’s Opera House has hosted numerous events this past fiscal year. Some of them are coordinated and hosted by the Virginia City Tourism Commission (VCTC), and others are room rentals managed by VCTC. These activities are listed below:

- Bingo Nights (third Thursday of each month)



- Guided Tours
- Concerts
- Dances/Balls
- Musicals and Plays
- Lectures
- Full Moon Investigations
- Comedy Nights
- Non-profit events (dances, fundraisers, etc.)

#### 5. **Current and Previous CCCHP Grant Status for Piper's Opera House**

- As part of the research for the 2020 amended Historic Structures Report (HSR) for Piper's Opera House, the County and Dube Group Architecture found that Piper's Opera House received approximately 15 grants from the Commission for Cultural Affairs (now known as CCCHP) from 1995-2009. Please see **Attachment D**.
  - Storey County has closed out all previous CCCHP grants for Piper's Opera House.
  - Please note that the building was sold to the School District in 2014. Then the County purchased it from the School District in 2017.

#### 6. **Past funding and future funding**

- **Past funding:** The County has not received grant funding in the last three years for Piper's Opera House
  - The County received a Historic Preservation Fund (HPF) grant for the amended 2020 Historic Structures Report (Attachment A) for Piper's Opera House.
- **Future funding:** The County used the 2020 amended Historic Structures Report for Piper's Opera House (Appendix 1, pgs. 4-5) to submit a federal appropriation request for \$1 million to rehabilitate the west wall.
  - *Project Summary:* Stabilize A Street, install a retaining wall between A Street and Piper's Opera House, install a French Drain to redirect spring and ground water, and stabilize the building's west wall.
  - For this request, the County expects to be notified in September 2024. However, as this is a federal appropriation request, the timeline is subject to change. The County will continue to dedicate both capital improvement funds and grant funds to the preservation and maintenance of Piper's Opera House.

## 2.0 | LIST OF PRIOR GRANTS 1995 – 2009

Piper's Opera House  
List of Prior Grants  
1995 - 2009

Grant Cycle	Covenant Expires	Grant Award	Scope of Work
CCA-95-15		\$375,000.00	Purchase of Piper's Opera House
CCA-97-15		\$200,000.00	Structural reinforcement; plumbing; fire sprinkler installation; electrical work; general work on the building; 1st year's mortgage payment of \$35,000.00; Supervisory coordination; mobilization; warranties & bonds; demolition; earthwork; concrete; rough carpentry & material; fire protection; fire alarm system; profit & overhead; mortgage interest; grants administrator; insurance; architectural; sewer connection; electrical; acoustical consultant; sanihut
CCA-99-15		\$200,000.00	USDA loan repayment; heating system installation (hot water boiler system which will be for basic needs but designed so it can be added on to in future to complete the system; administrative costs; roof R-38 insulation; debris box (for the old wood removed from the side of the building); ADA bathrooms (One male & one female W/C that meets ADA standards on auditorium level); redwood siding & R-19 insulation (North wall & possibly west wall will receive new redwood siding); electrical work (rerun some minor runs of electrical that is not in conduit & put into conduit)
CCA-00-15		\$199,940.00	Replacement of exterior siding on west, north, & east walls, to include removal of old siding, insulation, replacement redwood siding, priming & painting; restoration & replacement of front entry doors, to include 12 doors, jambs, hardware & glass; mortgage payment; upgrade electrical system; contingency fund. May have also included bathrooms.
CCA-01-15		\$245,000.00	ADA elevator; carriage house retrofit/elevator preparation; attic restoration; electrical upgrade; exterior restoration; front facade restoration; fire & safety requirements; grants management; HVAC; ADA fire ramp; Excavation; Kitchen (Bar); Office (prop room); restrooms; mortgage
<b>32-01-ML-1163</b> <b>(SAT grant)</b>		\$400,000.00	Production of Historic Structures Report or Preservation Plan; property repair to include installation of an ADA elevator; painting, restoration of the historic 1877 brick façade, and excavation and stabilization of the area beneath the auditorium floor
CCA-02-15	12/31/2023	\$284,250.00	Will support renovation, repair & rebuilding of existing doors; brick façade stabilization work; reinforce doorway pilasters; rebuild missing historic windows; repair/replace siding on carriage house; repair arched windows & frames; repaint/repair brick; painting; new cupola on existing roof. (The following items appear to have been removed via a scope of work amendment: restoration of B street balcony; general conditions; O&P; escalation; design contingency; construction contingency; grant administration)

Piper's Opera House  
List of Prior Grants  
1995 - 2009

Grant Cycle	Covenant Expires	Grant Award	Scope of Work
CCA-03-15		\$75,000.00	Administration activities in executing the grant work; repair facade finish (bricks are to be scraped, brushed, sealed & painted); windows & doors are to be scraped, prepared & painted; trim is to be scraped, prepared & painted; restoration of "Target" sign & mounted back in original position; structural engineering design work for ground floor support for the east auditorium wall, east end of the auditorium floor, & other ground level support for the east end of the ground floor; construction of ground level supports; concrete floor work on the ground level corner bar lobby including floor heating. May have also included removal of c. 1960s muslin and applying fire retardent to walls and balcony.
CCA-04-13	12/31/2025	\$127,000.00	Administration; contract/labor; engineering/architecture; materials & supplies. The report states that the following was done: curtain drain, sewer plumbing for saloon/kitchen/restrooms, preparation for concrete subfloor; steel reinforcement of burnt floor support beams, pouring concrete, installing hydronics, installing wooden floor. The grant report states that approximately \$40,000 of the \$127,000 was used for the completion of CCA-03 grant work, namely the plywood on the east auditorium wall and the installation of tension rods on the wall support beam.
CCA-05-18	12/31/2025	\$299,000.00	Restore entry foyer & bar; straighten the main stairs; complete gallery; ground level excavations with dressing rooms; restrooms & bar on ground level
CCA-06-19 and CCA-06-29	12/31/2027	\$204,000.00	<b>06-19 (\$200,000)</b> --Will support completion of the entryway; saloon hydronics & flooring; complete northside access; ground level excavations; steel work; concrete floor; partition wall; administration & engineering & architecture <b>06-29 (\$4,000)</b> --Saloon reconstruction
CCA-07-28	12/31/2058	\$120,000.00	North door work: door & concrete foundation; excavate back wall of restroom; place sewer lines; pour concrete floor; lay down sleepers & hydronics & sub flooring; build partition walls; install electrical & plumbing in the walls & ceiling; sheetrock, spackle & paint walls; install flooring, maple in hallway, tile in restrooms; install restroom fixtures; install drainage in dirt floor

Piper's Opera House  
 List of Prior Grants  
 1995 - 2009

Grant Cycle	Covenant Expires	Grant Award	Scope of Work
CCA-08-19	12/31/2059	\$110,000.00	Preserve south exterior: scrape & caulk; prime & paint body & trim (oil based); lift rental; preserve 7 double doors/windows; restore 7 thresholds, carriage house upper windows; carriage exit doorway, SE original balcony; replicate original cupola; Complete front half of saloon: ceilings, walls, floor, electrical; Hallway to N. door: ceiling, boiler room & W. walls, N. door wall; Elevator hallway/gift shop: ceiling, walls, carriage house interior doorway; Auditorium level stairway: mopboard, chair rail, ceiling, walls, stair treads, soffet repair, & finish trim; travel: six (6) round trips from Virginia City to Carson City--per month for 18 months.
CCA-09-20	12/31/2060	\$126,000.00	Architectural Services (recording existing conditions; design work for bathroom, fire exit corridor, north double doors, loading dock & construction drawings); Architectural Services (historic finishes analysis of interior); Engineering Services (baseline structural report to include main floor support & foundation, roof trusses & existing balcony, review of strengthening plans, review of "bulge" northwest wall, "A" Street retaining wall/soil failure); Electrical Engineering Services (record of existing conditions, evaluation of existing conditions, suggested remedies for code compliance); Contracting Services (record & locate all previous work completed at Piper's within five years, drawings, structural elements--elevation/survey records, stability/movement records, boiler room operating & safety procedures, labeling & safety signage, boiler repairs & system update; Construct Loading Ramp (exterior north side); Finish Stair Lobby; Finish Fire Corridor; Complete Bathrooms & Exit Corridors; Structural Repairs; Boiler Upgrades

**NEVADA COMMISSION FOR CULTURAL  
CENTERS & HISTORIC PRESERVATION (CCCHP)  
GRANT APPLICATION**



NEVADA  
**STATE HISTORIC  
PRESERVATION OFFICE**

**APPLICATION BUDGET**

**APPLICANT:** Storey County

**1. Personnel:** CCCHP Grant funds cannot be used to compensate personnel. Match is limited to work related to the grant project.

	Position Title	Hours	Hourly Rate (HR)	Does HR include fringe benefits?	% of HR that is fringe benefit	Amount of fringe benefit	Match (Non-CCCHP Grant)
a.							\$ 0.00
b.							\$ 0.00
c.							\$ 0.00
d.							\$ 0.00
e.							\$ 0.00
f.							\$ 0.00
g.							\$ 0.00
h.							\$ 0.00
i.							\$ 0.00
j.							\$ 0.00
						<b>Sub-total:</b>	\$ 0.00

**2. Travel:** CCCHP Grant funds only cover travel for contracted service providers. This can be companies or individuals. Travel expenses must follow U.S. General Service Administration (GSA) rates.

	Contracted service provider	Match	CCCHP Grant	Total Amount
a.				\$ 0.00
b.				\$ 0.00
c.				\$ 0.00
d.				\$ 0.00
e.				\$ 0.00
f.				\$ 0.00
g.				\$ 0.00
h.				\$ 0.00
i.				\$ 0.00
j.				\$ 0.00
	<b>Sub-total:</b>	\$ 0.00	\$ 0.00	\$ 0.00



**NEVADA COMMISSION FOR CULTURAL  
CENTERS & HISTORIC PRESERVATION (CCCHP)  
GRANT APPLICATION**



NEVADA  
**STATE HISTORIC  
PRESERVATION OFFICE**

**APPLICATION BUDGET Cont.**

**APPLICANT:** Storey County

**4. Operating: List estimated operating expenses relating to the proposed project.**

Note: CCCHP Grant funds cannot be used for administrative costs.

	# of	Rate	Flat Rate	Match	CCCHP Grant	Total Amount
a.	Photocopying					\$ 0.00
b.	Film and Processing					\$ 0.00
c.	Maps					\$ 0.00
d.	Postage					\$ 0.00
e.	Telephone					\$ 0.00
f.	Utilities					\$ 0.00
g.	Supplies (specify)					\$ 0.00
						\$ 0.00
						\$ 0.00
						\$ 0.00
						\$ 0.00
						\$ 0.00
h.	Other (specify)					\$ 0.00
						\$ 0.00
						\$ 0.00
				<b>Sub-total:</b>	\$ 0.00	\$ 0.00
						\$ 0.00

**5. Other (please specify or attach detailed budget):**

	Rate	Match	CCCHP Grant	Total Amount
a.				\$ 0.00
b.				\$ 0.00
c.				\$ 0.00
d.				\$ 0.00
e.				\$ 0.00
f.				\$ 0.00
g.				\$ 0.00
h.				\$ 0.00
i.				\$ 0.00
			<b>Sub-total</b>	\$ 0.00
				\$ 0.00



**NEVADA COMMISSION FOR CULTURAL  
CENTERS & HISTORIC PRESERVATION (CCCHP)  
GRANT APPLICATION**



NEVADA  
**STATE HISTORIC  
PRESERVATION OFFICE**

**APPLICATION BUDGET Cont.**

**APPLICANT:** Storey County

**6. Section #1- 5 Subtotals:**

		Match	CCCHP Grant	Total Amounts
1.	Personnel	\$ 0.00		\$ 0.00
2.	Travel	\$ 0.00	\$ 0.00	\$ 0.00
3.	Contractual Services	\$20,000.00	\$107,375.00	\$ 127,375.00
4.	Operating	\$ 0.00	\$ 0.00	\$ 0.00
5.	Other	\$ 0.00	\$ 0.00	\$ 0.00
	Sub-total	\$20,000.00	\$107,375.00	\$ 127,375.00

**7. Requested CCCHP Grant Total:** \_\_\_\_\_ \$107,375.00

**8. Potential Match:** \_\_\_\_\_ \$20,000.00

**9. Proposed Project Costs Grand Total:** \_\_\_\_\_ \$ 127,375.00

**Note:** For assistance with completing the budget, please refer to the CCCHP Grant Handbook.

Topics

- Match
- Procurement of Goods, Services, & Contracts

Forms

- Value of Donated Material
- Value of Donated Equipment
- Value of Donated Labor



*Central Sierra Construction, Inc.*

2551 Precision Drive Suite C Minden, NV 89423

775 267-2943 NV LIC # 23444B

4-19-2024

**PIPERS OPERA HOUSE BALL ROOM WINDOW RESTORATION**

**LINE ITEM SUMMARY**

Restore 8 Wood Windows	\$28,500.00
Frame Restoration	\$21,600.00
Painting	\$6,500.00
<b>TOTAL BID</b>	<b>\$56,600.00</b>

**CLARIFICATIONS:** No off-hour wages. No permit fees.

**Restore 8 Wood Windows** - Includes restoration of 8 existing wood window assemblies. 3@ South wall-Ball Room, 3@ North wall-Ball Room, 2@ South side Front living space rooms. Remove and transport 16 individual sash assemblies to CSCI shop for full restoration including milling of missing and deteriorated wood parts. Other restoration work with Advanced Repair Technology products.

**Labor**- Includes all labor needed for the restoration of existing frames to accept restored window sash assemblies.

**Painting**- Includes painting of restored windows and restored frames.



*Central Sierra Construction, Inc.*

2551 Precision Drive Suite C Minden, NV 89423

775 267-2943 NV LIC # 23444B

4-19-2024

**PIPERS OPERA HOUSE FRONT DOOR RESTORATION**

**LINE ITEM SUMMARY**

Restore Existing Doors	\$40,600.00
Frame/Transom Labor	\$36,300.00
Restoration Materials	\$6,000.00
Replacement Hardware	\$3,000.00
Painting	\$3,000.00
Misc. Materials	\$3,100.00
<b>TOTAL BID</b>	<b>\$92,000.00</b>

**CLARIFICATIONS:** No off-hour wages. No permit fees.

**Restore Existing Doors-** Includes restoration of 12 existing wood doors on front (east) elevation of the Opera House. Doors to be removed from site and transported to CSCI's shop for restoration work there, probably 4 at a time.

**Labor-** Includes all labor needed for the restoration of existing frames and transoms to accept restored doors. New threshold and installation of any new replacement hardware.

**Restoration Materials-** Includes all epoxy restoration materials (Advance Repair Technology) needed to restore existing frames and transoms. Also any needed replicated moldings for missing components

**Replacement Hardware-** Includes a budget to replace door hardware as needed for operational doors.

**Painting-** Includes painting of restored doors and restored frames and transoms.

**Misc. Materials-** Includes any needed misc. materials for the restoration work.

**Timeline of work.**

Remove and restore doors at CSCI shop	4 weeks
On site replacement/restoration work	6 weeks
<b>Total time for project</b>	<b>10 weeks</b>

---

# PIPER'S OPERA HOUSE

## AMENDMENT TO THE HISTORIC STRUCTURES REPORT



Prepared for:  
Storey County

Prepared by:  
Pete Dubé, NCARB, AIA, Historical Architect  
Paul Ferrari, P.E., Civil Engineer  
Sean Frey, P.E., Mechanical Engineer  
Ed Gansberg, Electrical Designer

Dubé Group Architecture  
458 Court Street  
Reno, NV 89501

September 28, 2020

---

## TABLE OF CONTENTS

<b>A. COVER SHEET</b>	<b>1</b>
<b>B. TABLE OF CONTENTS</b>	<b>2</b>
<b>C. EXECUTIVE SUMMARY</b>	<b>5</b>
1.0 Amendment Purpose and Scope	5
2.0 Research to Prepare Amendment	5
3.0 Major Findings	5
Plumbing	5
Heating, Ventilation, and Air Conditioning	6
Electrical	6
Structural and Seismic	6
Architectural	6
<b>D. INTRODUCTION</b>	<b>7</b>
1.0 Architectural / Engineering Evaluation and Documentation Methodology	7
2.0 Funding	7
3.0 Acknowledgements	8
<b>E. DOCUMENTATION AND CHRONOLOGY OF RECENT PHYSICAL CHANGES</b>	<b>9</b>
1.0 Improvements to Piper’s Opera House 1995 – 2002	9
2.0 Improvements to Piper’s Opera House 2002 – 2011	13
<b>F. INVESTIGATION AND EVALUATION OF SYSTEMS</b>	<b>15</b>
1.0 Plumbing	15
2.0 Fire Protection	16
3.0 Heating, Ventilation, and Air Conditioning (HVAC)	17
4.0 Electrical and Communications	19
Electrical Service	19
Lighting	20
Fire Alarm / Security	23
Telephone	23
5.0 Structural and Seismic	24

6.0 Architectural	25	
Building Exterior	25	
Roofing	25	
Siding	29	
1863 Brick Building	29	
1883 Auditorium Building	30	
Metal Elements	32	
Cast Iron Piers	32	
Railings	32	
Wood Elements	33	
Stairs	33	
Windows and Doors	34	
1863 Brick Building	34	
1883 Auditorium Building	35	
Building Interior	37	
Basement	37	
Old Corner Bar	37	
Lobby	37	
Carriage House	37	
Accessible Restrooms	37	
Required Means of Egress	40	
Auditorium Level	42	
Lobby	42	
Bridal Room and Catering Kitchen	42	
Carriage House	47	
Auditorium	48	
Opera Boxes	50	
Storage	52	
Accessible Means of Egress	53	
Stage	55	
Lobby Staircase to Balcony	58	
Balcony	60	
Attic	62	
7.0 Building Accessibility	65	
8.0 Building Code Review	66	
Occupancy Classification and Use	66	
Special Detailed Requirements Based on Occupancy and Use	68	
General Building Heights and Areas	68	
Type of Construction	68	
Means of Egress	68	
Plumbing Fixtures	69	

<b>G. RECOMMENDATIONS FOR TREATMENT</b>	<b>71</b>
1.0 Plumbing	71
2.0 Fire Protection	71
3.0 Heating, Ventilation, and Air Conditioning (HVAC)	71
4.0 Electrical and Communications	71
5.0 Structural and Seismic	71
6.0 Architectural	72
<b>H. PHASING AND COSTS</b>	<b>74</b>
1.0 Phasing	74
2.0 Costs	74
<b>I. APPENDICES</b>	<b>76</b>
1.0 Structural Report	78
2.0 List of Prior Grants 1995 – 2009	144
3.0 Bibliography of Record Drawings 1995 – 2009	148
4.0 Plans	154
Historic American Buildings Survey Piper’s Opera House	
Reroof of Piper’s Opera House	
Phase One Restoration of Piper’s Opera House	
Phase 2-b Siding for Piper’s Opera House	
Elevator for Piper’s Opera House	
Elevator Shop Drawings	
Piper’s Opera House Façade Stabilization	
A Historic Restoration for Piper’s Opera House	
Theater Renovation	
Piper’s Opera House Electrical Asbuilt	
Loading Dock and Driveway Improvements to the Piper’s Opera House	
Restroom Improvements to the Piper’s Opera House	
Piper’s Opera House Existing Conditions	

## C EXECUTIVE SUMMARY

### 1.0 Amendment Purpose and Scope

In March of 2020, Dubé Group Architecture (DGA) was retained by Storey County to prepare the following Amendment to the Historic Structures Report for Piper's Opera House, located at 12 North B Street, Virginia City, NV. This document is intended to update the existing conditions and recommendations contained in the Historic Structures Report prepared by van Dijk Westlake Reed Leskosky in 2002.

The amendment process was necessitated due to the passage of time and change of ownership of the property. When the original report was prepared, Piper's Opera House was owned and managed by Piper's Opera House Programs, Inc., who subsequently sold the property to the Storey County School District in January 2014. In 2017, the property was acquired by Storey County and is managed by the Virginia City Tourism Commission. Piper's Opera House Programs, Inc., continues to provide oversight and is a 501c3 non-profit organization focusing on grants and fundraising.

### 2.0 Research to Prepare Amendment

Research included a review of documents and plans provided by private and public archives including the State Historic Preservation Office, Comstock Historic District Commission, Piper's Opera House, and Storey County.

- Review of van Dijk Westlake Reed Leskosky's Historic Structures Report and Preservation Plan. Volume One includes the investigation, documentation, analysis and recommendations for the rehabilitation and restoration of the Piper's Opera House. Volume Two includes the Geotechnical Report, Survey and Civil Concept Drawings, Structural Concept Drawings, Cost Estimate Detail and Narratives.
- Research to locate the previous grant products (drawings, reports, etc.) from the fourteen Commission for Cultural Affairs (CCA) grants received between 1995-2009 in order to assess and evaluate what was actually constructed as well as existing conditions of that work.
- Field surveys consisting of detailed but non-destructive building investigations to assess the resource.

### 3.0 Major Findings

#### Plumbing

The existing plumbing system is adequate having been upgraded in 1999.

Proposed treatment recommendations include adding a backflow preventer and pressure reducing valve at the water main.



### **Heating, Ventilation, and Air Conditioning**

The existing propane-fired, fin tube boiler feeds a hydronic loop that serves a radiant floor heating system on the basement level (B Street) and is connected to multiple hydronic fan coils distributed throughout the facility. These fan coils are noisy during operation and cannot be used during performances. There is no direct ventilation as required by current code. There is no cooling with the exception of a portable air conditioner at the stage and an electric package window unit in the tech office.

Proposed treatment recommendations include replacement of fan coils with radiant floor heating in the auditorium, natural ventilation and evaporative cooling.

### **Electrical**

The existing electrical service is 120/208 volts, 3-phase, 4 wire, 400 amps disconnect switch, fed overhead from an NV Energy power pole. This service then distributes to 5 interior panels.

Proposed treatment recommendations include upgrading the service to accommodate future plans, replacement of keyless sockets with appropriate light fixtures, new emergency building generator, and upgrading illumination levels including emergency egress lighting.

### **Structural and Seismic**

Overall, the current structural condition of the building is relatively sound due to timely and appropriate response to structural deficiencies that occurred since 1997, including structural stabilization of the east and south facades of the 1863 brick building, strengthening of the auditorium floor, and structural repairs to columns and trusses. These actions to remedy structural deficiencies prevented what could have been catastrophic collapses.

Proposed treatment recommendations include roof truss support, wall column buckling, column repair at the basement level main lobby, additional auditorium floor support, water seepage from A Street, and balcony framing and support.

### **Architectural**

The building is in good condition overall, having undergone numerous renovations including repair / rehabilitation of entry doors and windows, replacement of siding and roofing, insulated building envelope, new accessible restrooms, tenant improvements to the Carriage House, lobbies on the Basement level and auditorium level, and the Old Corner Bar.

Proposed treatment recommendations include building egress from basement, accessible means of egress from auditorium, catering kitchen, completing stairs from auditorium to balcony, preservation of the balcony, and reconstructing the hipped roof ventilator.

## D INTRODUCTION

### 1.0 Architectural / Engineering Evaluation and Documentation Methodology

An architectural / engineering evaluation of the building was conducted by the project team starting June 2020 and continuing through the end of August 2020 consisting of detailed but non-destructive building investigations to assess the resource. Each discipline reviewed the appropriate section of the Piper's Opera House Historic Structures Report and Preservation Plan (van Dijk et al., 2002) and existing building plans detailing work funded wholly or partially by CCA and other preservation grants in context with actual work completed in the field. The following building systems were investigated:

- Plumbing
- Fire Protection
- Heating, Ventilation, and Air Conditioning (HVAC)
- Electrical and Communications
- Structural and Seismic
- Architectural
- Building Accessibility
- Building Code Review

### 2.0 Funding

The Amendment to the Historic Structures Report for Piper's Opera House has been financed in whole or in part with federal funds through a Historic Preservation Fund matching grant-in-aid from the National Park Service, U.S. Department of Interior, and administered by the Nevada Department of Conservation and Natural Resources, State Historic Preservation Office.

The contents and opinions, however, do not necessarily reflect the views or policies of the United States Department of the Interior or the State Historic Preservation Office.

This program receives federal financial assistance for identification and protection of historic properties.

Under Title VI of the Civil Rights Act of 1964, Section 504 of the Rehabilitation Act of 1973, and the Age Discrimination Act of 1975, as amended, the U.S. Department of the Interior prohibits discrimination on the basis of race, color, national origin, disability or age in its federally assisted programs.

If you believe you have been discriminated against in any program, activity, or facility as described above, or if you desire further information, please write to:

CHIEF, OFFICE OF EQUAL OPPORTUNITY PROGRAMS  
UNITED STATES DEPARTMENT OF THE INTERIOR, NATIONAL PARK SERVICE  
1201 EYE STREET, NW, WASHINGTON, DC 20005

### 3.0 Acknowledgements

This report is the result of cross-discipline collaboration and is made possible through the involvement of the following team members:

#### **Storey County**

Austin Osborne, County Manager, on behalf of the Board of County Commissioners

Lara Mather

Mike Northan

Whitney Brunson

Joe Curtis

#### **State Historic Preservation Office**

Rebecca Lynn Palmer, State Historic Preservation Officer

Robin K. Reed

Carla Hitchcock

Kristen N. Brown

#### **Comstock Historic District Commission**

Michael A “Bert” Bedeau

#### **Dube Group Architecture**

Peter R. Dubé, NCARB, AIA | *historical architect*

#### **PF Consultants LLC**

Paul Ferrari, P.E. | *civil engineer*

#### **SGF Engineering**

Sean Frey, P.E. | *mechanical engineer*

#### **Dinter Engineering Company**

Tim Prockish, P.E. | *electrical engineer*

Ed Gansberg | *electrical designer*

Special thanks to the following individuals for graciously sharing drawing files from their archives:

J.P. Copoulos, Architect

Melvyn Green and Associates

DLR Group (successor firm to van Dijk Westlake Reed Leskosky)

## E DOCUMENTATION AND CHRONOLOGY OF RECENT WORK

### 1.0 Improvements to Piper's Opera House 1995 - 2002

We were tasked with locating plans and reports for Work funded through CCA grants during the period 1995 through 2009. We were able to track down a number of drawings prepared by consultants over the years. However, some drawings disappeared, consultants have retired or gone out of business, and much of the Work appears to have been completed or installed without drawings.

We have included a bibliography of construction documents that we collected in the Appendices. It was difficult to definitively assign plans to specific grant cycles because the plans did not list the grant cycle on the cover sheet or title block, and often the improvements spanned multiple grant cycles.

To the best of our abilities, we have made every effort to verify completion of the Work through physical inspections - short of destructive demolition – and, where possible, we have attempted to cross-reference the Work with building plans and grant cycles.

The substantive upgrades below were listed as “Recent Work” and considered either completed or ongoing in the 2002 Historic Structures Report. If we were unable to verify something because either there were no plans, or perhaps the Work was covered up and not visible without destructive demolition, we noted those exceptions.

- **Fire Sprinkler and Fire Alarm System – 1999**

Funded by CCA-97-15, the fire sprinkler system was included in construction documents titled **Phase One Restoration of Piper's Opera House** issued by JP Copoulos Architect (1998). The mechanical engineer was Peterson & Associates, Ltd., and the Index to Drawings included fire protection drawings although we were unable to locate copies to compare design to what was installed. However, the systems are operational and have recently been inspected and tagged by authorities having jurisdiction (AHJ).

The Work has been completed (with exception noted).

- **New Roof Decking and Sheathing – 1999**

Funded by CCA-97-15. In a phone conversation with John Copoulos, he recalled having to issue repair plans to mitigate undisclosed structural deficiencies shortly after close of escrow. Structural repairs to a wood column and cracked roof beam, inspection and repair of deteriorated sheathing, new felt, new cedar shingles and flashing for the entire roof (**including 1863 building**) comprised the construction documents titled **Reroof of Piper's Opera House** issued by JP Copoulos Architect (1997). We were able to confirm plywood sheathing but the structural repairs are covered up with new siding and we were unable to verify.

The Work has been completed (with exception noted).

- **New roof structure and plywood decking over the front (1863) building - 1999**

Funded by CCA-97-15, this Work was included in construction documents titled **Phase One Restoration of Piper's Opera House** issued by JP Copoulos Architect (1998). Structural drawings call for new roof framing and plywood sheathing. The structural engineer, Mel Green, provided photos taken during construction which we used to verify the Work. Additionally, there are exposed areas in the attic where insulation batts are missing and plywood is visible from the underside of the roof.

The Work has been completed.

- **New Stair at Lobby – 1999**

Funded by CCA-97-15, this Work was included in construction documents titled **Phase One Restoration of Piper's Opera House** issued by JP Copoulos Architect (1998). However, as constructed, the B-Street level stair does not match the construction documents. Our research yielded multiple references to funding sources for stairs, along with different configurations.

The Work has been completed (with exception noted).

- **New Heating System and Exhaust Fan in Attic – 1999**

We were unable to locate plans but did find a reference to **Phase Two-A Heating, Specifications** submitted by JP Copoulos Architect on July 26, 1999 to NV SHPO for review and comment and we believe these plans showed the heating system throughout the building including the exhaust fan in the attic and attic insulation.

The exhaust fan is located in the attic on the east elevation. The switch that operates the fan is located in the kitchenette on the auditorium level we confirmed operation.

The heating system is comprised of a propane-fired boiler, associated piping, and fin tube / fan heaters, located in the attic, auditorium, kitchenette, and hallways.

The Work has been completed.

- **New Exterior Siding – 1999**

Funded by CCA-99-15 and CCA-00-15 and included in construction documents titled **Phase Two-B Siding for Piper's Opera House** issued by JP Copoulos Architect (1999). The plans included removing and replacing existing siding with new 1x12 redwood siding over vapor barrier over 5/8" gypsum board over 1/2" plywood sheathing with R-19 batt insulation in stud cavities.

We are unable to determine whether any of the walls are protected by gypsum board without destructive demolition.

The Work has been completed (with exception noted).

- **Quick-change restrooms on stage – 2000**

We were unable to locate any drawings, nor match the Work to a particular grant although possibly CCA-00-15. There are two small spaces stage left against the northwest corner. The larger space includes a lavatory, water closet, and shower stall. The smaller space includes a wall-mounted laundry sink a sheet metal patch on the floor where a water closet was roughed-in at one time but has since been removed.

The Work has been completed (with exception noted).

- **Structural shear walls in the lobby/carriage house space 2001**

The only structural modifications to the lobby/carriage house during the period 1995 – 2002 consist of new interior footings and structural shear walls (see construction documents titled **Phase One Restoration of Piper’s Opera House** issued by JP Copoulos Architect (1998)). The structural plans included new footings and structural shear walls. Because the improvements have been covered up, we are unable to verify this work has been completed.

Modifications post-2002 to present are detailed in Appendix 1.0 Structural Report.

- **ADA compliant, accessible restrooms at the auditorium level 2001**

Funded by CCA-99-15 (and possibly CCA-00-15) and included in construction documents titled **Phase One Restoration of Piper’s Opera House** issued by JP Copoulos Architect (1998). The drawings indicate two unisex accessible restrooms in the general vicinity of the current restrooms but does not match as-built conditions, and in fact, the restrooms as constructed are not accessible.

The Work does not match the plans and the current restrooms on the auditorium level are not accessible.

- **New exit doors, exterior stairways and landings 2001**

Funded by CCA-01-15 and included in construction documents titled **Phase One Restoration of Piper's Opera House** issued by JP Copoulos Architect (1998). A double door was added at stage left on the north side and a single door was added as an exit out of the upper balcony on the north side with new exterior stairs and landing to grade. The plans indicated a new exit door with new exterior stairs and landing to grade on the south side upper balcony which was never installed.

The Work has been completed (with exception noted).

- **Modifications to the roof framing and balcony support structure 2001 — on going**

The only modifications to the roof framing during the period 1995 – 2002 that we were able to confirm were plans to repair a cracked beam (see New Roof Decking and Sheathing – 1999 above) and additional framing in the 1863 building (see New roof structure and plywood decking over the front (1863) building – 1999 above).

We were unable to verify any modifications to balcony support structure during that same time period. As noted in Section E Investigation and Evaluation of Systems, Part 6.0 Architectural Building Interior- Balcony, there is no evidence to support the notion that the balcony was ever modified for occupancy.

Modifications post-2002 to present are detailed in Appendix 1.0 Structural Report.

- **Elevator — 2002 — on going**

Funded by CCA-01-15 and 32-01-ML-1163 (SAT grant) and included in construction documents titled **Elevator for Piper's Opera House** issued by JP Copoulos Architect (2001) and **Elevator Shop Drawings** issued by AMLIFT International on behalf of High Sierra Elevator (2002). The scope of work included installation of a new 2100 lb, 2-stop passenger elevator in a new rated shaft enclosure and a new elevator machine room located remotely.

The Work has been completed.

## 2.0 Improvements to Piper's Opera House 2002 - 2011

The following construction documents were prepared between 2002 and 2011 following completion of the historic structures report.

- **Piper's Opera House Façade Stabilization 2002**

Funded by CCA 02-15 and 32-01-ML-1163 (SAT grant), the construction documents were issued by van Dijk Westlake Architects. The scope of work included shoring of the 1877 façade with installation of a new concrete rigid frame (typical east and south elevation), new shiplap siding, and repair / reconstruction of heavy brick deterioration and repointing. The plans indicated all doors and windows to be refurbished by Owner. Based on quarterly progress report filed by director Howard Bennett, all work was completed per plans.

- **A Historic Restoration for Piper's Opera House 2006**

Funded by CCA-05-18, the construction documents were issued by Anthony Smith Architecture. The scope of work included new wider stairs connecting the first and second levels, new plaster finish and bead board wainscoting, new wood plank flooring, and structural improvements including new concrete footings, tube steel columns and wide flange beams to strengthen the floor. The work was completed per plans.

- **Theater Modernization 2008**

Drawings prepared by Flex-A-Lite West, a former Reno-based theater design company. The scope of work included new pipe grid to support curtain tracks and lighting, new valance, borders, and legs, raceways for lighting circuit distribution, light ladders, and associated wiring. The work appears to have been completed.

- **Piper's Opera House Electrical Asbuilt 2010**

Funded by CCA-09-20, the as-built plans were prepared by Construction Design Services. The scope of work included documenting existing conditions, evaluation of existing conditions, and suggested remedies for code compliance. We were able to locate the as-built plans which documented the existing conditions but did not obtain information regarding evaluation and suggested remedies.



- **Loading Dock and Driveway Improvements to the Piper's Opera House 2011**

Funded by CCA-09-20, the construction documents were issued by Dubé Group Architecture. The scope of work included a new concrete landing with snow melt system and a new paved driveway. The driveway has not been completed.

- **Restroom Improvements to the Piper's Opera House 2011**

Funded by CCA-09-20, the construction documents were issued by Dubé Group Architecture. The scope of work included design of partially completed accessible restrooms. The work has been completed.

For additional structural improvements including emergency repairs post 2002, please see Appendix 1.0 Structural Report.

## F INVESTIGATION AND EVALUATION OF SYSTEMS

### 1.0 Plumbing

The plumbing domestic water, waste and propane systems seem to adequately serve the building. The original structure had minimal if any plumbing within. These systems have been upgraded over time to meet current code requirements. The most recent major upgrades were in 1999 when a new 2" cold water service and 4" main sewer line was added to serve the building.

The 2" domestic cold-water main enters the building on the north side and rises up in the fire alarm room, just west of the elevator. There is no backflow prevention between the water service and the building, so one is suggested to be added. There is no pressure reducing valve on the water main so one is suggested to be added to reduce the strain on the piping, valves and fixtures within the facility. Both devices (the backflow preventer and PRV) can be added in line with each other and within a 2'x2' vertical area along the exterior wall at the existing riser, below the fire alarm panels. It appears that all the piping was replaced copper with some smaller PEX piping at various locations.

Electric water heaters serve the point of use areas such as the kitchen, first floor restrooms & bar and the restroom/shower at the backstage area.

The 4" sewer main was added on the north side of building. Its exact route is not documented, but a sewer cleanout can be seen on the north side of wood sidewalk at the front of the building.

The heating system's fuel source is now propane, which feeds a single boiler. Two propane tanks are located on the north side of the building, at the second-floor level. The piping is routed on north face of building to boiler room. A regulator is installed just outside of the boiler room.



Photo 1 Propane Storage Tanks on north side of Piper's Opera House

The kitchen is proposed to be renovated to a warming kitchen to serve events at the facility. The proposed plumbing equipment is a 3-compartment sink. This sink will require large volumes of hot water which will require an upgraded water heater (at least 60-gallon capacity with 60 MBH heating input). It is suggested to provide a new gas-fired water heater in the northwest first-floor storage area and serve the bar and adjacent restrooms and renovated kitchen. This water heater, at approximately 32" diameter by 60" tall, could reside to the east of the double doors at the loading dock. The water heater requires 36" clear in front and 18" on each side for service clearance and should be set on a housekeeping pad.

## 2.0 Fire Protection

The Piper's Opera House did not include any provisions for fire protection of the structure as witnessed by the three fires that occurred during the early days of this building's lifespan. In 1999 a wet fire sprinkler system was added to the structure. A fire department connection and post indicator valve are located outside on the northeast corner of the property. The service entrance is on the first floor of the north side, just to the west of the elevator. This riser is 4" in size and connected to the fire alarm system via a flow switch. The system serves all levels of the building including the attic space. This system has an incoming water pressure of 130 PSIG and adequately serves the building. The only modifications necessary to the system would be because of any remodels. Annual inspections of the system are required by the fire code to ensure it is in proper working order.



Photo 2 Fire Department Connection and Post Indicator



Photo 3 Fire Riser and Domestic Water Riser

### 3.0 Heating, Ventilation, and Air Conditioning (HVAC)

Piper's Opera House was originally heated by four wood burning stoves and utilized a natural ventilation system with the heat being relieved through the hipped roof ventilator. The stoves are no longer being utilized. The ventilator was installed in 1885 and collapsed circa 1950's. It was later removed. This feature is to be recreated and can be utilized to provide natural ventilation as originally designed.

The current HVAC system includes a propane-fired, fin tube boiler that feeds a hydronic loop and various point of use heating and cooling systems. The boiler and associated system were installed in 1999. This heated water loop serves a radiant floor heating system on the first level (B Street) at the main entry. The hydronic system is distributed around the facility and is connected to multiple hydronic fan coils located in the following rooms: first floor corridor, two in the auditorium, and kitchen. These fan coils



Photo 4 Boiler and Hydronic Equipment

are noisy during operation and unable to be used during performances. A snowmelt loop was added at the loading area on the north side of the building; it covers the full width north to south and extends 12' from the west retaining wall. There is no observable snowmelt sensor, so it is assumed to be manually operated. Heating for the bar is provided by an electric duct heater and the pellet stove. The electric duct heater is located in the ceiling is connected to ceiling-mounted registers. The stage has a portable air conditioner and tech office on the balcony level has an electric packaged terminal heat pump located in the window for heating and cooling. There is no direct ventilation in the facility; this is now a code requirement and should be added with the new systems. The restrooms all have ceiling-mounted exhaust fans; most operate, but some may need to be replaced. Two 5'x8' smoke vents have been installed at the stage ceiling/roof for relief in case of a fire on the stage. A large 7,000 CFM exhaust fan has been added at the east side of the attic and pull hot air from the spaces below to ventilate the facility. This fan

provides little, but some relief during mildly hot days.

The appendix to the previous Historic Structure Report proposed the use of hydronic heat and distribute to terminal devices for delivery of heat through air to each space. The actual type of heater was noted to be subject to discussion and agreement for each room depending on practical and aesthetic factors. This approach is still the most viable approach for heating the facility. Radiant floor heating should be entertained for the auditorium



Photo 5 Existing Ventilation Shaft from Auditorium



Photo 6 Exhaust Fan in Attic

spaces and other rooms on that level. Please refer to that appendix for details of the system. The current fan coils should be removed in the auditorium due to noise but could remain in the other spaces if desired.

In addition to utilizing a hydronic heating, it is proposed to use natural ventilation and evaporative cooling for cooling of the facility. Evaporative coolers or recirculating makeup air units with hydronic heat could be added in the attic to serve the auditorium level spaces. These units could be installed through the fire vents above the stage or through the 3'x7' door on the west gable end of the roof/attic. Intake air for either system would be through new sidewall louvers (approximately 4' wide x 6' tall), located on any side of the building that could be made of wood to resemble the building's current style. The evaporative cooler or makeup air unit's air distribution could be through ceiling diffusers located above the stage and auditorium.

The hipped roof ventilator could be retrofitted with actuated damper to open and relieve the air from the auditorium which would follow the original cooling concept for the building. This system would utilize the existing ventilation shaft that routes from the auditorium and stops in the attic. This shaft would have to be extended up to the hipped roof ventilator.



Photo 7 Heater above Old Corner Bar ceiling

The existing 7,000 CFM exhaust fan should remain and be interlocked to operate with the evaporative cooler or makeup air unit.

The evaporative unit would be approximately 4'x6'x4' tall and weigh as much as 1,200 pounds. The makeup air unit would be about 3.5'x9'4' tall and weigh up to 1,600 pounds. Structural supports would be required for either system along with platforms for service. A path along the roof trusses would be required to

access the equipment from the east side of the attic where the access hatch resides.

An evaporative cooler could be added at the B Street level storage room, ducted in from the north, and be distributed to the entire level for cooling. Intake air would be through new sidewall louver that could be made of wood to resemble the building's current style.

## 4.0 Electrical and Communications

### Electrical Service

The existing electrical service is on the exterior south side of the building. The service is 120/208 volts, 3-phase, 4 wire, 400 amps disconnect switch, fed overhead from an NV Energy power pole at the southeast corner of the building on "B" Street. This service then distributes to the interior panels. This service currently seems adequate for the limited power usage of the building, but any major added power requirements will probably require the service to be upgraded. An electrical load study should be done first to determine the power loads of the existing building.



Photo 8 Existing 120/208 volts, 3 phase, 4 wire, 400 amp electrical service on south auditorium elevation

Over the years there have been a couple of proposals to upgrade this service but were not done. Upgrading this service would require a new underground service line from the existing power pole to a pad mounted NV Energy transformer and new switchgear to replace the existing service, such as is shown in the 1999 proposed work from Barrett Engineering. However, that project was for a 1200-amp service to accommodate a future building addition.

We recommend upgrading the service to 600 amps, 120/208volts, 3 phase, 4 wire. This service will need to be set south of the existing building walkway. To allow the building to possibly be

used as an Emergency Operations Center, we recommend including an emergency generator to the service. This generator would be approximately 210Kw and would be placed on a concrete pad along with the new electrical service south of the building. It would include an automatic transfer switch.

There are 5 interior panels to serve areas of the building: Panel A- Stage; Panel (B) - serving kitchen; Panel in the shop; Panel on the 3<sup>rd</sup> floor in the hallway (Office and Hallway); Panel in the Bar.



Photo 9 Existing electrical overhead service from power pole at B Street

None of these panels have a nameplate on them; only identified by pen handwriting. We recommend that phenolic nameplates be provided for these panels. Three of these panels- A (Stage), Kitchen, and Shop- do not have written or typed panel schedules; just handwritten notes in pen or pencil along the face of the panels. These should be updated with typed panel schedules and the circuits verified. There are also limited spares or spaces on these panels so adding circuits to these will need to be verified for availability. The proposed upgrades for the Kitchenette would require that panel to be replaced as there are no additional spare circuit breakers. The panel could be set in the existing location of the west wall but some repairs to the conduits and conductors would be included in that work as well as finishing the wall board.

There is no emergency power in the building, including to the elevator, so any emergency power needs would have to be provided by batteries, unless a new generator is added to the electrical service.

The Balcony is provided with some electrical boxes and conduits to provide 120-volt power outlets on the Balcony. Extension cords and cable are laying along parts of the Balcony floor that make for tripping hazards for someone trying to walk in the Balcony. Additional power outlets should be provided to minimize or eliminate these cords and cables.



Photo 10 Extension cords and cables lying about in the balcony

## Lighting




Photo 11 Keyless sockets with exposed CFL lamps

The interior lighting has tried to maintain the historic look of the building in the Auditorium and the Chandeliers in the Entry Lobby. The Lobby, Stairs, and Kitchen lights have been replaced with keyless sockets using compact fluorescent screw-in lamps. These fixtures do not have a shade on them, and the fluorescent lamp is exposed. The public hallway fixtures are wall sconces like the Auditorium lights and the Restrooms and back of house spaces are using fluorescent light sources. Consideration should be given to replacing the keyless sockets with appropriate light fixtures with shades/lenses and usage of current LED light sources. The First Floor Lobby has an exit

light at the doors and an emergency over the door into the Auditorium. This emergency though might not be adequate to provide code required egress lighting in this space.

A walkthrough of the entire Building might be needed with the power turned off to measure the lighting levels provided by the emergency lighting units and inadequate areas recorded in order to establish all areas that might need additional units.

The Auditorium has a chandelier in the middle of the room and wall sconces on the north and south walls. These lights do not appear to provide adequate lighting for some functions and so string lighting cords are strung from the balconies, apparently to supplement lighting levels. These string lights are plugged into extension cords on the Balcony, which are strewn about the Balcony and could be tripping hazards for someone maneuvering in the Balcony. A permanent solution to the lighting levels should be considered under a separate contract. This could include investigating if the existing lights can be retrofitted with new LED lamps that might provide better illumination for those fixtures; but they probably will not still be adequate for higher illumination levels.



Photo 12 No emergency light at Main Entrance



Photo 13



Photo 14 Auditorium – string lights hung from Balcony

The Lobby out of the Auditorium has only one emergency light and has no light at the landing to the Stair. There is a blank plate in the ceiling that appears to be an outlet for what was a light fixture.

The Balcony is provided with similar wall sconces as the Auditorium. Most of them are operating but a few of them are missing shades and lamps. These lights do not provide adequate lighting levels if the Balcony were to become an occupied level, so additional lighting would need to be addressed. There is no emergency or



exit lights on the Balcony so these too would need to be added for occupancy.



Photo 15 Balcony wall sconce lights



Photo 16 Balcony stage lights and pipe rigging

A stage lighting system was installed in 2008 that includes piping and lights on the north and south sides of the Balcony. The lighting control console is also located in the Balcony to provide a good view of the Stage. This location is at the bottom of the Stairs down to the lower row of the Balcony and would be in the way for people to occupy the Balcony.

The Third Floor Stair mid-landing ceiling has a blank plate that appears to be an outlet for what was a light fixture. This Stair is not well lighted and additional lights should be addressed. There also is not any exit or emergency lighting on this floor. The light switch for this area is located over the edge of

the Stair railing and difficult to reach. This should be relocated to an accessible location on the Stair landing.

The new proposed Basement egress will need to be provided with exit lights and emergency lights to meet Code required illumination levels.

### Fire Alarm/Security

The building is provided with an addressable fire alarm system by Fire-Lite Alarms. The fire alarm panel is in the Fire Riser Room. The system provides supervision of the fire sprinkler system flow and tamper switches and fire alarm audio/visual devices are provided throughout the building and appear to be adequately provided for alerting Building Occupants in case of an alarm. Smoke detectors are provided in the Lobby areas of the elevator to provide recall operations. The system with a voice evacuation feature. The system has been recently inspected and tagged in compliance with the State Fire Marshal.

This panel also supervises motion detectors throughout the building that provide protection for the structure.



Photo 17 Existing Fire Alarm panel in Fire Riser Room

### Telephone

The existing telephone backboard is located on the Third Floor in a storage area outside of the Office and seems to be adequate for the existing devices and outlets in the Office.

## **5.0 Structural and Seismic**

See Appendix 1.0 Structural Report

## 6.0 Architectural

### Building Exterior

#### Roofing

The roofing system was replaced in its entirety in 1999, funded by CCA-97-15 and included in construction documents titled **Reroof of Piper's Opera House** issued by JP Copoulos Architect (1997) and **Phase One Restoration of Piper's Opera House** issued by JP Copoulos Architect (1998). The plans called out for a new roof consisting of cedar shingles over felt and included replacement of deteriorated sheathing with approved sheathing along with new z-flashing. A new roof hatch, 36" x 30" was installed along with two fire vents, 60" x 96". The plans called out repairs to soffit boards, crown molding, fascia, and miscellaneous trim.

Attics are generally required to be ventilated to allow heat and moisture to escape, and there is an equation in the building code to determine net free ventilation area. Best practice is to locate half of the vents on the lower portion of the roof, typically at eaves or soffits, and the balance on the higher portion of the roof, typically at or near the ridge.

There are round soffit vents at the north and south eaves of the auditorium roof but we were unable to locate additional vents on the higher portion of the roof. We recommend a continuous ridge vent and a ventilated underlayment such as Cedar Breather in the next re-roof.

We also recommend a Class A fire retardation in the future, given the significance of the resource, which consists of shingles treated with Class B fire retardant combined with a fire retardant cap sheet underlay. We were unable to verify the roof covering classification of the existing shingles.

The roof system appears to be in good condition and should last another 10 years given an average lifespan of 30 years. The smoke vents are interconnected with the fire alarm system and open automatically upon detection of smoke or heat on the stage. We were unable to test the fire vents but assume that is part of an annual inspection by the local authorities having jurisdiction (AHJ).

The roof hatch is accessed via a ladder attached to the north wall at stage left. The distance from the stage floor to the landing platform above is just over 20 feet, less than the 24 feet trigger for an OSHA-approved safety ladder. However, the ladder should be secured to the wall in several locations where it is loose. The rungs are well-worn over the years several should be retained for interpretation and replaced with like kind rungs to prevent injury.

There has been discussion in the past about reconstructing the hip roof ventilator (cupola) on the east slope of the upper roof. As noted in the HSR, "A ventilation shaft was placed above the balcony. The shaft extended through the attic area, opening directly into an exterior ventilator. This feature had louvers on all sides, and a shallow hip roof. The rooftop element has been removed, but its size and appearance is sufficiently documented in photographs and in the roof framing to enable accurate reconstruction". If the ventilator is reconstructed, it could be incorporated into a new exhaust air system as discussed in Section F Part 3.0 HVAC.



Photo 18 Hip roof ventilator, circa 1939



Photo 19 View looking south from A Street. Roof hatch visible lower left, smoke vent upper right



Photo 20 View looking north from A Street. Smoke vent visible over stage right.



Photo 21 View looking northwest from B Street. Shiplap siding covering brick on south elevation of 1863 building. Flue coming out of arched window vents pellet stove used to heat Old Corner Bar. Seven doors with archways and eight second level windows (facing south and east) were refurbished in 2003. Note high window facing east in upper balcony.



Photo 22 View from B Street looking south. Note eight openings – window in tech office, three windows in auditorium, basement egress doors (visible beyond retaining wall), 1970s oversize egress doors, upper balcony egress door, and stage egress doors (far right in photo)




Photo 23 View from B Street looking due west.

## Siding

### 1863 Brick Building

The brick veneer was noted in the HSR as “severely deteriorated and in danger of partial collapse”. Proposed treatment included pinning brick façade to new interior concrete wall, repairs including replacement of missing brick, and repointing.



HISTORIC SHIPLAP PROFILE  
DATE: 11/12/12

The 1877 brick façade (1863 brick building) was pinned to a new interior concrete rigid frame, typical on the east and south elevations. New wood siding matching the historic shiplap profile was installed on the south elevation (and on the north and east elevations of the adjoining Carriage House) in 2003, funded by CCA-01-15, 32-01-ML-1163 (Save America’s Treasures grant), and CCA 02-15 and included in construction documents titled **Piper’s Opera House Façade Stabilization** issued by van Dijk Westlake Architects (2002).

Additional items included:

- Historic balcony hangers to be salvaged and returned to owner
- New redwood drop cove shiplap siding to match historic profile at south elevation over original brick using new mechanical fasteners and wood blocking
- Repair / reconstruct area of heavy brick deterioration on B Street elevation
- Repoint and rebuild entire brick column and capitol on B Street elevation
- Provide new surface mounted j-box at historic light locations on B Street elevation

The brickwork on the east elevation appears to be in fair condition and generally should not require repointing for another 10 to 12 years, given an average lifespan of 30 years. The new shiplap siding installed over furring strips to cover the brickwork on the south elevation appears to be in good condition, as does the shiplap siding on the north elevation.

The surface mounted j-boxes have not been installed per the note on the plans and the wiring is taped and dangling.



The van Dijk Westlake Reed Leskosky drawings indicated columns and capitols were to be rebuilt and repointed. However, there has been recent damage particularly near the base of the columns flanking main entry to Old Corner Saloon and Piper’s Opera House.



Photo 24 Damaged brick column on B Street façade at entry to Old Corner Saloon

It is unclear if the damage is caused by humans or nature – seasonal rain and snow cascading from the roof and bouncing off the boardwalk onto the brick and possibly causing spalling. Regardless, the damaged columns should be repaired by removing loose material and setting salvaged brick if possible.

### 1883 Auditorium Building

New shiplap siding was installed on the north, south, east and west elevations of the auditorium building by 2001, funded by CCA-99-15 and CCA-00-15 and included in construction documents titled **Phase Two-B Siding for Piper’s Opera House** issued by JP Copoulos Architect (1999).

The plans included removing and replacing existing siding with new 1x12 redwood siding over vapor barrier over 5/8” gypsum board over ½” plywood sheathing with R-19 batt insulation in stud cavities. The addition of 5/8” gypsum board is interesting, since the plans do not limit the application solely to the south auditorium wall, which would require a one-hour fire resistive rating due to its location on the property line and the fact that the building encroaches roughly 9 feet over into the A Street right of way on the west wall. We are unable to confirm whether the gypsum board was installed on the south wall and whether the east, west, and north walls are similarly protected without destructive demolition.

The shiplap siding is in good condition and was recently repainted (2016). Northern Nevada's dry climate, hot sun, and seasonal temperature swings are tough on painted wood surfaces, which require repainting every 7 to 10 years.



*Photo 25 West elevation from A Street looking east. Door above stage provides additional attic access. Siding was replaced over new plywood sheathing.*

## Metal Elements



Photo 26 Four cast iron piers visible in photo to right. Pier at north end appears to support adjoining building which has been demolished

### Cast Iron Piers

Four cast iron piers flanking two arched entry ways on the Carriage House east elevation are visible in exterior photographs of the dilapidated conditions taken in 1939 or 1940 (Library of Congress) as shown in photo to the left. The piers were identified as notable, in good condition, and with a high preservation priority.

Two cast iron piers have been fastened in place, primed, and painted. They are in good condition. The remaining two piers are displayed in the corridor alcove on the basement level and should be retained on site for interpretive purposes.



Photo 27 Note missing finials

### Railings

Approximately 22 lineal feet of wrought iron railing was installed on top of the tall retaining wall around the loading dock and service driveway which was cut into the north slope of Piper's Opera House in 2007.

The wrought iron railing is in good condition except for 10 missing finials, which should be replaced.



## Wood Elements

### Stairs

New exterior stairs and landing were specified for the auditorium building, funded by CCA-99-15 and CCA-00-15 and included in construction documents titled **Phase Two-B Siding for Piper's Opera House** issued by JP Copoulos Architect (1999).

The unpainted wood exterior stairs that serves the egress door from the upper balcony and the double doors from the stage (both openings were cut into the north side of Piper's Opera House around 1998) are deteriorating, as noted in the Structural Report, and should be replaced with new wood stairs and treated with linseed oil.

Photo 28 Exterior stairs from new exit at north balcony



Photo 29 New exit at north balcony and stage left with staircase and landing constructed 1999

## Windows and doors

### 1863 Brick Building

Funded by CCA-02-15 and CCA-03-15 and included in construction documents titled **Piper's Opera House Façade Stabilization** issued by van Dijk Westlake Architects (2002), seven entry doors in the 1863 brick building were refurbished in 2003, including arched transoms. Eight windows (6 facing east and 2 facing south on the second floor) were called out "to be refurbished / rebuilt from historic stock or new to match. Removal, storage, renovation, and installation by Owner".

In mid-2015, six windows facing east and one facing south (1862 brick building) were inadvertently removed and replaced with modern reproduction windows in violation of recorded covenants. Fortunately, the original windows were still intact and were able to be restored/reinstalled in 2017 after discovery. 14 window sashes were restored and painted, including epoxy filling and rebuilding, milling of new wood parts as required, and replacement of broken glass with 1/8-inch clear historical glass. The windows are in good condition.

The doors are in fair to poor condition. It is recommended they be refurbished and re-painted. There is an immediate need for maintenance repairs - some of the hardware needs to be re-attached.



Photo 30 Main entry doors at B Street. Screws missing at door knob escutcheons. Paint peeling.

The carriage house double doors and transoms were not rebuilt. One of the archways is flanked by cast iron piers and the doors are visible, although in poor condition and inoperable; there is a plywood panel covering the transom. The other archway has been completely covered and the opening obscured with shiplap siding installed and painted to match the second floor. It is recommended that the extant doorway be refurbished including double doors with arched transom.



Photo 31 Carriage House doors. Note the cast iron piers. Doors are in poor condition and arch obscured by plywood panel

### 1883 Auditorium Building

The doors – and some of the openings – are contemporary. Flush metal double doors (extra wide 42” leaf) with panic / crash bars exit the auditorium on both the south and north elevations; these doors were installed in the 1970s. The doors appear to be in good condition.

The flush metal double door was added at stage left on the north side and a four panel single door was added as an exit out of the upper balcony on the north side with new exterior stairs and landing to grade, funded by CCA-01-15 and included in construction documents titled **Phase One Restoration of Piper’s Opera House** issued by JP Copoulos Architect (1998). The doors appear to be in good condition, although we were unable to unlock the upstairs balcony door to verify egress.

The flush metal double egress door at basement level that opens out onto the concrete pad at the loading dock was cut through 30 inch thick concrete wall in 2007. The door appears to be in good condition.



*Photo 32 Exterior mounted 1 over 1 storm window, typical of three on south side and three on north side. Note deteriorating condition of window sashes beyond.*

There are three windows on both the south and north elevations. The six over six single hung windows are in fair condition. A storm window is located on the exterior side of each window and are attached by screws into the trim.

We recommend the storm windows be removed for repairs and the sash windows be refurbished including replacing any damaged or missing panes with “restoration glass”. Wood window components should be repaired and the entire assembly repainted prior to reinstallation of storm windows.

## Building Interior

### Basement

The B Street level has undergone significant improvements between 2003 and 2011 including the build out of the Old Corner Bar, a new passenger elevator, accessible restrooms, new fire exit, and completion of the main lobby and stairs.

### Old Corner Bar

The Old Corner Bar occupies roughly 1,275 SF and is prominently located on the southeast corner of the 1863 brick building. Formerly a workshop, the tenant improvements were completed in 2008 and the spacious saloon features a custom bar and painted canvas walls. The service area includes storage and a cool vintage walk-in cooler, which was apparently donated. The tavern shares accessible men's and women's restrooms with Piper's Opera House. The mop sink is located in a closet inside the men's restroom.

### Lobby

The wall separating the Old Corner Bar and the main lobby was constructed as part of improvements in construction documents titled **Phase One Restoration of Piper's Opera House** issued by JP Copoulos Architect (1998). The lobby renovations were completed in 2007 and include maple flooring over hydronic tubes, plastered and painted walls above bead board wainscoting, and a wood ceiling.

### Carriage House

Two arched openings in the original 1863 brick building connect the main lobby to the Carriage House. Due to a grade change, the lobby floor slopes down to meet the lower finish floor elevation at the corridor. The corridor provides access to the workshop, fire alarm, elevator, and an office currently being constructed for the director.

The passenger elevator was constructed based on construction documents titled **Elevator for Piper's Opera House** issued by JP Copoulos Architect (2001) and **Elevator Shop Drawings** issued by AMLIFT International on behalf of High Sierra Elevator (2002) and funded by CCA-99-15 (and possibly CCA-00-15). The 2-stop hydraulic holeless elevator has a 2,100 pound load capacity. The hoistway is a one-hour shaft. The cab size and call buttons meet accessibility requirements.

The elevator machine room is located remotely and is accessed through the workshop. The machine room contains a controller and submersible pump unit. We were unable to verify an independent ventilation system. Because the room does not abut the hoistway enclosure, is located in a building less than four stories above grade plane, and because it is not a fire service access elevator, the machine room is not required to have fire rated construction.

### Accessible Restrooms

Accessible restrooms were completed in 2011 based on construction documents titled **Restroom Improvements to the Piper's Opera House** issued by Dubé Group Architecture (2011) and funded by CCA-09-20. The men's restroom is equipped with one lavatory, one mop sink, and two water closets. The women's restroom is equipped with two lavatories and two water closets. The restrooms, which were generally constructed to plans, meet accessibility requirements.





Photo 33 B Street lobby looking west. Walls are plastered and painted with bead board wainscoting and cap. Wood ceiling with soffits to hide piping. Wood column in middle of photo leaning. Stairs complete. New maple flooring over hydronic heating tubes. New director's office visible through archway.



Photo 34 B Street lobby looking east to B Street. Main entry doors with arched transoms.



Photo 35 B Street lobby looking south. Double doors are required second exit from Old Corner Bar.



Photo 36 B Street Lobby looking north. Access to second exit to left in photo. Arched opening in original 1863 brick building leads to corridor through Carriage House. Elevator beyond.

### Required Means of Egress

A second required means of egress out of the basement was cut into the north side of Piper's Opera House in 2008, which required substantial excavation of the existing slope and saw-cutting a new opening through 30 inch thick reinforced concrete. A pair of doors with panic hardware swings in the direction of travel onto a concrete landing. A gravel driveway extends east to the edge of existing paving at B Street.

We were unable to locate any plans for the excavation, retaining wall, or the new concrete piers flanking the new opening. Construction documents titled **Loading Dock and Driveway Improvements to the Piper's Opera House** issued by Dubé Group Architecture (2011) specified a new concrete landing consisting of 6 inch thick fiberglass reinforced concrete (min. 4000 psi @ 28 days) over four inch Type 2 compacted aggregate base, snowmelt system, and 3 inches of AC over 6 inch compacted aggregate base

for the driveway. The concrete landing with snowmelt was installed but the driveway is not paved. Work was funded by CCA-09-20.




Figure 1 Proposed basement egress plan at north side of Piper's Opera House

The exit path to the north door is continues through a 42" wide swinging door and partition wall that spans between the women's restroom and boiler room. The exit sign in the main lobby that appeared in earlier photographs has been removed. Once past the swinging door, the exit path is cluttered with stored materials.

The existing partition wall and door spanning between the boiler room and Women's restroom should be removed along with stored material and the space enclosed with

partition walls and ceiling to complete the exit path to the out-swinging doors at the loading dock. The existing 42" wide door can be relocated to provide access to the crawlspace. The driveway should be paved to B Street (approximately 1,000 SF).

The proposed interior work occurs in an area that has little remaining fabric, which is limited to floor joists, supporting members, and brick piers; similarly, the proposed exterior work is limited to new a/c paving on previously excavated site.



Photo 37 Excavation at north side for access to double egress doors. Existing concrete pad with snow melt system. Pour new 3 inches of a/c pavement over 6 inches of compacted aggregate base from edge of concrete pad to B Street



Photo 38 View of double egress doors looking north. Note blocked exit. New partition wall will align with the footing supporting the column.

## Auditorium Level

### Lobby

The second level of the 1863 brick building has undergone significant improvements since completion of the HSR. The lobby received new wood flooring, plaster finish on walls and ceilings, and bead board wainscoting. The grand staircase is now complete and finished about midway up to the landing between the auditorium and balcony levels.

The second story façade windows were identified in the HSR as being in fair to poor condition with high preservation priority. The windows were salvaged from other local buildings in 1883, following the fire. As noted above, the windows have been repaired and are in good condition.

The south wall of the auditorium lobby dates to at least 1877 and the salvaged lumber sheathing has been left exposed above the wainscot. The ticket window and gun check window are intact.

### Bridal Room and Catering Kitchen

There are two rooms on the south end of the 1863 building which served as the administrative office for the theater after 1885: the Bridal Room and kitchenette. Piper's Opera House is a wedding venue and the Bridal Room functions as the dressing room for the bride.

Storey County would like to upgrade the existing kitchenette to facilitate catered events including weddings, and staff would like a setup similar to the Historic Fourth Ward School. It will be used to hold and serve cold, frozen, and warm food catered by outside vendors. No food will be prepared onsite, eliminating the need for exhaust hoods and grease interceptors.



Photo 39 Looking east at auditorium lobby landing. Grills were added for fall protection. Salvaged lumber exposed above wainscot.




Photo 40 Decorative grill visible at landing above. Note keyless sockets with exposed bulbs.



Photo 41 Auditorium lobby looking west. Door at left into Bridal Room; note two steps. Wainscoting, flooring, and wall and ceiling finishes complete. Stairs down to B Street level and up to balcony level. Folding doors at auditorium visible in background



Photo 42 Bridal Room looking south. Door at right into kitchenette. Wood floors retained in former theater office



Photo 43 View of existing kitchenette looking west. Auditorium visible through open doorway. Exposed wall sheathed in salvaged lumber shown on right side of photo should be protected in place and left exposed for interpretation or covered with fabric and new wall paper attached. Electrical subpanel to right of doorway. Fan coil unit for heating in kitchenette and adjoining Bridal Room. New flooring overlaid on existing wood floors

The kitchenette occupies a room roughly 16' x 18' measured from interior face of the walls with a ceiling height of roughly 11'-6" above finished floor. There is a two compartment sink set into an L-shaped plastic laminate countertop with laminated base cabinets, a microwave, two residential refrigerators with freezer compartments, and a couple of café tables.

The north wall exposed sheathing, shown in Photo 39 is part of the historic fabric and should be protected in place. That wall, which separates the kitchenette from the Auditorium lobby, has two openings, a ticket window and a weapons check window. Both are character defining features and should be protected in place.

The floor level of the kitchenette (and the adjoining Bridal Room) is approximately 16 inches higher than the auditorium and lobby. There are two steps up into the kitchenette through an existing 32" wide opening, all of which poses a challenge when remodeling because equipment must be sized to fit through the existing doorway.

The flooring in the kitchen is a contemporary vinyl in a simulated wood look which could be retained or replaced with a similar product as part of the remodel. The gypsum board ceiling should be patched and new light fixtures installed.

The new catering kitchen will consist of a U-shaped countertop with base cabinets and upper cabinets. The countertop should be solid surface or stainless steel with a stainless steel commercial three compartment sink with dual drain boards.




Figure 2 Proposed catering kitchen layout

Equipment includes two warming carts, one reach-in freezer, and two reach-in refrigerators; all equipment will be NSF certified and on casters.

Additional equipment could include countertop microwave and commercial coffee maker.

A new 60-gallon hot water heater and upgraded electrical sub-panel to replace the existing panel are necessary to accommodate the new catering kitchen and these improvements are discussed in the plumbing and electrical sections elsewhere in this report.





Photo 44 Auditorium level single occupancy restroom. Does not meet accessibility standards



Photo 45 Auditorium level Men's Restroom. One lavatory, three urinals, and one water closet. As configured, single occupancy restroom while water closet in use. Does not meet accessibility standards as currently configured. Door is too narrow into restroom.



Photo 46 Auditorium level looking east. Original 1863 brick wall visible in arched opening.

### Carriage House

The north half of the second story (Carriage House), formerly John Piper's apartment, has been extensively modified over the years with the addition of new restrooms and an elevator, and the finishes including flooring, walls and ceilings are contemporary.

The single occupant restroom is accessed of the hallway through a 36-inch wide door and consists of a lavatory, water closet, and fire sprinkler standpipe. It does not meet the clear floor area requirements for accessibility nor does it appear feasible.

The Men's Restroom is accessed through a 28-inch wide door and consists of a lavatory, three urinals, and a water closet with urinal-type partitions, rendering it a single occupant restroom if the water closet is being utilized. The Men's Restroom does not meet the clear floor area requirements for accessibility as currently configured although it is possible with conversion to single occupancy, nor does it meet the door width requirement. Sight lines into the Men's Restroom and single occupant restroom are poor.

The Women's Restroom, located at the end of the narrow hallway, is accessed through a 28-inch wide door and consists of three water closets in private compartments and a single lavatory. Although the space is tight, there is some degree of privacy. This restroom is not accessible as currently configured although it is possible with conversion to single occupancy, nor does it meet the door width requirement.

There is a loft above the single use restroom used for storage and another one above the Men's Restroom where the water heater is located which are accessed through a sidewall door. The lofts are sheet rocked, fire-taped, and sprinklered.

### Auditorium

As noted in the HSR, “The audience chamber and staging remain virtually intact from the 1885 completion. The proscenium arch, box seats, wainscoting around the perimeter of the walls, the face plates of the balcony, and the window frames are all original material.” The treatment recommendations were “all wood elements to be retained, patched where essential, and repainted. Colors to be determined by conservator and forensic paint analysis”. We were unable to determine if a paint analysis was completed.



Photo 47 “Sunburner” gasolier intact. Painted plywood floor installed 2007 covers 1907 maple floor. In 2004, underside of balcony and walls sprayed with fire retardant and covered in fire-retardant muslin. Wood elements in good condition.

In 1907, a maple floor was installed over the original floorboards (circa 1884), and the recommended treatment was to “repair and restore 1907 floor with view panels to 1884 flooring”. In early 2007, HBO rented the space and set up a sound stage, covering the maple floor with two layers of 1-inch thick plywood painted black, which remains in place today. The top layer is attached with screws but we were unable to determine how the bottom layer is attached and whether there is any damage to the underlying historic fabric.

To accommodate the future hydronic radiant heating system, the painted plywood should be removed and a new floor installed consisting of 3/4” plywood sleepers to support tubes overlaid with 3/8” plywood subfloor and topped with a floating wood floor. The entire assembly should be less than 2 inches thick and will match the existing finish floor elevation.



Photo 48 1907 maple flooring visible in foreground. In 2007, HBO set up production studio and added 2 layers of plywood, painted black, over maple flooring. Note beveled transition strip painted yellow. Maple flooring appears to be in fair to good condition.



Photo 49 View from stage right looking at auditorium chamber. Typical table and chair layout. Note stage lighting on balcony

In 2004, possibly funded by CCA-03-15, the water-damaged 1960s muslin (or possibly canvas) was removed from the underside of the balcony and wood walls. The exposed wood surfaces were treated with “FLAMORT-WC”, which the manufacturer described as “a non-toxic, water-base, fire retardant coating, and then covered with muslin sprayed with flame retardant (possibly manufactured by Rose Brand Textile Fabrics). The flame retardancy has an expected lifetime of at least one (1) year and recommends annual testing.



*Photo 50 View of exposed lath under balcony at north side above door to stage and boxes. Unit heater visible to right in photo.*

### **Opera Boxes**

The opera boxes are original and in fair condition. The wall paper remains intact but is substantially covered with red felt; the floors have been covered with contemporary carpeting. Valances and drapery drops are contemporary. Access to each of the lower boxes is through a narrow doorway and up five steps. There is another steep, narrow stairway leading to each of the upper boxes from the stage and a secondary access through the balcony. As noted in the HSR, “Limited access from the rear. Not viable for contemporary seating” and we concur with this statement unless the AHJ is willing to allow the boxes to be occupied as a non-conforming use. The remaining treatment recommendations noted in van Dijk Westlake Reed Leskosky report are still valid.



Photo 51 Stairs to opera boxes at stage left



Photo 52 View of stage and auditorium chamber from lower opera box at stage left. Existing wood elements in fair condition.

## Storage

Storey County will continue to utilize the auditorium for plays, meetings, celebrations, and similar group functions. Depending on the function, it could be set up for sit down meals, arranged conference style for meetings and seminars, or theater style for performances of up to 300 spectators. Tables and chairs are currently stored stacked up against the wall when not in use. Padded folding chairs are stacked onto mobile carts which can be moved to the side. Standard plastic folding tables, 2 feet by 6 feet, are simply stacked, leaning against the wall.

To prevent damage, provide a cleaner look, and offer more flexible use of the space, the county would like to find a long term solution for storing tables and chairs.

It was discussed adding an enclosure at the basement level north side concrete landing but we don't recommend that location for several reasons. First, the north door serves as the second exit from the basement level and there is insufficient area to enclose a room and still maintain egress width. As shown in Figure 3, the storage area footprint would be roughly 250 square feet.

Second, it would be difficult to maneuver carts through hallways into and out of the elevator while subjecting wall finishes to potential damage.

Until a long-term storage solution can be found, we recommend the county purchase mobile carts to store tables.




Figure 3 Minimum area requirements for table and chair Storage

**Accessible Means of Egress**

As discussed in Section 8.0 Building Code Review, the elevator cannot be used as part of an accessible means of egress without standby power. The south-facing exit doors swing out onto a level landing at grade, which is technically in the public way since the adjoining property is owned by the county. If the gate separating the two properties is removed or equipped with a panic device, the AHJ has the authority to make a determination that this would meet the intent of the code.

The north-facing exit doors swing out onto a level landing with two steps down to grade. This could be reconfigured as shown in Figure 4 to include a deeper landing with a switchback ramp to grade. The ramp is held back 4 feet from the building for a snow drop area. In lieu of continuing a ramp down to B Street (public way) which has been proposed in the past, a safe dispersal area could be maintained on the north lot.




Figure 4 Proposed accessible means of egress from north exit doors to safe dispersal area





Photo 53 South exit from auditorium



Photo 54 North exit from auditorium

### **Stage**

Treatment recommendations for the stage included documenting, inventorying, and removing scenery flats and gas control panel, and preserving for display. Scenery guide racks were in good condition, and recommendations included replacing support ropes, realigning rails, and tightening connections. The stage rigging components were in fair to extremely poor condition and it was recommended to refurbish for light duty if possible or remove and preserve for display. The wood grid floor above the stage was in fair condition, and it was recommended to repair, refurbish, and reinforce for continued use.

The staging area has been upgraded with new draperies, lighting, and sound systems. The remaining treatment recommendations noted in van Dijk Westlake Reed Leskosky report are still valid.



*Photo 55 View of stage with curtains and valances*



Photo 56 40-channel digital live mixer rack installed stage right



Photo 57 view from stage right. Stairs on right go up to balcony, stairs to left go down to auditorium. Stage exit door facing south. Note electrical panels to left of door.



Photo 58 View from stage left looking south. Note light through floor boards of loft area in attic above stage.

### Lobby Staircase to Balcony

Currently, the grand staircase is partially completed from the auditorium level to the balcony level and should be finished to match existing hand rails, half-round bannister cap, bead board wainscoting, and flooring including pre-molded slip-resistant vinyl treads and risers. Materials stored on the landing and stairs should be removed. The iron grill work obtained from the International Hotel that was across the street from Piper's Opera House was repurposed in 2007 as the guardrail, shown clamped in Photo 58, and should be welded after verifying it can resist a concentrated load of 200 pounds (it might be necessary to strengthen the connections to the floor deck). Lighting and life safety components including horn / strobes are required and exposed gypsum board surfaces above wainscoting should be textured and painted to match adjacent finishes.



Photo 59 Existing stairs complete with handrails on both sides of stairs; half-round bannister cap, bead board wainscoting, and vinyl treads and risers

The iron grill work obtained from the International Hotel that was across the street from Piper's Opera House was repurposed in 2007 as the guardrail, shown clamped in Photo 58, and should be welded after verifying it can resist a concentrated load of 200 pounds (it might be necessary to strengthen the connections to the floor deck). Lighting and life safety components including horn / strobes are required and exposed gypsum board surfaces above wainscoting should be textured and painted to match adjacent finishes.



Photo 60 View looking east of partially completed stairs to balcony level.



Photo 61 View of landing to balcony level. Note clamp at guardrail.



Photo 62 Unfinished stairs to balcony level. Door to current VCTC office shown at right on intermediate landing

## Balcony

The balcony itself has not undergone the treatment recommendations contained in the HSR, which noted the condition as “good”, and went on to state “support beams for balcony have been replaced and occupancy is approved”. We reached out to representatives at both engineering firms that worked on Piper’s (Mel Green and Paul Ferrari) to confirm neither firm designed any improvements or were otherwise aware of any improvements by others and concluded that statement is incorrect. There is no evidence that new support beams were engineered or installed. As noted in Appendix 1.0 Structural Report, the balcony would need to be analyzed and upgraded structurally as required to meet today’s full code live and dead load in order to protect the health, safety, and welfare of the occupants.

The balcony is currently used by technicians to control sound and lighting and for storage of props and chairs. If the county intends to occupy the balcony, significant and irreversible modifications to the historic fabric would be required unless the AHJ agrees to waive code requirements for rise and run of stepped aisles, handrails and guardrails, aisle widths, and exiting. Here are some of our concerns:



Photo 63 balcony light fixture missing glass shade and bulb

- The stair risers vary from 7-1/2” to 10-3/4” and the treads vary from 10-1/4” to 12”; code allows an 8-inch rise maximum and 12-inch run minimum with little to no variation in the same plane.
- The balcony face plates extend 16 inches vertically beyond the deck to act as a guardrail; an extension would be required to meet minimum sightline-constrained guardrail height of 26 inches in front of the pews and 36 inches at the end of aisles, in addition to 36 inch high handrails in the center of aisles.

- A 36-inch wide exit door and exterior stairs were added on the north side in 1999. Access from the balcony to the exit discharge is through a narrow intervening doorway (28-inch wide). The aisle width varies from 17 – 22 inches instead of the minimum 36 inches required.
- Another exit door and exterior stairs would be required on the south side.

Some pews are missing, there are loose and missing pieces of wainscot, floor boards are damaged or missing, and the guardrail cap is damaged in areas. Missing wood elements should be custom milled and loose pieces reattached. The tattered remains of carpet runner on the main stairs could be removed for display and replaced with like kind material. Missing lamp shades should be replaced and all lights inspected.



Photo 64 View of north balcony looking west toward doorway which exits behind upper opera box. Boards should be reattached to wainscot and missing pieces custom milled.



Photo 65 Stairs descend from main balcony entrance to right in photo. Pew bottom missing. Note damaged guardrail cap left of rod supporting balcony



### Attic

The attic is accessed through a pull-down ladder just inside and to the right of the main entry to the balcony level. The opening size is 22.5" x 54" and the attic lights are controlled by a switch on the side of the opening before you step onto a wooden platform. There is an exhaust fan on casters that ventilates the auditorium and is discussed in detail in Section E Part 3.0 Heating, Ventilation, and Air Conditioning, along with the round ventilation shaft.



Photo 66 Attic access via pull down ladder

The attic is protected with fire sprinklers; there is a hydronic fan coil in the southeast corner that we believe was installed prior to insulating the attic. The sidewalls have been insulated with R-19 batts and the roof rafters are insulated with R-38 batts, making the attic part of the insulated and heated building envelope.

In addition to three penetrations through the roof, including a roof access hatch and two smoke vents, the attic can be accessed from the outside through a new door that was installed in the west elevation gable end (see Photo 11). The smoke vents and the door could provide access in the future to install equipment in the attic as discussed in Section 3.0 HVAC.

The stage rigging components including the wood grid floor pictured below will need to be repaired and reinforced for continued use and to support new HVAC equipment such as the evaporative cooler.



Photo 67 View of ladder access from platform in attic. Note location of light switch



Photo 68 Kraft-faced fiberglass batt insulation at walls (R19) and roof (R38). Note plywood sheathing



*Photo 69 View of loft area above stage taken from ladder platform looking south.*



*Photo 70 View of loft area looking southwest. Note door in middle center of photo – this is the door in the west gable end visible from A Street.*

## **7.0 Building Accessibility**

As of March 15, 2012, all newly constructed or altered State and local government facilities must follow the requirements of the 2010 ADA Standards for Accessible Design, including Title II regulations at 28 CFR 35.151 and the 2004 ADAAG at 36 CFR part 1191, appendices B and D.

In addition to federal regulations, IBC Section 3411.9 requires accessibility in historic buildings that undergo alterations or a change in occupancy except where it is deemed technically infeasible by the governing authority. If compliance with the requirements for accessible routes, entrances or toilet rooms would threaten or destroy the historic significance of the facility, the following minimum alternatives requirements must be met:

- At least one accessible route from a site arrival point to an accessible entrance shall be provided
- An accessible route from an accessible entrance to public spaces on the level of the accessible entrance shall be provided
- At least one main entrance shall be accessible with appropriate signage
- Where toilet rooms are provided, at least one accessible family or assisted-use toilet room shall be provided

Providing accessibility including accessible means of egress in a historic building on a steeply sloping site is challenging at best, and technically infeasible in some instances. We recommend sitting down with local authorities to discuss compliance with regards to the auditorium.

For the purpose of this report, we have not attempted to make the balcony level accessible.

We noted the following deficiencies:

Basement:

- The basement level, which is the primary entrance / exit into the building, is generally accessible at grade from B Street. As noted in Section 8.0 Building Code Review, the path of travel through the lobby to the exit discharge doors opening onto the loading dock would need to be accessible since it is a required exit.
- The accessible restrooms are located in the basement and were designed to be shared between the Old Corner Bar and Piper's Opera House. When only the bar is open for business, the gate is locked on the Piper's side; conversely, the gate can be locked on the bar side if it is closed during events at Piper's. In reality, it looks like the bar is storing supplies and stock in the hallway, preventing use from Piper's side. This should be remedied.
- Accessible restrooms need an ADA Compliant International Symbol of Accessibility (ISA) sign and non-accessible restrooms need directional signage

- The finished floor of the B Street lobby is several inches higher than the adjoining Carriage House. Access to the elevator (and future director's office) is through two arched openings in the 1863 brick building. To accommodate the height difference, the floors are sloped in the archways, varying from 6.5% to 12.5% across a 44-inch run. The steeper slopes are allowable under the International Existing Building Code (IEBC). However, handrails on both sides of ramps are required.

Auditorium:

- The elevator connects the basement and auditorium levels, and does meet the minimum requirements for an accessible passenger elevator set forth in the 2010 ADA Standards for Accessible Design. However, as noted below in Section 8.0 Building Code Review, the elevator is not considered part of an accessible means of egress because it does not comply with standby power requirements. In the event the elevator is rendered inoperable, we would need to provide an accessible route from the auditorium to the public way.

### 8.0 Building Code Review

Piper's Opera House is afforded special recognition by virtue of its listing both individually and as a contributing resource on the National Register of Historic Places. However, such listing does not preclude conformance with life safety and accessibility requirement and any future improvements to the facility will be affected by code-based legal constraints, including state statutes, adopted model building codes, and federal accessibility requirements.

The forgoing analysis is intended to review basic code requirements and is not exhaustive nor assumes changes in use or occupancy. The analysis is taken from the 2018 Edition of the International Building Code (IBC) and encompasses Chapter 3, Occupancy Classification and Use; Chapter 4, Special Detailed Requirements based on Occupancy and Use; Chapter 5, General Building Heights and Areas; Chapter 6, Types of Construction; Chapter 9, Fire Protection and Life Safety Systems; Chapter 10, Means of Egress; Chapter 11, Accessibility; and Chapter 29, Plumbing Systems. Additional analysis includes the 2018 Edition of the International Existing Building Code (IEBC), Chapter 12, Historic Buildings.

### OCCUPANCY CLASSIFICATION AND USE

The Old Corner Bar, a private business, leases roughly 1,275 SF of the southeast portion of the basement level at B Street and is considered a Group A-2 occupancy (taverns and bars).

Virginia City Tourism Commission's on-site manager currently occupies a small office on the balcony level but pending completion of a new office being constructed at the northeast corner of the Carriage House, roughly 200 SF, is considered a Group B occupancy (business).

The main auditorium can be rented by private individuals and community groups to host weddings, receptions, memorial services, lectures, plays, and other similar functions and is considered a Group A-2 occupancy (banquet halls).

The following chart summarizes the area, use, occupancy and number of occupants:

**Area and Occupancy – Piper’s Opera House**

Space	Area (SF)	Use	Occupancy	Occupant Load (SF/Occupant)	Number of Occupants
Old Corner Bar	1275	Assembly	A-2	15	85
Future Office	160	Business	B	150	2
Women’s Restroom	164				
Men’s Restroom	166				
Boiler Room	157				
Elevator Mach. Room	55				
Workshop	110				
Fire Alarm	68				
Lobby	848	Assembly	A-2	7	121
Circulation, etc.	937				
<b>Basement Total</b>	<b>3940 SF</b>	-	-	-	<b>208</b>
Bridal Room	270	Business	B	150	2
Catering	340	Business	B	150	3
Unisex Restroom	56				
Men’s Restroom	70				
Women’s Restroom	125				
Auditorium	4100	Assembly	A-2	Per SC Fire Dept.	360
Opera Box (stage left)	48	Assembly	A-2	15	4
Opera Box (stage right)	48	Assembly	A-2	15	4
Stage	1490			15	100
Dressing Rooms	90				
Circulation, etc.	1155				
<b>First Floor Total</b>	<b>7792 SF</b>	-	-	-	<b>473</b>
Balconies	2168	Assembly	A-2	Fixed Seating	200
Opera Box (stage left)	60		A-2	15	4
Opera Box (stage right)	60		A-2	15	4
Storage	147				
Circulation, etc.	378				
<b>Second Floor Total</b>	<b>2813 SF</b>	-	-	-	<b>208</b>
<b>Building Total</b>	<b>14565 SF</b>	-	-	-	<b>889</b>

### **SPECIAL DETAILED REQUIREMENTS BASED ON OCCUPANCY AND USE**

The stage in Piper’s Opera House exceeds 1,000 SF in area and is required to have fire sprinklers and emergency ventilation consisting of two or more roof vents which open automatically by approved heat-activated devices and with an aggregate clear opening area of not less than 5% of the area of the stage.

The stage is approximately  $1490 \text{ SF} \times 5\% = 74.5 \text{ SF}$  net ventilation required, which was met in the 1997 Reroof with the installation of two vents, 5’ x 8’ each.

### **GENERAL BUILDING HEIGHTS AND AREAS**

Piper’s Opera House is considered a two-story building with a walk-out basement at B Street. Based on a sprinklered, multiple story, Type V-B, A-2 occupancy, the following allowable heights, number of stories, and areas are permitted by the code:

Allowable Building Height:	60’
Actual Building Height:	45’ <i>as measured from story above grade plane</i>
Allowable Number of Stories:	2
Actual Number of Stories:	2 <i>plus basement</i>
Allowable Building Area:	18000 SF
Actual Building Area:	14565 SF

### **TYPE OF CONSTRUCTION**

The wood-frame building is considered Type V-B construction, wherein the structural elements, exterior walls, and interior walls are of any material – combustible or noncombustible – permitted by code. However, the south auditorium wall would require a one-hour fire resistive rating due to its location on the property line. Interestingly, the west wall of the auditorium encroaches 9’-0” +/- into the A Street right of way, and we would recommend that the west and a portion of the north wall have a one-hour fire resistive rating (see also discussion regarding siding).

### **MEANS OF EGRESS**

Based on the occupant loads, a minimum of two exits are required from each floor. Rooms or spaces with more than more than 49 occupants are required to have two exits, which affects the Old Corner Bar saloon area and the auditorium. An occupant load of more than 500 would trigger the requirement for a third exit, but we calculated the auditorium load at 473. Exit doors must be placed a distance apart equal to not less than one-half the length of the maximum overall diagonal dimension of the building or space served. Exit doors serving an occupancy greater than 50 are required to be out-swinging in the direction of travel and discharge directly to the exterior of the building. The exit discharge must be on grade or provide direct access to grade via an accessible ramp.

We noted the following deficiencies:

Basement: The double doors that open onto the loading dock were intended to be the second exit from this level. The stored materials located between the exit doors and the intermediate partition wall should be removed and exit signs and emergency lighting installed. The Old Corner Bar, with an assembly occupancy of 85, also requires two exits including exit signs. The double doors that swing into the main lobby should remain unlocked during business hours.

Auditorium Level: this level does not have two accessible means of egress and is discussed in depth in Section 7.0 Building Accessibility above. It is important to note that the passenger elevator cannot be used as a component of a required means of egress because it does not comply with the emergency power requirement.

Balcony Level: Not less than two means of egress shall be provided, with one from each side of every balconies, galleries or press boxes having a seating capacity of 50 or more. There is 300 lineal feet of balcony benches, which can seat 200 people (1 per 18"). There is a main exit at the east side and an exit was constructed on the north side circa 1999. However, a new exit will be required on the south side prior to occupying the balcony.

#### **PLUMBING FIXTURES**

IBC Table 2902.1 provides the minimum number of plumbing fixtures required based on the type of occupancy and number of occupants. To determine the occupant load for each sex, the building total occupant load must be divided in half and separate facilities provided for each sex.



## Minimum Number of Required Plumbing Fixtures

Occupancy	Toilet Male	Toilet Female	Lavatory Male	Lavatory Female	Other
Old Corner Bar Assembly A-2 85 occupants	1 per 40 occupants	1 per 40 occupants	1 per 75 occupants	1 per 75 occupants	1 drinking fountain 1 service sink
<b>Subtotal</b>	<b>1.06</b>	<b>1.06</b>	<b>0.57</b>	<b>0.57</b>	<b>1 each</b>
Without Balcony Assembly A-2 589 occupants	1 per 75 occupants	1 per 75 occupants	1 per 200 occupants	1 per 200 occupants	1 drinking fountain 1 service sink
<b>Subtotal</b>	<b>3.92</b>	<b>3.92</b>	<b>1.47</b>	<b>1.47</b>	<b>1 each</b>
With Balcony Assembly A-2 797 occupants	1 per 75 occupants	1 per 75 occupants	1 per 200 occupants	1 per 200 occupants	1 drinking fountain 1 service sink
<b>Subtotal</b>	<b>5.31</b>	<b>5.31</b>	<b>1.99</b>	<b>1.99</b>	n/a
VCTC Business B 7 occupants	1 per 25 for the first 50 and 1 per 50 for the remainder exceeding 50	1 per 25 for the first 50 and 1 per 50 for the remainder exceeding 50	1 per 40 for the first 80 and 1 per 80 for the remainder exceeding 80	1 per 40 for the first 80 and 1 per 80 for the remainder exceeding 80	1 drinking fountain 1 service sink
<b>Subtotal</b>	<b>0.14</b>	<b>0.14</b>	<b>0.09</b>	<b>0.09</b>	n/a
<b>Total without balcony</b>	5.12 or <b>6</b>	5.12 or <b>6</b>	2.13 or <b>3</b>	2.13 or <b>3</b>	<b>2</b>
<b>Total with balcony</b>	6.51 <b>7</b>	6.51 <b>7</b>	2.65 or <b>3</b>	2.65 or <b>3</b>	<b>2</b>
<b>Existing</b>	<b>7</b> 4 toilets 3 urinals*	<b>6</b>	<b>3</b>	<b>4</b>	<b>No DF</b> <b>2 SS</b>
<b>Deficit with balcony</b>		<b>1</b>			<b>2 DF</b>

\* Per IPC Section 424.2, Assembly Occupancies may substitute up to 67% of required water closets

## **G RECOMMENDATIONS FOR TREATMENT**

### **1.0 Plumbing**

- Install backflow prevention device
- Install pressure reducing valve
- 60-gallon capacity water heater to serve catering kitchen and saloon

### **2.0 Fire Protection**

- Annual inspections

### **3.0 Heating, Ventilation, and Air Conditioning (HVAC)**

- Provide direct ventilation per code
- Verify operation of restroom exhaust fans
- Hydronic heating
- Evaporative cooling

### **4.0 Electrical and Communications**

- Upgrade electrical service to 600A
- Emergency building generator
- Additional power receptacles at balcony
- Replace keyless sockets with appropriate light fixtures
- Add emergency egress lighting
- Replace kitchenette panel with larger panel, more circuit breakers

### **5.0 Structural and Seismic**

- Roof truss support
- Wall column buckling
- Column at entry
- West wall of the building / water infiltration / drainage
- Balcony framing and support (“full use” option)

## **6.0 Architectural**

### **Building Exterior**

#### **Roofing**

- Annual inspection of roofing system to correct defects in shingles, roof penetrations, fascia, and soffit

#### **Siding**

- Annual inspection to correct defects in paint, joints, brickwork, or siding to prevent water intrusion
- Repair damaged brick on B Street façade

#### **Metal Elements**

- Replace missing finials
- Annual inspection to verify paint condition

#### **Wood Elements**

- Remove and replace exit stairway and landing on north side
- New exit stairway on the south side if balcony will be occupied (“full use” option)
- Reconstruct hip roof ventilator

#### **Windows and Doors**

- Refurbish (7) entry doors on 1863 Brick Building at B-Street
- Refurbish / rebuild Carriage House doors with arched entryway
- Refurbish (6) windows including storm windows at south and north elevations of 1883 Auditorium Building

## **Building Interior**

### **Basement**

- Building egress
- Handrails at arched openings

### **Auditorium Level**

- Catering Kitchen
- New wood floor assembly to support hydronic heating
- Annual testing for flame retardancy
- Table and chair storage
- Accessible means of egress (ramp)
- Repair / refurbish ladder to landing platform above stage

### **Balcony**

- Complete stairs to Balcony Level
- Repair / refurbish flooring, pews, wainscoting (“as-exists” option)

### **Attic**

- Repair / reinforce wood grid floor

## H PHASING AND COSTS

### 1.0 Phasing

Preservation and restoration recommendations are presented as a phased approach to allow Storey County to allocate funding judiciously based on the most pressing life safety needs. We have grouped repairs into three categories or phases:

- Priority I:** Life Safety, including but not limited to structural stabilization and egress
- Priority II:** Repairs, including but not limited to repointing, changing out fixtures, repair or replacement of missing or damaged historic fabric
- Priority III:** Improvements, including but not limited to evaporative cooling, catering kitchen, upgraded electrical

### 2.0 Costs

We have provided a range of costs from low to high for each item on the next page. The items are presented in order of importance for Priority 1 but there is no sequential order of importance within the remaining two priority groups.

Priority	Item	Task	Estimated Cost Range	
I	1	Lobby Column	\$ 30,000.00	\$ 50,000.00
	2	Roof Truss Support	\$ 80,000.00	\$ 120,000.00
	3	Wall Columns	\$ 8,000.00	\$ 8,000.00
	4	Add emergency egress lighting	\$ 5,000.00	\$ 7,000.00
	5	Basement level building egress (interior)	\$ 15,000.00	\$ 17,500.00
	6	Pave loading dock to B Street	\$ 3,100.00	\$ 4,500.00
	7	Additional power receptacles at balcony	\$ 2,000.00	\$ 5,000.00
	8	Install backflow preventer	\$ 2,500.00	\$ 4,000.00
	9	Install pressure reducing valve	\$ 500.00	\$ 1,000.00
	10	Accessible ramp from north side auditorium	\$ 12,000.00	\$ 15,000.00
<b>Priority 1 Subtotal</b>			<b>\$ 158,100.00</b>	<b>\$ 232,000.00</b>
II	11	West building wall / water infiltration	\$ 337,500.00	\$ 405,000.00
	12	A Street roadway improvements	\$ 750,000.00	\$ 850,000.00
	13	Complete stairs to balcony	\$ 8,500.00	\$ 12,500.00
	14	Balcony repairs "as-exists" option	\$ 15,000.00	\$ 20,000.00
	15	Restroom exhaust fans	\$ 2,500.00	\$ 5,000.00
	16	Repoint / repair mortar & brick at Old Corner Bar	\$ 3,500.00	\$ 7,000.00
	17	Replace missing finials	\$ 500.00	\$ 500.00
	18	Refurbish (7) front entry doors	\$ 105,000.00	\$ 126,000.00
	19	Replace exterior egress stairs north side	\$ 8,500.00	\$ 12,500.00
	20	Refurbish ladder	\$ 2,500.00	\$ 3,500.00
<b>Priority 2 Subtotal</b>			<b>\$ 1,233,500.00</b>	<b>\$ 1,442,000.00</b>
III	21	Add 60-gallon capacity water heater	\$ 5,000.00	\$ 8,000.00
	22	Add auditorium hydronic heating	\$ 120,000.00	\$ 140,000.00
	23	Add auditorium evaporative cooling	\$ 50,000.00	\$ 70,000.00
	21	Add direct ventilation	\$ 35,000.00	\$ 60,000.00
	25	Reconstruct hipped roof ventilator	\$ 4,000.00	\$ 5,500.00
	26	Additional framing for evaporative cooling	\$ 75,000.00	\$ 80,000.00
	27	Upgrade electrical service to 600A	\$ 20,000.00	\$ 40,000.00
	28	New catering kitchen	\$ 35,000.00	\$ 50,000.00
	29	Upgrade kitchenette panel size	\$ 7,000.00	\$ 10,000.00
	30	Prep (2) openings for Carriage House doors	\$ 20,000.00	\$ 30,000.00
	31	Reburbish / rebuild (2) Carriage House doors	\$ 36,000.00	\$ 40,000.00
	32	Add emergency generator	\$ 50,000.00	\$ 75,000.00
	33	Balcony repairs "full use" option	\$ 200,000.00	\$ 250,000.00
	34	Add exterior egress stairs south side balcony	\$ 9,000.00	\$ 13,500.00
<b>Priority 3 Subtotal</b>			<b>\$ 666,000.00</b>	<b>\$ 872,000.00</b>
<b>Subtotal Net Construction Costs</b>			<b>\$ 2,057,600.00</b>	<b>\$ 2,546,000.00</b>
<b>Gross Construction (+ 35% for General Conditions)</b>			<b>\$ 2,777,760.00</b>	<b>\$ 3,437,100.00</b>
<b>Add for balcony "full use" option</b>			<b>\$ 249,750.00</b>	<b>\$ 310,500.00</b>

## I APPENDICES

- 1.0 Structural Report
- 2.0 List of Prior Grants 1995 – 2009
- 3.0 Bibliography of Record Drawings 1995 – 2009
  - Historic American Buildings Survey Piper’s Opera House
  - Reroof of Piper’s Opera House
  - Phase One Restoration of Piper’s Opera House
  - Phase 2-b Siding for Piper’s Opera House
  - Elevator for Piper’s Opera House
  - Elevator Shop Drawings
  - Piper’s Opera House Façade Stabilization
  - A Historic Restoration for Piper’s Opera House
  - Theater Renovation
  - Piper’s Opera House Electrical Asbuilt
  - Loading Dock and Driveway Improvements to the Piper’s Opera House
  - Restroom Improvements to the Piper’s Opera House
- 4.0 Plans

## **1.0 | STRUCTURAL REPORT**



## INDEX OF CONTENTS

<u>SUBJECT</u>	<u>PAGE NUMBER</u>
INTRODUCTION	1
BACKGROUND	2
Historic Topographical Considerations for Siting the Building	2
Ground floor	2
Second floor	2
Balcony & attic	2
Structural Construction of the Building	2
Roof trusses and framing	2
Balcony	3
Wall framing	3
Second floor framing	3
Front (east) brick wall façade	3
Rear (west) wall	3
Structural Engineering and Construction Considerations	3
Unreinforced brick masonry	4
Existing Capability of Piper's to resist seismic forces	4
Building site considerations	4
MAJOR PREVIOUS STRUCTURAL DEFICIENCY REPAIRS	5
Front (east) and South Wall Stabilization (October, 2011)	5
Structural deficiency	5
Repair concept (Appendix A construction documents)	5
Percent completion	6
Auditorium Floor Strengthening & New Entry Stairway (2005 budget projects)	6
Structural deficiency	6
Repair concept (Appendix B construction documents)	6
Percent completion	7
Roof Truss Framing (Appendix C construction documents)	7
Structural deficiency	7
Repair concept	7
Percent completion	7
North Wall Column Bucking, Roof Truss #4 Support	7
Structural deficiency	7

Repair concept	8
Percent completion	8
Balcony Framing and Support	8
Structural deficiency	8
Repair concept	8
Percent completion	9
West Wall of the Building	9
Structural deficiency	9
Repair concept	9
Percent completion	9
Water Infiltration/Drainage at the West Wall of the Building	9
Structural deficiency	10
Repair concept	10
Percent completion	10
<b>MISCELLANEOUS STRUCTURAL CONDITIONS</b>	<b>10</b>
Column at the Entry Lobby	10
Structural deficiency	10
Repair concept	10
Percent completion	11
North Balcony Exit Stairs	11
Structural deficiency	11
Repair concept	11
Percent completion	11
<b>DISCUSSION</b>	<b>11</b>
Front (east) and South Wall Stabilization	11
Auditorium Floor Strengthening & new Entry Stairway	12
Roof Truss Framing	12
North Wall Column Bucking, Roof Truss #4 Support	12
Balcony Framing and Support	13
1). "As existed" option	13
2). Retrofit option for full use	13
West Wall of the Building	14
Water Infiltration/Drainage at the West Wall of the Building.	14
Column at the Entry Lobby	15
North Balcony Exit Stairs	15

<u>SUBJECT</u>	<u>PAGE NUMBER</u>
<b>CONCLUSIONS</b>	<b>15</b>
Roof Truss Support	16
Wall Column Buckling	16
Column at the Entry Lobby	16
Auditorium Floor Support	16
West Wall of the Building/ Water Infiltration/Drainage	17
Balcony Framing and Support	17
As-exists option	17
Code conforming upgrade option	17
Repair cost options	18
<b>RECOMMENDATIONS</b>	<b>18</b>
Project Cost Estimates for Structural Repair Recommendations	19
<b>APPENDIX A</b>	<b>20</b>
<b>FRONT (EAST) WALL STRENGTHENING/REPAIR</b>	
Ferrari Shields Construction documents May 14, 2002, sheets S-1 through SD-2	
<b>APPENDIX B</b>	<b>21</b>
<b>2005 BUDGET PROJECTS – AUDITORIUM FLOOR STRENGTHENING &amp; NEW ENTRY STAIR</b>	
Ferrari Shields Construction documents dated May 20, 2005, sheets SN-1 through SD-3	
<b>APPENDIX C</b>	<b>22</b>
<b>ROOF TRUSS STRENGTHENING/REPAIR</b>	
Ferrari Shields Construction documents dated December 28, 2010, sheet S-1 P&F Consulting report dated January 6, 2017, plates 1, 2	
<b>APPENDIX D</b>	<b>23</b>
<b>ROOF TRUSS &amp; NORTH WALL COLUMN STRENGTHENING/REPAIR</b>	
Ferrari Shields Construction documents dated December 28, 2010	
<b>APPENDIX E</b>	<b>24</b>
J.D. Copolous July, 1997 NORTH WALL COLUMN/BEAM REPAIR DOCUMENTS	
J.D. Copolous February, 1998 FLOOR REPAIR CONSTRUCTION DOCUMENTS	

# PF Consultants LLC

## Consulting Engineers

P.O. Box 1369 Verdi, Nevada 89439

775-771-1720

April 20, 2020

PF#4-15-20

Dube Group Architects  
458 Court Street  
Reno, Nevada 89501

Attention: Pete Dube, President

Subject: Amendment to Historic Structures Report for Piper's Opera House, Virginia City, Nevada Structural Engineering Aspects.

Dear Pete,

The following report is the structural component of the *2020 Amendment to Historic Structures Report for Piper's Opera House, Virginia City, Nevada*. In order to properly develop and understand the structural aspect of the report, it is necessary to understand how the building was integrated into the steeply sloped site between B and A Streets, as well as how the building was constructed. The following Background Section will provide a baseline of understanding by reviewing the past structural retrofits, emergency structural repairs, and previous structural studies.

As an engineer, I have been involved in the structural stability of Piper's Opera House for the past twenty years. During that span of time, I have engineered over five major structural repairs/retrofits of the building structure, including emergency structural repair as well as many more minor actions. After the pertinent background information has been presented, I will review the structural configuration of the building, and the major structural activities that I have performed on the building: Front (east) and South Wall Stabilization (October, 2001), Auditorium Floor Strengthening and New Entry Stairway (2005 budget projects), Roof Trusses and Framing, Wall Framing/Roof Truss Support. The preceding aspects will be buttressed by supplemental information gathered from field site visits. I will then develop a conceptual structural retrofit/repair concept for the future use of the building. This conceptual structural retrofit/repair concept for the future use of the building will provide a basis for budgetary planning and a prioritized structural life/safety retrofit for the future use of the building.

## **BACKGROUND**

### **Historic Topographical Considerations for Siting the Building.**

The architectural concept of the Piper's Opera House building was dictated by the topography of Virginia City. The building is located on an east to west 30' upslope from B Street to A Street. This slope necessitated a "stepped", multi-level floor plan to accommodate the elevation change.

**Ground floor.** The first floor plan (ground floor entrance at B Street) includes the "Corner Bar" (at the southeast corner), the main entrance lobby and stairway at the center of the building, and the "carriage" house at the northeast corner of the building. The ground floor is cut level back into the existing slope of the site approximately 56 feet to maintain the grade for the ground level and the ground floor uses. At that point, a dirt slope extends upward to a crawl space that supports the second floor (main auditorium floor) structure. The crawlspace height decreases from 5'- 6' at the top of the slope to approximately 3' to the north under the front of the stage.

**Second floor.** The stairway at the center of the building at the ground floor provides access to the main (second floor) auditorium level. The majority of the main auditorium level is supported by brick piers extending from the ground level of the crawlspace to the bottom of beams supporting the auditorium floor.

**Balcony & attic.** The main stairway continues up from the auditorium level to the balcony level which provides access to the two balcony "wings" bordering along the north and south walls. From the balcony level, a ladder accesses the attic level roof trusses and framing.

### **Structural Construction of the Building.**

The construction concept of Piper's Opera House was typical of the Comstock heyday. It was intended to be constructed as quickly as possible to be able to perform its intended function; it was never designed and constructed with the intention that the building last well over a century. With this consideration, the building structure is in remarkable condition for a building entering its second century. The construction of the building will be related in the following paragraphs, beginning with the roof structure.

**Roof trusses and framing.** The roof framing structure consists of a hand-cut and fit heavy timber construction, which along with steel tension tie rods, comprises a rudimentary "truss" member that spans 53' at approximately 8' on-center (see plate S-1, cross-section B-B, page 2a). The gambrel shaped roof ridge is constructed by infill stud framing members that extend from the top of the horizontal top truss chord to the roof ridge. The "truss" is not like a modern engineered truss, in which triangular section comprise the structural load resisting path of the member. Of particular concern is the geometric configuration where the top and bottom chord of the "truss" are supported by the vertical wood column in the wall. The preferred configuration of this joint is to have the centerline of the diagonal top chord and the bottom chord to intersect at a point over the top of the supporting column. Instead, the diagonal top chord stops short of the column by approximately 2' from the supporting column where the diagonal member load is transferred to the lower chord member. This configuration results in half of the total load on the truss diagonal having to be transferred via the 2' offset to the supporting column causing bending in the bottom chord of the truss. By definition, truss

PIPPER'S OPERA HOUSE  
 VIRGINIA CITY, NEVADA  
 ROOF TRUSS & WALL STRENGTHENING

STRUCTURAL PLAN & DETAILS


FERRARI SHIELDS & ASSOCIATES  
 Consulting Engineers and Cost Engineers  
 183 Chicago Place  
 Reno, Nevada 89509  
 775-328-2577  
 www.ferrarisshields.com



NO.	REVISION

DATE	DESCRIPTION

S-1



(E) BLDG.  
 CROSS-SECTION B-B  
 SCALE 1/8" = 1'-0"

ROOF COLUMN SECTION A  
 SCALE 1/4" = 1'-0"

FLOOR PLAN  
 SCALE 1/8" = 1'-0"

members are supposed to be subject to only axial tension or compression loads. The 2' offset of the load transfer creates a bending moment couple in the bottom chord, in addition to the tension force that the lower chord is also carrying. This condition causes a significant increase in the tension/bending stresses in the lower chord, and has proven to be problematic, as will be explained in the *Roof Truss Repair* section of this document.

**Balcony.** The balcony framing joists are supported by a perimeter beam at the interior edge of the balcony and the exterior wall at the other end. The perimeter beam at the edge of the balcony is supported by vertical steel tension rods. The tension rod load is transferred to a horizontal beam in the attic that is resting on top of the lower chord, spanning between the "trusses". The wrought iron tension rods are anchored by a steel plate at the bottom of the balcony beam, and extend upward through a hole in the bottom of the balcony beam through a hole in the upper beam at the trusses where the rod is also anchored by a steel bearing plate. The rods are anchored at both ends by a steel plate and a nut (see plate S-1, page 2a).

**Wall framing.** The height of the auditorium wall is approximately 30'. For the majority of the length of the building, the wall is buttressed at mid height by the balcony framing. Each of the roof trusses is supported by an 8"x8" wood column. Because of the 30' wall height, the column has to be butt spliced (end to end) at the midheight (see plate S-1, page 2a). Although the splice is stabilized by wood side members, this splice is problematic, and a source of structural instability, as will be explained later.

**Second floor (auditorium) framing.** As previously stated, the second floor framing over the crawlspace is supported by brick piers. The inclusion of a 10" diameter x 6" high coiled wrought iron springs between the floor framing beam and the top of the supporting brick piers provide a "sprung" floor system. This system provided a "forgiveness" and damping of floor vibrations caused by activities such as dances.

**East (front) brick wall façade.** The east (front) wall of the building is composed of unreinforced, two-story, brick masonry. The mortar is a slacked lime mortar that has no inherent tension/structural capability. The brick lintels, over the ground floor entrance openings and windows were constructed by stacking brick upon a horizontal steel fire door that served as the structural support for the opening. The entire east brick wall is "leaning" outward, over 4" away from the building at the top of the wall.

**West (rear) wall.** The west (rear) wall of the structure is a wood framed wall. The back of the building is situated on a plateau in the hillside against the slope that extends upwards and supports A Street.

### **Structural Engineering and Construction Considerations.**

It is important to remember that the Opera House construction delineated above is not indicative of shoddy construction or workmanship. To the contrary, the carpentry was very well done, and performed by workmen who installed the intricate square-set wood timbering in the depths of the Comstock mines. The construction of the building is indicative of the "state-of-the-art" in construction and engineering practices prevalent over one hundred and twenty years ago. However, the 1870's engineering state-of-the-art was not versed in seismic load path engineering. Furthermore, the construction materials and techniques in common practice then did not provide a consistent level of

quality and/or performance; these considerations will be addressed in the following paragraphs.

**Unreinforced brick masonry.** The unreinforced brick masonry comprising the two story front entry façade at the east wall is a specific example of construction materials that are extremely problematic in areas such as Virginia City that are subject to potentially large earthquakes. The bricks themselves are not fully fired, and have a soft interior. However, the mortar bedding the bricks is not a cementitious mortar; cement mixed into the mortar is the ingredient that provides the mortar with engineered strength to create a unified structural component. The mortar in the front wall consists of sand, lime, and water (slacked lime mortar). The lime mortar is suitable for bedding the soft, partially fired brick of the Comstock, but it does not provide any structural strength to the wall assembly that would be necessary to resist earthquake forces. In particular, earthquake forces tend to create a “pull away” force where the wall is peeled away from the building and causes structural collapse. In its current status, the wall is, indeed, pulled away from the building approximately 4” to the east at the top of the wall.

**Existing capability of Piper’s to resist seismic forces.** As was outlined in preceding paragraphs, the 1870’s engineering state-of-the-art was not versed in lateral seismic load path engineering. However, that does not imply that the building has no inherent lateral load resistance capabilities. Historic materials and construction have been found to have a certain degree of capability to resist lateral loads. For typical buildings similar to the Opera House, a lateral load system consists of a horizontal roof/floor diaphragm spanning between vertical “shearwalls” that transfer the lateral load forces contributed by the roof/floor diaphragm to the ground, where they are resisted.

In the longitudinal (east/west) direction, the long, mostly solid north and south wood framed walls of the building provide enough length that the unit in-plane shear stress in the walls is very low, and thus not a concern, especially since the walls have been sheathed with plywood. Also, the fact that the building is cut into the slope helps to stiffen the building.

In the transverse direction (north/south), there are few structural shearwalls that were capable of providing a lateral load resisting system for the building. The front unreinforced brick masonry wall was in a state of instability and not capable of providing any lateral load capacity. The west wall of the lobby, east (rear) wall of the auditorium, was a plank-sheathed full height (2 story) high wall. This wall provided some lateral load capacity for the building. The next transverse wall capable of providing lateral load capacity is the rear (west) wall of the building at A Street.

A lateral load system need to be in place for both the longitudinal and transverse axis of the building.

**Building site considerations.**

There are two main concerns regarding the siting of the building in the hillside: the slope of the hillside (A Street) sloughing against the rear wall of the building, and a subterranean spring that runs through the crawlspace of the building.

The fill slope supporting A Street to the west of the building has sloughed downhill over the years and is building up and impacting the west wood wall of the building. If it continues, it could affect the structural stability of the wall.

A subterranean spring flows from the cut slope at A Street down under the crawlspace of the building, and exits under the southeast corner of the Corner Bar; this



can cause structural problems to the building. The spring should be intercepted at the A Street cut and integrated into a french drain which would by-pass the building.

## **MAJOR PREVIOUS STRUCTURAL DEFICIENCY REPAIRS**

As noted in the introduction of this report, as an engineer, I have been involved in the structural stability of Piper's Opera House for the past twenty years. During that span of time, I have engineered over five major structural repairs/retrofits of the building structure, including emergency structural repair as well as many more minor actions.

The major structural retrofits will be presented. The structural deficiency that was corrected will be identified, the structural repair plans/concept will be presented (where applicable construction documents will be presented in appendices), and the percent of completion will be indicated. The repair concepts, are presented in the following paragraphs:

### **Front (east) and South Wall Stabilization Lobby Shearwall (October, 2001).**

**Structural deficiency:** The east and south walls of the building are composed of unreinforced, two-story, brick masonry. The mortar is a slacked lime mortar that has no inherent tension/structural capability. The entire east brick wall was "leaning" outward, over 4" away from the building at the top of the wall. The immediate structural problem was that of the ultimate stability of the wall; the 4" outward lean could have eventually progressed to the point where the entire front wall could have collapsed. Also, the front brick wall was very susceptible from collapse due to out-of-plane and perpendicular seismic forces from earthquakes. Likewise, the south wall also exhibited the same weaknesses as the front wall.

**Repair concept (see Appendix A for construction documents):** The front (east) wall of the Opera House is the historic face of the building. As such, it was of utmost importance that the architectural characteristic of the wall be retained in any structural repair concept, while integrating appropriate structural capability into the wall. This was accomplished by initially providing extensive shoring of the east and south walls; the shoring was designed so that access to critical portions of the walls that were designated for reconstruction could be easily accessed. With the shoring in place, the 12"x20" existing brick pilasters at the interior face of the wall were removed, to be replaced with similar dimensioned reinforced concrete (see section B-B/SD-2, Appendix A). This kept two wythes of the outside face brick in place. The exterior face brick wythes of the wall were reinforced by the insertion of *Dur-O-Wall* friction pins drilled into the back of the face brick and the opposite ends of the pins anchored in the new concrete pilaster (see detail B-B/SD-2, Appendix A). The new friction pins enhanced the stability of the exterior brick wythes, while the new concrete frame provided both in-plane and out-of-plane strength, essentially re-building the walls from within to a capable structural system while maintaining the historic integrity of the exterior of the building. The extent of the new reinforced concrete frame is shown on sheets S-4, 5 Appendix A. The 4" lean of the front wall to the east (away from the building) was maintained, since trying to re-plumb the front wall would have caused considerable damage to the wall. However, the new reinforced concrete frame was capable of

providing structural integrity to the wall in-place with the 4" deflection. Further stability for the new concrete wall was provided by tying the new concrete structure into the roof diaphragm structure, assuring both out-of-plane and in-plane lateral forces can be resisted (see details DD/SD-2 and KK/SD-2 Appendix A). The integration of the new reinforced concrete frame (covered with plaster similar to the original condition) into the fabric of the existing historic east wall was performed in such a manner that the historic visage of the wall was maintained while the structural deficiencies inherent in the original construction were remedied. Also, the west lobby wall, adjacent to the auditorium was sheathed with plywood to develop added north/south seismic capability.

**Percent completion:** The front wall stabilization and strengthening and the west lobby wall shear sheathing were completed 100% in accordance with the plans presented in Appendix A.

### **Auditorium Floor Strengthening and New Entry Stairway (2005 budget projects).**


**Structural deficiency:** The existing brick pilaster piers supporting the main auditorium floor framing suffered significant deterioration which compromised their structural integrity to support the main floor framing. Compounding the structural instability was the fact that many of the brick piers were supported on the sloping grade of the cut slope. The sloped ground was compromised when ground water seeping through the grade caused the brick piers supporting the floor framing to become unstable.

**Repair concept (see Appendix B for construction documents):** In February, 1998, a floor repair/strengthening was undertaken for the first (eastern) 40' of the existing floor (J.P. Copolous Architect plans, Appendix E). The scope of work extended from the east wall of the building to the east wall of the auditorium; also included were foundation and wall to floor attachments.

The 2005 Ferrari Shields budget project was designed to address the brick pilaster deterioration supporting the floor framing in the auditorium at gridlines 2, 3, 4 (see sheet S-1, Appendix B). The cut bank slope was sloughing, causing structural distress in the brick pilasters. Because of the slope instability, the existing brick pilaster foundation at grid 3 had to be abandoned. In order to accomplish this, new concrete foundations were constructed at the top (gridline 4) and the bottom (gridline 2) of the slope. New, 20' long, structural steel "C" channels were "sistered" on each side of the existing 10"x10"x10'-0" long wood beam supporting the auditorium floor framing (see detail 112/SD-1, and sheet 1/1, Appendix B, and page 6a respectively). The new steel beams span 20' from the new concrete footing at the top of the slope to the new concrete footing at the bottom of the slope, by-passing the failing brick pilaster at the mid slope (gridline 3). This concept addressed the distressed pilaster footings at gridlines 2, 3, and 4. New beams/footings (5 total) were constructed across the entire width of the building (gridlines B, C, D, E, F, G).

As part of the 2005 budget projects, a new, wider-width stairway was constructed. Also included in this phase of repair was the installation of a large gravel drainage trench, adjacent to the bottom of the cut slope, to collect and channel ground water seepage away from the ground floor of the building, especially the Corner Bar at the southeast corner. The ground water seepage has had a deleterious effect on the

NO SCALE



stability of the cut slope and the brick pilaster foundations. The location of the drainage trench is shown on sheet S-1, Appendix B.

**Percent completion:** The auditorium floor strengthening, new stairway, and new gravel drainage trench were completed 100% in accordance with the plans presented in Appendices B, E.

### **Roof Trusses and Framing.**

**Structural deficiency:** The roof framing structure consists of a hand-cut and fit heavy timber construction, which along with steel tension tie rods, comprises a rudimentary “truss” member that spans 53’ at approximately 8’ on-center (see plate S-1, cross-section B-B, Appendix C). As stated earlier in the *Structural construction of the Building*, page 2, “Of particular concern is the geometric configuration where the top and bottom chord of the “truss” are supported by the vertical wood column in the wall. The preferred configuration of this joint is to have the centerline of the diagonal top chord and the bottom chord to intersect at a point over the top of the supporting column. Instead, the diagonal top chord stops short of the column and the column supporting the lower chord of the truss is offset by 2’ short of the column.” This configuration induces bending stress in the lower chord of the truss, which should only be subject to axial tension forces. The resulting increased bending stress in the lower chord resulted in an axial cracking failure of the wood lower chord (see photo 1, Appendix C). This structural failure was first noted in 2006. Several truss locations were repaired with plywood layers on each side of the connection (see photo 2, Appendix C) or, in the more severe cases, steel angles (see photos 1, 2 Appendix C).

**Repair Concept (see Appendix C):** In December, 22-28, 2016, a critical failure of this condition, that could cause a catastrophic failure, was noted at the north support of truss #4; the bottom chord of the truss had severe longitudinal cracking (see photo 1, Appendix C). On January 6, 2017, I prepared a report regarding the cause of the failure and a method of repair (see January 6, 2017 P&F Consulting report, Appendix C). Plates 1, 2 of the January 6, 2017 P&F consulting report present repair plans for the cracked beam; photo 3, plates 1, 2 A; Appendix C shows this repair in the as-installed condition.

**Percent completion:** The severely cracked lower chord at truss 1 north has been repaired. Also, three other locations have been strengthened with the plywood “sistering” as shown in photo 2 Appendix C. However, there are twelve other locations that should also be strengthened; this criteria will be addressed in the Discussion section of this report.

### **North Wall Column Buckling, Roof Truss #4 Support.**

Each of the roof trusses is supported by an 8”x8” wood column; because of the 30’ wall height, the column had to be butt spliced (end to end) at the midheight (see plate S-1, Appendix D). In early 2010, the north column of truss #4 began showing a buckling at the column butt splice. Over intervening months, the condition worsened, the column butt splice began “kneeing”, buckling outward, over 9” at the mid height of the wall. Because the situation was stability based, and not based on internal member strength, the condition required immediate attention in order to prevent a catastrophic

structural collapse. This condition was also noticed and repaired at truss #2, north wall, in 1997 by Copoulos/Green (Appendix E).

**Structural deficiency:** The potential column buckling is a stability concern for life/safety. If the column buckling passes its metastable position, the column will fail, and the roof truss and roof framing it supports will suffer a catastrophic collapse that severely damages the building and causes a significant life/safety concern for building occupants.

**Repair Concept (see Appendix D):** In December, 2010, I prepared a set of repair plans to rectify the column instability (see sheets S-1, SD-1, appendix D). The “kneed” column was first stabilized with a midheight diagonal brace at the exterior. Once the column was stabilized, it was reinforced by “sistering” a HSS 3”x7”x5/16” steel tube column, full height, on each side of the wood column (see sheets S-1 and SD-1, and photos 1, 2, 3, Appendix D).

**Percent completion:** The distress condition at truss #4 north wall was repaired 100% according to the repair documents presented in Appendix D.

**Balcony Framing and Support.** As was stated in the *balcony section* of the *Structural Construction of the Building* on page 2, the balcony framing joists are supported by a perimeter beam at the edge of the balcony and the exterior wall at the other end. The perimeter beam at the edge of the balcony is supported by vertical wrought iron tension rods, which in turn, are supported by a roof beam spanning between the roof trusses. The balcony extends along both the north and south walls, along with seating at the rear auditorium wall. The only access to the balcony seating is via a set of stairs up from the main auditorium access. The balcony “wings” have two rows of tiered bench seating, while the rear has 3 tiers. The seating areas are very problematic for actual use; the knee space is very limited and the slope of the balcony is severe.

**Structural deficiency:** Per current building code, the vertical live load a balcony must support is 100 pounds per square foot (psf). Because of its historic construction, the Piper’s balcony is not capable of meeting that life/safety criteria. The load path for the balcony includes tension rods suspended from roof framing to support half the balcony load; the tie rods are wrought iron, which is a very brittle steel and is subject to fracture under load which will cause a catastrophic collapse. Additionally, the wrought iron tension rods are anchored at the bottom of the balcony beam and at the top of the roof beam with small steel plates, secured with a nut that are intended to spread the load reaction from the rods onto the wood beams. However, some of these plate are of insufficient area to safely distribute the historic balcony loading, and are pulling into the wood, which eventually could be a structural problem.

**Repair Concept.** The entire balcony structure would have to be re-engineered and the existing load path members strengthened to accommodate the required (and expected) live load of people. Additionally, in order to reuse the balcony for future activities, additional emergency fire exits would have to be constructed at the west end of each balcony wing at the north and south walls. The emergency exits would have to exit to the outside of a building, and would require an exterior stairway to grade.

The feasibility of opening the balcony seating to use will be discussed in the Discussion and Recommendation sections of this report.

**Percent completion: (Not applicable).** During the repair of the buckled wall column at truss #4 north wall, some remedial actions were undertaken on the balcony framing while the canvas covering of the wall and balcony was removed for the column repair. The repair basically involved using metal connectors to attach the balcony floor joists to the perimeter balcony beam; this was undertaken when it was noticed that some of the nailing from the floor joist into the perimeter beam had pulled away and were in danger of failure. Other than that emergency repair to the joist/beam connection, no additional structural retrofit work was done to enhance or stabilize the existing condition of the balcony structural capability.

**West Wall of the Building.** As denoted in the *Building Site Considerations*” section of this report, page 4, the rear of the building was set back into a cut slope at the west. “A” Street. There is an approximate 30 foot elevation difference between the ground floor level of Piper’s and the A Street elevation; the east edge of A Street pavement is approximately 15 feet from the west wall of Piper’s. The east edge of the pavement at A Street has exhibited slope instability, and the width of the east traffic lane has been reduced due to sloughing of the dirt slope supporting the roadway. As the slope sloughs, the dirt moves downhill where it can pile up against the west wall of Piper’s.

**Structural deficiency.** The structural deficiency created by this condition is twofold: the instability of the A Street slope endangers both the west wall of Piper’s as well as the stability of A Street itself. As the dirt sloughed from the slope moves downhill, it builds up against the west wall framing. The accumulation of dirt against the wall introduces a horizontal bending force into the wall studs. With unabated soil build up, a bending moment in the studs is created that can cause a structural failure of the wall studs. Furthermore, continued sloughing of the slope supporting A Street could cause a complete slope failure where a significant portion of the roadway is demolished and moves downhill against the west wall of Piper’s. This slope failure could have enough kinetic energy that its impact against the west wall of the building could have a catastrophic effect, causing a building collapse from the front of the stage to the rear wall of the building.

**Repair Concept.** The repair concept for the structural deficiency explained in the paragraph above is not incorporated into the building itself, but is external to the structure. In order to stabilize the slope above the building, and supporting A Street, a new wall retaining and supporting A Street must be constructed to alleviate the danger to Piper’s. The water infiltration/drainage at the west wall (presented in the following paragraph) is also a comingled deficiency consideration.

**Percent completion: 0%** - no consideration of this deficient condition has been undertaken to rectify the slope instability.

**Water Infiltration/Drainage at the West Wall of the Building.** During the 2005 budget structural retrofit (see page 6), substantial amount of subterranean water flow was noticed emanating from the cut slope to the west. The amount of water appeared to be related to a subterranean spring fed by water higher up mount Davidson. The amount of water flow destabilized the slope supporting the auditorium floor (see Auditorium Floor Strengthening, page 6) requiring structural retrofit. The volume of water infiltrating the crawl space of the building was so high that a gravel drainage

trench had to be constructed to collect the seepage and channel it away from the building (see sheet S-1, Appendix B). The water accumulation was particularly high at the Corner Bar at the southeast corner of the building.

**Structural deficiency.** Flowing ground water in, around, and beneath a building is a cause for concern, as was evidenced in the deterioration of the existing brick pilasters supporting the auditorium floor at the crawl space slope. The groundwater flow is endemic to the building site, and, although it varies in intensity by each year's rainfall, the condition will not go away. If unresolved the cumulative nature of this condition can cause significant deterioration and structural distress in future years. This condition can be most critical at the bottom of the west wall, at the cut of the ground slope, where the cut slope intersects the groundwater flow line. The buildup of groundwater behind the wall and foundation can cause wood deterioration and foundation instability.

**Repair Concept.** The appropriate repair concept to intercept and redirect the ground water around the building is the installation of a "french" infiltration/intercept drain at the west wall of the building, adjacent to and below the foundation level. The drain, with the perforated pipe installed in a gravel-filled trench can be used to collect and divert the water from the west wall, around the building, where it will slope to "daylight" into above ground drainage channels at the north and south sides of the building. The infiltration/intercept trench can be constructed in coordination with the retaining wall stabilizing the A Street slope, as mentioned above.

**Percent completion: 0%** - no consideration of this deficient condition has been undertaken to rectify the groundwater infiltration into the building.

## MISCELLANEOUS STRUCTURAL CONDITIONS

The following paragraphs will discuss miscellaneous structural condition that need to be discussed, specifically, the column in the entry lobby near the stairway, and the north balcony exit stairs.

**Column at the Entry Lobby.** The existing 10"x10" column at grid lines 1.5/D.25, sheet S-1, Appendix B supports a large portion of the auditorium floor framing.

**Structural deficiency.** The existing 10"x10" wood column is bending to the south approximately 6" at the top. Typically, a column is only loaded axially. However, when the top of the column is offset (leaning) over the bottom of the column, a secondary bending moment stress, characterized as a "P\*delta" bending moment where "P" is the axial load, and "delta" is the offset or lean of the column. The bending moment not only results in additional stress that the column was not designed to withstand, but the column lean causes a structural instability which can engender a catastrophic collapse of all structure the column is supporting when the "tipping point" of lean is reached.

**Repair Concept.** The existing column has taken a permanent, curve. In order to correct the metastable position, it will be necessary to install temporary column shoring at each side of the leaning column and then using hydraulic jacks, lift the structure until the existing column loading can be transferred to a new column installed adjacent to the existing column, It may be necessary to construct a new concrete

foundation for the column, as well as structural connection hardware at the top and bottom of the column. When the new column is installed and secured, the temporary jacking columns can be removed.

**Percent completion: 0%** - no consideration of this deficient condition has been undertaken to rectify the lean and instability of the existing column.

**North Balcony Exit Stairs.** An exit stairway structure has been constructed at the north wall of the building, balcony level, near the stage.

**Structural deficiency.** The entire stairway structure, including the guardrail have been poorly constructed. It is unclear if the stairway structure had structural engineering and construction plans prepared. The construction appears to be poor, particularly at the critical guardrails.

**Repair Concept.** The actual need for the stairway structure is questionable, and would not be needed if the balcony is not used as an occupiable space. If it is decided the stairway is needed, the existing stairway structure should be torn down and reconstructed properly.

**Percent completion: 0%** - no consideration of this deficient condition has been undertaken to rectify the deficient stairway structure.

## DISCUSSION

This section will discuss structural deficiencies addressed in the MAJOR PREVIOUS STRUCTURAL REPAIRS/RETROFITS and the MISCELLANEOUS STRUCTURAL CONDITIONS sections, specifically”

- Front (east) and South Wall Stabilization
- Auditorium Floor Strengthening & new Entry Stairway
- Roof Truss Framing
- Wall Framing/Roof Truss Support
- Balcony Framing and Support
- West wall of the Building
- Water Infiltration/Drainage at the west wall of the Building
- Column at the Entry Lobby
- North Balcony Exit Stairs

The significance of the structural deficiencies with regard to life/safety and the continued use of the building will be addressed in its relative order of importance in terms of retrofit and repair/retrofit concepts. An associated, general budget to accomplish the work will also be estimated.

**Front (east) and South Wall Stabilization.** The front wall stabilization was perhaps the most significant repair that was needed in terms of immediate life/safety considerations. Anytime structural stability is in question, the structure is in a metastable condition, that is, it is relatively “stable” under the existing conditions, but if a small change occurs in the existing conditions, the structure could collapse. The May, 2002 structural strengthening of the wall (see Appendix A) not only strengthened the



wall for vertical loads, and in-plane and out-of-plane lateral forces, but it also stabilized the 4" outward lean of the wall while not changing the historic appearance of the exterior or interior appearance of the wall. **This structural deficiency has been completely eliminated, and no further action is required.**

**Auditorium Floor Strengthening & new Entry Stairway.** The February, 2006 structural retrofit and strengthening of the auditorium floor framing from gridlines 1.3 to 4 (see Appendix B, sheet, S-1), has eliminated the major concern regarding the deterioration of the existing brick pilasters supporting the auditorium floor framing at the dirt slope of the crawlspace. However, the stability of the dirt cut slope in the crawl space supporting the brick pilasters could be adversely affected by subterranean ground water seepage through the face of the slope. The competence of the brick pilaster should be periodically reviewed and repaired as needed. It should be noted that this condition can be aggravated by the infiltration of subterranean ground water

**Roof Truss Framing.** The structural deficiency resulting from the geometry of the offset of the top chord from the bottom chord and the column is both a structural strength and stability issue. In this regard, this is one of the most dangerous conditions that exist in the building because of the potential for a catastrophic collapse that can occur without warning. As was noted in my January 6, 2017 "*Review of roof truss deficiencies at Pipers Opera House*" Appendix C, the truss member cracking distress was noted in several other locations, as well as the north truss #4. This potential distress condition is endemic to the design and construction of the trusses and possess potential structural problems for the future that are of primary concern. **Of all of the structural deficiencies identified in this report, this condition is paramount to be addressed.**

There are approximately 14 of these truss/column connection conditions that have not been addressed. For the most of these conditions, a 1 1/8" plywood plate can be installed on each side of the truss/column connection per photo 3, Appendix C. As was noted in my January 6<sup>th</sup> report, page 2, "...an inventory of the condition of each truss should be undertaken". An annual observation of the trusses should be undertaken and compared to the baseline observation to detect any changes. Most likely, a majority of the trusses have not suffered cracking that could lead to failure. However, as a preemptive action, all of the non-damaged truss/column connections should be reinforced; the plywood gusset repair method could be used for these locations. For the remainder of the conditions, where cracking is evident, the more expensive triangular steel support (plate 1, 2, and photos 1, 2, appendix C) must be used. Because these retrofits are not easily installed in the attic space of the building, construction will be more costly. **Therefore, a budget allowance of between \$80,000 to \$120,000 should be set aside.**

**North Wall Column Buckling, Roof Truss #4 Support.** Like the roof truss condition, the potential column buckling at the north and south walls is life/safety stability issue. However, in the century plus that the building has stood, only two condition, both at the north wall, occurred. Although this is a critical condition, it appears that the likelihood of a critical occurrence is relatively small. Therefore, a

survey of the both the north and south walls at the midheight column splice should be undertaken as a baseline to determine existing location of the columns. An annual inspection of the north and south wall should be undertaken visually to ascertain if movement has occurred. If it appears that movement has occurred, a new survey should be taken at that location and compared to the baseline survey; If there is evidence of movement, the condition should be repaired similar to the plans in Appendix D. **Therefore, a budget allowance of \$8,000 should be set aside for the baseline wall survey.**

**Balcony Framing and Support.** The projected utilization of the balcony in the future plans of Piper's will directly affect the structural scope of retrofit that must be undertaken, and therefore, the overall cost of retrofit. The two divergent courses of use are: 1). leave the balcony "as exists", and use it only as a historic aspect of the building that is not utilized for public occupancy (except for miscellaneous activities, such a lighting, historical tours, etc.); or, 2). retrofit the balcony to current code requirements and utilize the seating to add to the capacity of the theater. The two preceding options have very different cost parameters.

**1). "As exists" option:** With this option, the balcony is not upgraded structurally for full code occupancy, and, as such, requires no structural upgrade and therefore encounters little associated expense. With this option, the balcony would be repaired as needed to return it to its original configuration. The balcony would not be utilized for occupancy seating, but would be viewed as an example of the original balcony configuration and could be viewed as a historic artifact of the original intent of the building. The structural costs for the "as exists" alternative would be as follows:

**Structurally**, the only criteria would be to repair the existing balcony construction as needed to reflect its original construction. Several areas of missing or damaged framing members exist in both the floor and the walls of the balcony. The repair work would be relatively minimal. **The structural cost for the "as exists" option 1 would be relatively minimal and be limited to basically maintenance items and carpentry. An allowance of \$15,000 to \$20,000 should cover the scope of work for this item.**

**2). "Full use" retrofit option:** This option would entail the structural and architectural upgrade of the balcony in order to have a code-conforming structure that could be used for full occupancy seating. In order to accomplish this, structural and architectural aspects must be incorporated into a current code-conforming balcony.

**Architectural**, a new exterior exit stairway must be installed at the south wall, and the existing, deficient stairway at the north wall has to be demolished and rebuilt in order to qualify for exiting from the balcony.

**Structural**, in order to upgrade the balcony for the full code live and dead load, the entire balcony structure must be analyzed and upgraded structurally as required. Specifically, the balcony perimeter beams must be reinforced, the vertical tension rods, and the roof beam supporting the tension rods must be reinforced/replaced. The steel bearing plates attaching the vertical tension rods at the top and bottom beams must be removed and replaced with properly sized plates to prevent the tension rods from pulling through the top and bottom beams. However, the most significant problem is the vertical tension rods. The rods are wrought iron, and as such, have a low allowable

tension stress. As such, the code vertical and dead load are of a magnitude that the diameter of the rods and their spacing are not adequate to support the code loads of the balcony. Therefore, either the historic, existing tension rods have to be removed and replaced with steel rods, or additional rods have to be retrofit into the existing configuration. This would alter the historic configuration of the balcony. **The “full use” option 2 would require a substantial retrofit cost that would result in only a marginal benefit of additional seating that may never be needed; therefore, I do not believe the retrofit option for full use is viable, however, should the decision be made to open the balcony to full use, a budget of \$200,000 to \$250,000 should be set aside (the estimate includes the construction of emergency exit stairways at the north and south walls).**

**West Wall of the Building.** This structural consideration, unlike all of the preceding structural deficiencies, is not related to the building itself, but is an outside factor that is not under the control of the building itself. As denoted in the *Building Site Considerations* section of this report, page 4, the rear of the building was set back into a cut slope at the west. “A” Street. There is an approximate 30 foot elevation difference from the ground floor level of Piper’s and the A Street elevation; the east edge of A Street pavement is approximately 15 feet from the west wall of Piper’s. The east edge of the pavement at A Street has exhibited slope instability, and the width of the east (north bound traffic lane) has been reduced due to sloughing of the dirt slope supporting the roadway. As the slope sloughs, the dirt moves downhill where it can pile up against the west wall of Piper’s”. Although this is not an imminent threat, the continued instability of the cut slope below A Street can become a significant structural concern. If the cut slope fails and moves downhill, it can impact the west wall framing and cause a failure of the wall.

Unlike the other potential structural concerns within the building itself, this condition cannot be directly addressed by Piper’s itself. The failure of the cut slope extends into the Storey County right-of-way beneath A Street. As such, it is likely that the stability of A Street will have to be addressed by Storey County Public Works. Any effort to independently stabilize the cut slope at the toe of the slope could destabilize the entire height of the slope. **Because of the question of jurisdiction of the site, a repair cost will not be estimated.**

**Water Infiltration/Drainage at the West Wall of the Building.** As was noted in the *Auditorium Floor Strengthening* repair section, page 6, the existence of ground water seepage was noted in the cut face of the dirt slope in the crawlspace when the auditorium floor was strengthened. As a result, a gravel collection area was installed to aid in the transport of water from that area of the crawlspace. However, the gravel collection area was not intended to be a remedy for the groundwater seepage, but merely an aid to remove and prevent water from collecting. The proximate cause of the water seepage into the crawlspace is related to the *Topographical Considerations for Siting the Building*, as explained in that section in page 2 of this report. When the building was sited into a cut slope in the existing topography to the west of the building, a subterranean aquifer was exposed, which is the source of the ground water seepage noted in the crawlspace.

In order to intercept and redirect the aquifer seepage around the building, a “french” drain (a gravel filled trench with a perforated PVC pipe) should be installed below foundation grade at the west wall of the building and the intercept pipe directed around the building to daylight grade. **However, the french drain cannot be installed without destabilizing the already unstable cut slope supporting A Street. Any remedial action to install the french drain must be paired with and part of the stabilization of A Street (see preceding paragraph).**

**Column at the Entry Lobby.** As was indicated in the *MISCELLANEOUS STRUCTURAL CONDITIONS* section, page 10, the column lean creates a stability concern which is dangerous, since the condition could give no advanced warning of failure, but could cause a catastrophic failure without any notice, causing a significant life/safety concern. Per the repair concept listed on page 10, the column need to be re-plumbed. In order to accomplish this, once the column contributing structure is jacked up, the bottom of the column should be leveled with the top, and a new concrete footing constructed. **The cost for this repair construction should range between \$30,000 and \$50,000.**

**North Balcony Exit Stairs.** The current structural condition of the north balcony exit stairs is an unsafe condition. The guardrails are not properly attached to provide proper code-compliance, and the stairway structure itself is questionable. This item, in itself, should not be subject to repair consideration. In its current state, with the balcony not under consideration for occupancy, the exit stairway is not required. To save funds that can be better utilized to correct serious structural consideration, the exit door of the stairway should be barricaded, and the stairway abandoned in place. If, it is decided to retrofit the balcony into a fully code conforming structure, new exit stairways will have to be constructed. **The cost of the new exit stairways is already included in the cost estimate for the balcony “full use” retrofit, page 13.**

## CONCLUSIONS

The future use of the Piper’s Opera House as a gathering facility which requires a high level of structural life/safety capability. Overall, the current structural condition of the building is relatively sound, due to the timely and appropriate response to structural deficiencies that occurred since 1997, particularly:

- J.D. Copolous July, 1997 NORTH WALL COLUMN/BEAM REPAIR
- J.D. Copolous February, 1998 FLOOR REPAIR
- Ferrari Shields May 14, 2002 Front (EAST ) WALL STRENGTHENING/REPAIR
- Ferrari Shields May, 2005 BUDGET PROJECTS – AUDITORIUM FLOOR STRENGTHENING & NEW ENTRY STAIR
- Ferrari Shields December 2010 ROOF TRUSS STRENGTHENING/REPAIR
- Ferrari Shields December, 2010 ROOF TRUSS & NORTH COLUMN STRENGTHENING/REPAIR

These actions to remedy structural deficiencies, particularly the front wall, the roof trusses, and the north wall column buckling, kept the building intact and prevented what could have been catastrophic collapses that could have destroyed or severely damaged the building. With these timely actions helping to provide a competent structural baseline for the building, a roadmap for future, necessary structural actions to be undertaken to increase the structural capability and safety of the building can be developed. The needed sequence of structural strengthening projects will be listed below; it is based upon the potential for structural life/safety problems that the condition has the potential to create. These recommendations will help to secure a solid structural future for the building for many years of use. The following conclusions and recommendations will be made with that context in mind.

**1). Column at the Entry Lobby. This condition should be repaired as soon as possible and be the first item addressed; because the column is leaning severely, it has the potential to have a stability failure which can be unanticipated and unpredictable, resulting in an unacceptable life/safety concern.**

**2.) Roof Truss Support.** The structural deficiency resulting from the geometry of the offset of the top chord from the bottom chord and the column is both a structural strength and stability issue. In this regard, this is one of the most dangerous conditions that exist in the building because of the potential for a catastrophic collapse that can occur without warning. As was noted in my January 6, 2017 "*Review of roof truss deficiencies at Pipers Opera House*" Appendix C, the truss member cracking distress was noted in several other locations, as well as the north truss #4. This potential distress condition is endemic to the design and construction of the trusses and possess potential structural problems for the future that are of primary concern. This condition has the potential to provide an on-going source of potential failure with structural consequences. **There are approximately fourteen conditions remaining that have this potential. Preventative action would be to install heavy plywood "sistering" on each die of the joint that would provide structural strengthening to the condition (see photo.3, Appendix C). Also, an annual observation of the general truss construction/connections should be undertaken and compared to the baseline observation to detect any changes.**

**3.) Wall Column Buckling.** The column splice in the north and south wall is a universal support condition at every roof truss column support location. In the past history of the building, only two of these conditions have buckled and needed to be repaired. However, the condition is critical, since if it fails, it will cause a catastrophic collapse of the roof truss it supports. The columns buttressed by the balcony are less likely to experience a problem than the columns that are clear spanning. Therefore, as stated in the DISCUSSION SECTION of this report: "a survey of the both the north and south walls at the midheight column splice should be undertaken as a baseline to determine existing location of the columns. An annual inspection of the north and south wall should be undertaken visually to ascertain if movement has occurred. If it appears that movement has occurred, a new survey should be taken at that location and compared to the baseline survey; if there is evidence of movement, the condition should

be repaired similar to the plans in Appendix D". **The baseline survey should be undertaken immediately.**

**4.) Auditorium Floor Support.** The auditorium floor is generally structurally sound. The degradation of the pilasters on the cut slope at gridline 3 has been eliminated by the Ferrari Shields 2005 retrofit which installed new 20' long, structural steel "C" channels were "sistered" on each side of the existing 10"x10"x10'-0" long wood beam supporting the auditorium floor framing (see detail 112/SD-1, and sheet 1/1, Appendix B, and page 6a respectively). However, continued groundwater seepage through the cut bank and into the crawlspace could cause deterioration in other brick pilasters. This condition is tied to both the cut slope at the west wall at A Street, as well as ground water seepage from the cut. **Until the A Street cut slope condition is addressed and corrected, periodic inspections of the brick pilasters in the crawlspace supporting the auditorium floor framing should be undertaken.**

**5.) West Wall of the Building/ Water Infiltration/Drainage.** These two items are intertwined, and must be addressed as a single unit. The water seepage into the crawlspace of the building from the A Street cut is not immediately threatening to the structural stability of the building. However, an extremely wet winter could change the current conditions for the worse, and require some immediate attention. There is no way that the infiltration condition can be addressed without consideration to the A Street slope stability concern.

At present the slope stability of the A Street cut does not pose an imminent concern for the structural stability of the building. The worst case scenario would occur if a major slope failure occurs that causes the entire shear circle of the slope to fail and slide down to the west wall. If this occurs, structural damage or complete destruction of the west wall and any ancillary structure could occur.

Although the preceding concerns are not the most likely structural failures to occur, they should none the less, be given proper attention to eliminate or reduce the possibility for the long-term structural benefit of the building. As was stated in the *DISCUSSION SECTION*, the A Street cut slope should be discussed in conjunction with the Storey County Public Works Department to stabilize A Street. The retaining wall can be a stacked large concrete block wall, similar to the wall at the loading dock, or any other concrete type structure that can modified with an architectural finish that would simulate rock or block construction.

**6.) Balcony Framing and Support.** Of all the structural deficiencies noted in the building, the balcony is the one item that any strengthening is discretionary. As was stated in the *Balcony Framing and Support* section on page 13, two options were presented, 1.) leave the balcony in the "as exists" condition; or, 2) upgrade the balcony for a code conforming 100psf live load.

**As-exists option.** Under the "as-exists" option, the balcony would essentially be refurbished to its original configuration, providing a historic "snapshot" of the balcony usage. The refurbished balcony could be used for historical tours of small groups of people with no expenditure and no disruption of the historic fabric of the balcony. Also, the balcony could be used for lighting and audio uses.

**Code conforming 100psf option.** If the second option is pursued, a significant cost for the retrofit will be incurred. To accomplish the live load upgrade for the balcony, the following tasks will need to be accomplished:

- the existing deficient north balcony stairway must be demolished and rebuilt.
- a new stairway must be constructed at the south end of the balcony;
- the balcony must be shored and the existing wrought iron tie rods must be removed and replaced with steel rods.
- the historic canvas fabric covering the bottom of the balcony must be removed to allow access to structural members.
- the existing north and south balcony perimeter beams must be removed and replaced with an appropriately engineered beam for the upgraded live loading.
- the north and south balcony tie rod support beams at the roof trusses must be reinforced for the upgraded live loading.
- new connection hardware must be installed to properly connect the existing balcony joists to the perimeter beam
- new canvas must be installed at the bottom of the balcony.

**Repair cost options.** The cost for the preceding scope of work could be \$250,000. The balcony seating is steeply sloped “bench” style seating with limited knee space and uncomfortable seat backs. At most, the balcony could provide marginal seating for an additional 30 people. The cost to provide the additional balcony seating would be approximately \$8,333/seat. This is a high incremental cost for seating capacity that may only be marginally if ever, needed.

**Therefore, it is recommended that the “as exists” option for the balcony be adopted if the \$250,000 is raised, it would be better spent on other needed aspects outlined previously; in any event, the balcony upgrade should be the last item addressed.**

## **RECOMMENDATIONS**

Based on the results of my twenty year association with the building and field observations, the following recommendations for the structural stability future of the building are as follows:

- 1.) The stabilization and repair of the front entry lobby column by the stairs should be addressed as soon as possible, since it possess a structural stability concern.
- 2.) The approximately fourteen remaining unrepaired truss/column support conditions are a structural life/safety stability concern that should be addressed. Preventative action would be to install heavy plywood “sistering” on each die of the joint that would provide structural strengthening to the condition (see photo.3, Appendix C). Also, an annual observation of the general truss construction/connections should be undertaken and compared to the baseline observation to detect any changes.

- 3.) A baseline survey of the midheight of the north and south walls should be undertaken. The survey will allow a quantitative comparison of any column buckling should the appearance require.
- 4.) Upgrading the structural capacity of the existing balcony framing to support the code-required 100psf live load would be very costly and result in only a small number of usable seats. **It is recommended that option 2 – the “as-exists” option be used. This option would return the balcony to its historic appearance and be suitable for tours at a very cost-effective amount, saving between \$185,000 to \$230,000.**
- 5.) The stairway at the north wall should be demolished and the exit door secured.
- 6.) West Wall of the Building/ Water Infiltration/Drainage are two items are intertwined, and must be addressed as a single unit. The water seepage into the crawlspace of the building from the A Street cut is not immediately threatening to the structural stability of the building. However, an extremely wet winter could change the current conditions for the worse, and require some immediate attention. There is no way that the infiltration condition can be addressed without consideration to the A Street slope stability concern. Piper’s Opera House and Storey county Public Works should begin discussion regarding the unstable existing conditions.
- 7.) The roof structure can be modified to support the proposed new HVAC units.

**Project Cost Estimates for Structural Repair Recommendations**

**Based on the preceding conclusions, the estimated cost range for the structural recommendations that will help to secure a solid structural future for the building are as follows:**

	Option 1	Option 2
• strengthen roof truss/column connection:	\$80,000 - \$120,000	\$80,000 - \$120,000
• baseline survey for wall column buckling	\$ 8,000 - \$ 8,000	\$ 8,000 - \$ 8,000
• balcony “as-exists” option	\$15,000 \$20,000	N/A
• balcony “full use” option	N/A	\$200,000 \$250,000
• column at entry lobby	\$30,000 - \$50,000	\$30,000 - \$ 50,000
<b>TOTAL</b>	<b>\$133,000 - \$198,000</b>	<b>\$318,000 - \$428,000</b>
• west building wall/water infiltration drainage	TBD	TBD

If you have any questions, or require any further assistance, please do not hesitate to contact me.

Sincerely,

Paul A. Ferrari, P.E.




# **A P P E N D I X A**

## **FRONT (EAST) WALL STRENGTHENING/REPAIR**

**Ferrari Shields Construction documents dated May 14, 2002, sheets S-1 through SD-2**

180305DC0403 - Piper's Paradise/CH03 PLANS.dwg 1/07/2003 04:41:08 PXL 5:15



**SCHEMATIC 2ND FLOOR PLAN**  
SCALE: 1/4" = 1'-0"

**ROOF PLAN**  
SCALE: 1/4" = 1'-0"

NOTE:  
ALL ANIMAL DETAIL  
REFERENCES ARE ON  
SHEET S-3

PLEASE NOTIFY ARCHITECT  
OF ANY CHANGES TO THE  
CONTRACT DOCUMENTS  
OR THE  
DRAWINGS

REV	NO	DATE	DESCRIPTION

**FERRIS SHIELDS & ASSOCIATES**  
REGISTERED PROFESSIONAL  
ARCHITECTS  
1025 W. WASHINGTON ST.  
RENO, NEVADA 89509  
TEL: 775-333-8337  
FAX: 775-333-8338  
www.fshields.com

**PIPER'S OPERA HOUSE**  
FACADE  
RENO, NEVADA


SHEET TITLE: SCHEMATIC 2ND FLOOR PLAN & ROOF PLAN



DESIGNED	SA
CHECKED	SA
DRAWN	SA
DATE	01/24/03
SCALE	AS SHOWN
PROJECT NO.	0403
SHEET	S-1

**S-1**  
OF 3 SHEETS

11/02/2020 09:03 - Piper's Facade/CDMS-BLDG.dwg, 10/27/2020 04:28:29 PM, SAS



EXTERIOR ELEVATIONS-SHORING SUPPORT @ FRONT FACADE LOOKING WEST  
SCALE: 1/2" = 1'-0"

PLEASE NOTIFY FABRICATOR & ARCHITECT IF EXISTING CONDITIONS ARE DIFFERENT THAN SHOWN ON THE DRAWINGS.

SEE SHT SD-2 FOR SHOPPING LIST & S-6 FOR CONSTRUCTION SEQUENCE AND PHASING PLAN.

REVISIONS	BY

**FERRAR SHIELDS & ASSOCIATES**  
ARCHITECTS  
1000 W. WASHINGTON AVENUE  
SUITE 100  
LAS VEGAS, NEVADA 89102  
TEL: 702-735-8888  
WWW.FERRARSHIELDS.COM


**PIPER'S OPERA HOUSE**  
FACADE  
RENO, NEVADA

PIPER'S OPERA HOUSE - EXTERIOR ELEVATION-SHORING SUPPORT @ FRONT FACADE WALL

DESIGNED BY	
CHECKED BY	
DATE	
SCALE	
NOT TO SCALE	
DATE PLOTTED	
SCALE	
SHEET	

**S-2**  
OF SHEETS

H:\3002\CO-03 - Piper's Opera House\CO-03-BLDG.dwg, 10/27/2002, 04:38:09 PM, SAS



INSIDE FACE-FRONT FACADE LOOKING EAST-SHORING SUPPORT @ INTERIOR FACE  
SCALE: 1/4" = 1'-0"

SEE SHIT SO-2 FOR SHORING & TIMING S-G PHASING PLAN

PLEASE NOTIFY ENGINEER & ARCHITECT IF EXISTING CONDITIONS ARE DIFFERENT THAN SHOWN ON THE DRAWINGS

REVISIONS	BY


**FERRARI SHIELDS & ASSOCIATES**  
 ARCHITECTS  
 1000 W. BROADWAY  
 SUITE 200  
 DENVER, COLORADO 80202  
 TEL: 303.733.1111  
 FAX: 303.733.1112  
 WWW.FERRARISHIELDS.COM

**PIPER'S OPERA HOUSE**  
 FACADE  
 DENVER, COLORADO  
 SHEET TITLE: INSIDE FACE-FRONT FACADE LOOKING EAST-SHORING SUPPORT @ FRONT FACADE WALL

--

DATE	
BY	
CHECKED	
SCALE	
JOB NO.	
DATE	

H:\3002\CM03 - Piper's Paradise\CM03-BLDG.dwg, 10/23/2002, 04:37:50 PM, SAS



**PIPER'S OPERA HOUSE**  
FACADE  
RENO, NEVADA

ARCHITECT: INTERIOR ELEVATION NEW CONCRETE FRAME & FRONT FACADE WALL


**FERRARI SHEETS & ASSOCIATES**  
ARCHITECTS  
1000 W. WASHINGTON AVENUE  
SUITE 200  
LAS VEGAS, NEVADA 89102  
TEL: 702-735-3333  
FAX: 702-735-3334

NO.	DATE	BY	CHECKED	APP.

**S-4**

OF SHEETS

11:00:02:00403 - Pipers' House/CO403-BLDG.dwg, 10/23/2002 04:31:47 PM, SAS



**EXTERIOR ELEVATIONS-SHORIZING SUPPORT**  
**@ EXTERIOR FACE LOOKING NORTH**

SCALE: 1/2" = 1'-0"

PLEASE NOTIFY ENGINEER & ARCHITECT IF EXISTING CONDITIONS ARE DIFFERENT THAN SHOWN ON THE DRAWINGS

SEE S-6 FOR CONSTRUCTION FRANKING - CONSTRUCT SOUTH WALL AFTER FRONT FACADE (SEAT WALL) HAS BEEN REINFORCED.

**INSIDE FACE-FRONT FACADE LOOKING SOUTH**  
**GUNITE CONC REINF @ INTERIOR FACE**

SCALE: 1/2" = 1'-0"

SEE SHY S-6 FOR SHORING/FRANKING S-6 FRANKING PLAN AND NOTES

REVISIONS	BY

**FERRIS SHIELDS & ASSOCIATES**  
 ARCHITECTS  
 1000 WEST WASHINGTON  
 LAS VEGAS, NEVADA 89102  
 702-253-1111 (EXT)  
 702-253-1112 (FAX)  
 www.ferrisshields.com

**PIPERS' OPERA HOUSE**  
 FACADE  
 RENO, NEVADA

PROJECT TITLE: INTERIOR ELEVATION WITH CONCRETE FRANK & EXTERIOR ELEVATION-SHORIZING SUPPORT SOUTH WALL


DATE	
CHECKED BY	
SCALE	
DATE	
BY	


**S-5**

11/03/2023 09:40:19 PM, SWS


**SHORING/CONSTRUCTION SEQUENCE**

- Front facade west wall:
- 1.1 The front, 187' facade of the west wall shall be reconstructed from the south wall west wall.
  - 2.1 The front facade shall be stored and reconstructed in three phases, as outlined in the phasing diagram on sheet S-6 of this plan.
  - 2.2 Install shoring/bracing as indicated on sheets S-2, S-3, S-4, and S-14, prior to removing any of the existing construction. For example, the phasing diagram on sheet S-2 indicates that the bracing of construction is to begin with shoring installed in opening between bays D-F, and F-E, as well as column shoring/bracing at grids C, F, and E.
  - 4.3 Brace all vertical I.L. beams at the steel wall grid A through G and the entire south wall with 2" diameter pipe. All bracing bracing securely anchored to bracing the I.L. at 2' above the second floor level and to the ground at a 45 degree angle. Also, install the floor and roof ties shown in detail S-12/S-13.
  - 5.3 Remove bracing per phase plan shown on sheet S-4. Carefully remove and store the bracing for future use.
  - 6.3 Install proper fire, architectural, membrane, and concrete frame reinforcing per sheet S-14.
  - 7.3 Guide the vertical wall columns per the construction phasing plan.
  - 8.3 Remove phase 2 bracing, per sheet S-4, at the roof and second floor beam areas.
  - 9.3 Install cover fire, architectural membrane, and concrete frame reinforcing per sheet S-14.
  - 10.3 Guide the horizontal wall beams per the construction phasing plan.
  - 11.3 Repeat steps 2 through 10 until the front facade is completed.

- South Wall:
- 12.1 Begin the reconstruction of the south wall by providing the roof and floor shoring and bracing as shown on sheet S-2.
  - 12.2 Remove, reinforce, and guide the roof beam shown on S-4.
  - 14.1 Remove the interior walls of bays 1 through 5. *INSTALL 1/2" x 4" ST. PL*
  - 15.3 Install the perforating, corner anchors, and other hardware as per 1 per plan and details.
  - 16.3 Guide wall 1.
  - 17.3 Repeat steps 12 and 14 through 16 for areas 2 and 3.
- 18 Remove shoring *REIN* @ exterior face -  
reinstall Simpson RP-6 & tighten nut.



**PHASES OF CONSTRUCTION**  
SCALE: 1/8" = 1'-0"  
ROOF FACED EAST WALL  
ROOF BEARING OUT



**SOUTH WALL PHASE OF CONSTRUCTION**  
SCALE: 1/8" = 1'-0"  
NEW WORKING OUT

REVISION	BY

**FERRARI SHIELDS & ASSOCIATES**  
ARCHITECTURAL  
1000 W. WASHINGTON ST.  
SUITE 100  
LAS VEGAS, NEVADA 89102  
TEL: 702-735-8332 (FAX)  
WWW.FERRARISHIELDS.COM


**PIPER'S OPERA HOUSE**  
FACADE  
RENO, NEVADA

PIPER'S OPERA HOUSE  
RENO, NEVADA

DATE: 11/03/23  
BY: SWS  
CHECKED BY: SWS  
SCALE: 1/8" = 1'-0"  
JOB NO.: 2023-0001  
SHEET NO.: S-6

**S-6**  
OF SHEETS

11/03/2010 09:03 - Pipers' Facade Details.dwg, 1/03/2010 04:39:08 PM, SAS



NO.	REVISIONS

**FERRIS SHIELDS & ASSOCIATES**  
 1400 WEST WASHINGTON  
 LAS VEGAS, NEVADA 89102  
 (702) 735-1337 (Fax)  
 www.ferrisshields.com

**PIPER'S OPERA HOUSE**  
 FACADE  
 BRACING, NEVADA

DATE: 11/03/2010 04:39:08 PM


DRAWN: SAS  
 CHECKED: SAS  
 SCALE: AS SHOWN  
 APP. TO: CHRY WHEELER  
 SHEET: SD-1







R:\3202\COV03 - Pipers Erects\COV03-DTL.dwg, 10/28/2002, 1:06:50 AM, SAS



NO.	DATE	BY
10724/01		PAF


**PIPER'S OPERA HOUSE**  
 FACADE REINFORCING AND BRICKWORK  
 PIPERS ERECTS, INC.  
 1000 N. 10TH ST., SUITE 100  
 DENVER, CO 80202  
 TEL: 303.733.1111  
 FAX: 303.733.1112

**PIPER'S OPERA HOUSE**  
 FACADE REINFORCING AND BRICKWORK  
 PIPERS ERECTS, INC.  
 1000 N. 10TH ST., SUITE 100  
 DENVER, CO 80202  
 TEL: 303.733.1111  
 FAX: 303.733.1112

NO.	DATE	BY

**SD-2**

R:\0002\COMD - Piper's Place\CD\03 - PLANS.dwg, 10/28/02, 10:23:28 AM, SA/S



**SCHEMATIC 2ND FLOOR PLAN**  
SCALE: 1/4" = 1'-0"

**ROOF PLAN**  
SCALE: 1/4" = 1'-0"

APPROVED	BY
10/24/02	PM

**FERM SHIELDS & ASSOCIATES**  
 ARCHITECTS  
 1000 W. WASHINGTON AVE.  
 SUITE 100  
 LAS VEGAS, NV 89102  
 TEL: 702-733-3333 (FAX)  
 WWW.FERM-SHIELDS.COM

**PIPER'S OPERA HOUSE**  
 FACADE  
 REPAIR, NEVADA

SHEET TITLE: SCHEMATIC 2ND FLOOR PLAN & ROOF PLAN



DESIGN
CHECKED
DATE
SCALE
DATE PLOTTED
SHEET

**S-1**

11/03/2014 10:45 - Pipers Opera House CH03-ORDER.dwg 10/25/2012 10:23:57 AM SJS

**DESCRIPTION IN GENERAL**


- Front facade (east wall):
1. The front SDF facade of the wall shall be reconstructed first; the south wall shall follow.
  2. The front facade shall be removed and reconstructed in three phases, as defined by the phasing diagram on sheet S-5 of this plan.
  3. Install shoring/bracing as indicated on sheets S-2, S-4, and S-5, and/or as necessary for the existing construction. For example, the phasing diagram on sheet S-2 indicates that the first bay of construction is to occur with shoring installed in opening between bays C-F, and F-C, as well as column shoring/bracing at grid L, F, and E.
  4. Brace all vertical ribs down at the wall grid A through G and the vertical ribs at G through L. All ribs shall follow the vertical rib layout indicated in sheet S-4. All 2" x 4" wood bracing shall be in the plane of a 45 degree angle. Also, install the floor and roof ties shown in detail G-10-2.
  5. Remove brick and phase plan shown on sheet S-6. Carefully remove and store the brick for future use.
  6. Install rebar, ties, architectural openings, and concrete form reinforcing per sheet S-2.
  7. Grade the vertical wall below per the construction phasing plan.
  8. Remove phase 2 brick, per sheet S-6, at the roof and second floor beam levels.
  9. Install rebar, ties, architectural openings, and concrete form reinforcing per sheet S-2.
  10. Grade the horizontal wall below per the construction phasing plan.
  11. Report steps 3 through 10 until the front facade is completed.
- South Wall:
12. Begin the reconstruction of the south wall by providing the roof and floor shoring and bracing as shown on sheet S-5.
  13. Remove, rebar, ties, and grade the roof beam shown on S-6.
  14. Remove the interior wythe of brick in the vertical column joints, install SDF on S-5.
  15. Install the rebar, ties, rebar anchors, and other hardware in area 1 per sheet S-2 and details.
  16. Grade area 1.
  17. Report steps 12 and 14 through 16 for sheet S-6.
  18. Remove shoring S-5 at exterior face - re-install SDF on S-5 & tighten nuts.



**PHASES OF CONSTRUCTION**  
SCALE: 3/16" = 1'-0"

FRONT FACADE (EAST WALL)  
HOUSE LOOKING EAST

PHASE 1	REMOVED
PHASE 2	REMOVED
PHASE 3	REMOVED
PHASE 4	REMOVED
PHASE 5	REMOVED



**SOUTH WALL PHASE OF CONSTRUCTION**  
SCALE: 3/16" = 1'-0"

HOUSE LOOKING EAST

REVISIONS	BY
10/24/01	EAF

**FERRAR SHIELDS & ASSOCIATES**  
ARCHITECTS  
1000 W. WASHINGTON  
SUITE 100  
RENO, NEVADA 89509  
TEL: 775-333-8333  
FAX: 775-333-8334

**PIPER'S OPERA HOUSE**  
FACADE  
RENO, NEVADA  
FRAME REINFORCING CONSTRUCTION MODERNS AND FINISHING PLAN  
SHEET 1104 -




DESIGN	DATE
CHECKED	DATE
BY	DATE
SCALE	DATE
JOB NO.	DATE
DRWN	DATE
SHEET	DATE

**S-6**

## **A P P E N D I X B**

**2005 BUDGET PROJECTS – AUDITORIUM FLOOR STRENGTHENING & NEW ENTRY STAIR  
Ferrari Shields Construction documents dated May 20, 2005, sheets SN-1 through SD-3**

H:\2005\058146 - Pipers Opera 2005 Budget Project\058146-PLANS.dwg, S-1, 10/20/06 10:57:49 AM, HP Designer, 1050C Printer.plt



PROJECT NO.	058146
DATE	10/20/06
DESIGNER	HP
CHECKED	
DATE	
SCALE	
REVISED	
BY	
DATE	

**FERRAR SHIELDS & ASSOCIATES**  
 1000 UNIVERSITY BLVD.  
 SUITE 1000  
 RENO, NEVADA 89509  
 TEL: 775-784-1555  
 FAX: 775-784-1556  
 WWW.FERRARSHIELDS.COM

**PIPER'S OPERA HOUSE**  
 2005 BUDGET PROJECTS & NEW ENTRY STAIR  
 RENO, NEVADA

PROJECT NO. 058146 FLOOR FRAMING PLAN REVISED PLAN

**S-1**

H:\3025\05846 - Pipers Opera 2005 Budget Project\05846-DTL5.dwg, SD-1, 4/17/2006, 10:55:50 AM, HP Designer, 1058C.plt, r13

**TABLE 1: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 2: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 3: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 4: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 5: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 6: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 7: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 8: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 9: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 10: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 11: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**TABLE 12: JOINT PLATE**

JOINT DEPTH, IN.	PLATE THICK., IN.	ALLOW. STRESS, KSI	ALLOW. LENGTH, IN.
12	1/2	36	12
18	3/4	36	18
24	1	36	24
30	1 1/4	36	30
36	1 1/2	36	36
42	1 3/4	36	42
48	2	36	48
54	2 1/4	36	54
60	2 1/2	36	60
66	2 3/4	36	66
72	3	36	72
78	3 1/4	36	78
84	3 1/2	36	84
90	3 3/4	36	90
96	4	36	96
102	4 1/4	36	102
108	4 1/2	36	108
114	4 3/4	36	114
120	5	36	120

**DETAIL 101: STD - FULL HEIGHT WEB STIFFENER**

**DETAIL 102: STD - SINGLE PLATE SHEAR CONN (TYPE I)**

**DETAIL 103: STD - DBL ANGLE SHEAR CONN (TYPE II CONN)**

**DETAIL 104: STD - RC & TS COL BASE PLATE**

**DETAIL 105: STD - BEAM TO COLUMN CONN**

**DETAIL 106: STD - BEAM TO TS COLUMN CONN**

**DETAIL 109: STD - BEAM TO COLUMN CONN**

**DETAIL 110: STD - BEAM TO COLUMN CONN**

**DETAIL 111: STD - BM TO GIRDER CONN**

**DETAIL 112: STD - BEAM TO SPANDREL CONNECTION**

**DETAIL 113: STD - ISOL COL FTG**

**DETAIL 114: STD - GROUT UNDER BASE PLATE**

**DETAIL 115: STD - ISOL JT @ INT COL**

**CONTINUOUS WALL FOOTING SCHEDULE**

MARK	HEIGHT	THICKNESS	COMP. STRENGTH, PSI	STRENGTH, PSI
1	12"	12"	4000	4000
2	18"	18"	4000	4000
3	24"	24"	4000	4000
4	30"	30"	4000	4000
5	36"	36"	4000	4000
6	42"	42"	4000	4000
7	48"	48"	4000	4000
8	54"	54"	4000	4000
9	60"	60"	4000	4000
10	66"	66"	4000	4000
11	72"	72"	4000	4000
12	78"	78"	4000	4000
13	84"	84"	4000	4000
14	90"	90"	4000	4000
15	96"	96"	4000	4000
16	102"	102"	4000	4000
17	108"	108"	4000	4000
18	114"	114"	4000	4000
19	120"	120"	4000	4000

**FERRAR SHIELDS & ASSOCIATES**  
 CONSULTING ENGINEERS ARCHITECTS  
 1000 S. GARDNER, SUITE 100  
 RENO, NEVADA 89502  
 (775) 784-2222  
 FAX (775) 784-2222

**PIPER'S OPERA HOUSE**  
 2005 BUDGET PROJECT MAIN ENTRY STAIR  
 RENO, NEVADA


DATE: 4/17/06  
 DRAWN BY: JPM  
 CHECKED BY: JPM  
 DESIGNED BY: JPM  
 APPROVED BY: JPM  
 REVISIONS:  
 NO. DATE DESCRIPTION

**SD-1**





H:\2005\05846 - Pipers Opera 2005 Budget Project\05846-DTL.s.dwg, SD-3, 4/27/06, 10:56:29 AM, HP Desktop, 1680c, printer3



DETAIL  
SCALE: 1/4" = 1'-0"

130


**FERRAR SHIELDS & ASSOCIATES**  
REGISTERED PROFESSIONAL ENGINEERS  
1221 W. WASHINGTON ST., SUITE 200  
RENO, NEVADA 89509  
TEL: 775-784-2552 (FAX)  
WWW.FERRARSHIELDS.COM

**PIPER'S OPERA HOUSE**  
2005 BUDGET PROJECTS & NEW ENTRY STAIR  
RENO, NEVADA



DESIGNED
DRAWN
CHECKED
DATE
APPROVED
BY
DATE
SCALE
PROJECT
SHEET

SD-3

## **A P P E N D I X C**

### **ROOF TRUSS STRENGTHENING/REPAIR**


**Ferrari Shields Construction documents dated December 28, 2010, sheet S-1**

**P&F Consulting report dated January 6, 2017, plates 1, 2**


**Photo 1: view of cracked bottom truss chord and steel triangular repair plate**

**Photo 2: view of steel repair plate being installed**


**Photo 3: view of a similar truss failure repaired with plywood gussets**



(E) BLDG.  
**CROSS-SECTION B-B**  
 SCALE: 1/4" = 1'-0"



**FLOOR PLAN**  
 SCALE: 1/4" = 1'-0"



**ROOF COLUMN SECTION** (A)  
 SCALE: 3/8" = 1'-0"

DATE	BY

**FERRARI SHIELDS & ASSOCIATES**  
 Consulting Structural and Civil Engineers  
 1825 Charleston Place  
 Las Vegas, NV 89102  
 702.438.8800  
 775.438.8358 (fax)  
 www.ferrari-shields.com

**PIPER'S OPERA HOUSE**  
**ROOF TRUSS & WALL STRENGTHENING**  
 VIRGINIA CITY, NEVADA

PROJECT TITLE: STRUCTURAL PLAN & DETAILS


OWNER
DESIGNER
DATE
SCALE
BY
CHECKED

**P&F Consultants**  
Consulting Civil Engineers

520 Edison Way  
Reno, Nevada

**Memo**

To

From Paul Ferrari, P.E.

January 6, 2017

Pat Whitten  
Storey County Manager  
P.O. Box 176  
Virginia City, Nevada

Project Piper's Opera House

Subject Review of roof truss deficiencies at Pipers Opera House

Pat, per our previous discussions, this memo will highlight the structural conditions of the roof trusses, balcony framing, and general construction at Piper's Opera House.

**BACKGROUND**

Most recently (December 22-28, 2016) an emergency stabilization and subsequent strengthening of the north support at truss #1 was successfully concluded. The emergency stabilization of this support was necessitated by the original geometry of the way the trusses were constructed. A similar deficiencies were noted and repaired approximately 5 years ago. The proximate cause of the observed deficiency at the roof truss support is the asymmetric loading configuration where the vertical reaction of the final roof diagonal is offset from the supporting column by approximately 4'. This asymmetric condition results in the vertical reaction of the roof diagonal truss being supported perpendicularly on the bottom chord member of the truss instead of being supported in direct compression on the vertical column supporting the truss. As a result of the asymmetric support, the vertical load on the bottom member of the truss, 4' from the supporting column initiates a vertical couple on the member, resulting in an unintended bending moment on the member (see the design deficiency graphically presented in Appendix A, page 1). This bending moment causes a horizontal failure cracking in the bottom chord truss member (see photo 1). The "cleanness" of the crack in the bottom chord member at truss 1 north indicates that the failure is a relatively recent occurrence and represents an active deficiency condition that is endemic to the design of the roof trusses. If left unattended, this cracking can result in a failure of the truss up to and including a catastrophic failure of the truss.

An emergency stabilization, utilizing a steel triangular gusset was installed at truss 1 north (see photo 1). Subsequently, horizontal steel channel "splints" were installed on each side of the bottom chord to correct the deficiency permanently (see photo 2). This offset, asymmetric condition exists at both the north and south truss supports, and is a typical detail; however, the distress seems more prevalent at the truss supports at the north side of the building. Several other similar distress conditions at the north wall have been repaired (see photo 3).

## DISCUSSION

The roof trusses at Piper's are constructed and engineered using 19<sup>th</sup> Century technology and construction methods. The trusses are constructed with excellent carpentry skills, and the structure has performed well for over 135 years. However, the inherent structural engineering deficiencies in the trusses, especially the offset top chord, are starting to manifest themselves and the structural integrity is beginning to be compromised. Also, the roof truss construction is beginning to suffer from truss member warping, rotation, and deflection. These degenerate conditions can be critical, since they can cause stability failures, which can be sudden and serious. Some of the large wood truss members have twisted, rotated, and split due to shrinkage and checking.

It was also noted that some of the main columns on the north wall of the building are bowing outward. Several of the columns have experienced a deflection that required a structural repair to stabilize the column from a buckling failure (see photo 3).

The condition of the balcony framing is also suspect. The stringers supporting the balcony extend from the supporting wall out to support on a perimeter beam supported by tie rods dropped down from, and supported by the roof trusses. As constructed, the balcony stringers are only "toe-nailed" to the supporting perimeter beam, which is insufficient for any expected code loading. Also, the tie rods are drilled through the perimeter beam; the perimeter beam is supported onto the tie rods by a horizontal steel plate washer. In many cases, the plate washer is not large enough, and has been pulled into the beam. The eventual support for the balcony tie rods is provided by transfer into the roof trusses, which is questionable for the new code loads required for the balcony.


## CONCLUSIONS and RECOMMENDATIONS

Overall, the condition of the roof trusses at Piper's Opera House is stable, but subject to deterioration. The offset top chord condition will continue to be a significant structural problem that will get worse with age. However, this condition can be corrected and strengthened as several trusses have already been retrofit to correct deteriorated situations that endangered structural stability. In order to ascertain the existing condition of the trusses, an inventory of the condition of each truss, particularly the north and south offset condition should be undertaken. This inventory will serve as both a baseline to quantify any deterioration of the trusses' structural condition, as well as an action plan to identify structural problems that will require immediate attention.

The possibility of re-opening the use of the balcony is problematic. The deficiencies of the balcony structure itself need to be repaired, as iterated in the Discussion section above. However, half of the balcony load is ultimately supported by the roof trusses. The current structural condition of the roof trusses makes it difficult consider adding the significant balcony live load to the trusses. If the roof trusses are retrofit to mitigate observed deficient conditions, it may be feasible; alternatively, the balcony load could be supported by a new, independent support system.

If you have any questions, please do not hesitate to contact me.

Sincerely,  
  
 Paul A. Ferrari, P.E.  
 09/06/17




PEZONELLA

PF  
FERRARI

CONSULTING LLC

520 EDISON WAY RENO, NEVADA 775 856-5566

PLATE 2



A-A





Photo 1: racked/split bottom truss member and triangular steel repair gusset




Photo 2: Fully repaired steel truss/column connection detail



Photo 3: Plywood "sistering" repair concept for truss/column connection detail

## **A P P E N D I X D**


### **ROOF TRUSS & NORTH WALL COLUMN STRENGTHENING/REPAIR**

**Ferrari Shields Construction documents dated December 28, 2010, sheets S-1, SD-1**


**Photo 1: view of top of strengthened column with plywood truss gusset**

**Photo 2: view of top of column with strengthening steel tube columns and truss/column connection**


**Photo 3: view of column with midheight bracing at column failure**



(E) BLDG.  
 CROSS-SECTION B-B  
 SCALE: 3/4" = 1'-0"



FLOOR PLAN  
 SCALE: 1/8" = 1'-0"



ROOF COLUMN SECTION  
 SCALE: 3/4" = 1'-0" (A)

REVISIONS	BY

**FERRARI SHIELDS & ASSOCIATES**  
 Consulting Structural and Civil Engineers  
 185 Cherokee Plaza  
 Reno, Nevada 89502  
 Phone: 775-335-1110 (Ext.)  
 Fax: 775-335-1110  
 www.ferrari-shields.com



**PIPER'S OPERA HOUSE**  
 ROOF TRUSS & WALL STRENGTHENING  
 VIRGINIA CITY, NEVADA

PIPER'S TITLE, INC. STRUCTURAL PLANS & DETAILS


DRAWN
CHECKED
DATE
SCALE
BY - EP
JOB NO.
SHEET
PROJECT

S-1





Photo 1: view of top of strengthened column with plywood truss gusset



2010 8 23 0102

Photo 2: view of top of column with strengthening steel tube columns and truss/column connection





Photo 3: view of column with midheight bracing at column failure

## **A P P E N D I X E**

**J.D. Copolous July, 1997 NORTH WALL COLUMN/BEAM REPAIR DOCUMENTS S-1, S-2**

**J.D. Copolous February, 1998 FLOOR REPAIR CONSTRUCTION DOCUMENTS S-1 – S-6**

# GENERAL NOTES

## GENERAL REQUIREMENTS


- All materials and workmanship shall conform to the requirements of both local and 1994 Uniform Building Code (U.B.C.) standards.
- Contractor shall check and verify all dimensions and conditions on the job site and report any errors, omissions or possible discrepancies to the engineer prior to proceeding with the work.
- Dimensions shown on the plans shall take precedence over scale or drawings.
- Typical details and notes shall apply unless shown otherwise on the plans.
- Where "continuous inspection" is required on the plans, a special inspector, approved by and responsible to the engineer and building department, shall be employed by the owner.
- The contractor shall provide safe and adequate bracing and connections to support the component parts of the structure until the structure itself (including the floor and roof diaphragms) is complete enough to adequately support itself.
- Where reference is made to various test standards for materials, such standards shall be the latest edition and/or addendum.
- Construction safety provisions in accordance with Chapter 33 of the Uniform Building Code shall be provided and approved by the Building Department.
- The stamped set of plans and specifications shall be kept on the job site in an accessible location and shall be available to authorized representatives of the Building Department. There shall be no deviation from the approval plans and specifications without official approval from the Building Department. All work is designed to the minimum building standards or better.

## STRUCTURAL AND MISCELLANEOUS STEEL

- All structural steel shall conform to ASTM A-36-57 and shall be fabricated and welded in accordance with the A.S.C. Specifications for the design, fabrication and erection of structural steel for buildings, latest edition.
- All structural tubing shall conform to ASTM A-500 Grade B or ASTM A-501.
- Boles and nuts shall conform to ASTM A-307, U.S.C.
- All welding shall be performed in the shop of a licensed fabricator approved by the engineer or with continuous inspection by a special inspector.
- All welding is to comply with A.W.S. Standards and is to be done by welders certified by the type of welding to be performed as required by the Building Department.
- All welding is to be done by electric arc process with E70XX electrodes.
- Holes for bolts in structural steel shall be drilled or punched. Burning of holes shall not be permitted.

## LUMBERNAILING

- Structural Lumber
  - General: All structural lumber shall be stress graded Douglas Fir.
  - Grading:
    - All joists, rafters, beams, girders, posts, and braces shall be No. 1 Douglas Fir and better.
    - All studs, studs, sills, and planks shall be No. 2 Douglas Fir or better.
  - All wood in direct contact with concrete or masonry, if within 48" of the finished ground, shall be pressure treated wood or foundation grade material.
- All plywood shall be Douglas Fir CDX or C-D, C-C structural II (U.K.D.) conforming to Product Standards PS-174 with Exterior Glue and shall be stamped by an approved fabricator.
- Installed blocking: Bottom of blocking shall be installed exactly flush with bottom of joist on rafters so that steel stress and other steel connectors shall be installed straight with no bend in the steel connectors.
- All nails to be common wire nails. Where splitting occurs, pre-drill holes. Machine nailing to be permitted, using controlled distribution of suitable nailing. Nails shall not be driven more than 1/2" below surface of plywood. Joints, corners shall be nailed direct flush to plywood surface.
- Half penetration for plywood sheathing shall be 1 1/2" into blocking, near misses to be re-nailed.
- Pre-drilling is required for all wood screws larger than #10.
- Framing hangers, post caps and bases, and other connectors shall be as manufactured by HARTLEM Company or an approved equal.
- Out washers shall be placed under heads and nuts or at bolts and under heads of lag bolts.



**AUDITORIUM LEVEL PLAN**  
SCALE 1/8" = 1'-0"



FEASIBILITY PLAN FOR  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA

SCALE	1/8" = 1'-0"
JOB	100-005-1907
DATE	JULY 1997
DRAWN BY	SH

J.P. COPOULOS  
 ARCHITECT  
 P.O. BOX 201  
 CARSON CITY, NEVADA  
 89403  
 702-005-1907

**S\*1**


ELEVATION  
AND DETAILS

PHASE ONE RESTORATION OF  
**PIPER'S OPERA HOUSE**  
NEVADA  
VIRGINIA CITY


SCALE: 1/8" = 1'-0"  
JOB: PIPER  
DATE: JAN 1971  
DRAWN BY: SI

J.P. COPPOLLO  
ARCHITECT ©  
P.O. BOX 2071  
CARSON CITY  
NEVADA  
89103  
703-685-7807


S\*2




**NORTH ELEVATION**  
SCALE: 1/8" = 1'-0"



**TRUSS SUPPORT DETAIL (1)**




**GIRT CONNECTION (2)**




**COLUMN BASE DETAIL (3)**

HEAD OFF JOIST IF NECESSARY.  
USE 1/2\"/>



**BEAM REPAIR DETAIL (4)**



**TIE DETAIL (5)**

**STRUCTURAL REPAIRS**

1. COLUMN REPAIR PROCEDURE  
CONTRACTOR SHALL SUBMIT PROCEDURE FOR INSTALLATION OF NEW STEEL SUPPORTS AND REPAIR OF EXISTING COLUMN TO ARCHITECT FOR REVIEW AS A MINIMUM THE SUBMITTAL SHALL INCLUDE:  
1. SHORE EXISTING TRUSS - PROVIDE DETAILS FOR SUPPORT OF TRUSS DURING COLUMN REPAIR WORK.  
2. JACKING THE COLUMN INTO ITS ORIGINAL POSITION TO REMOVE THE BUCKLE AND TO PLUMB THE COLUMN.  
3. SUPPORT FOR THE EXISTING FLOOR JOISTS DURING ANY REQUIRED JOIST HEADER CONSTRUCTION.  
4. INSTALLATION OF NEW STEEL COLUMNS TO SUPPORT THE EXISTING TRUSS.  
5. INSTALLATION OF NEW TRUSS SUPPORT AND ANCHORAGE PER DETAILS 1 AND 3.  
6. OTHER WORK REQUIRED, BUT NOT LIMITED TO.  
7. REMOVE EXISTING SIDING AND BATTS AS REQUIRED TO PERFORM THE WORK AND STORAGE OF THE SIDING AND BATTS FOR REINSTALLATION.  
8. CONNECTION OF EXISTING GIRTS TO NEW STEEL COLUMNS PER DETAIL 2.  
9. REINSTALL EXISTING SIDING AND BATTS.
2. ROOF BEAM REPAIR PROCEDURE  
1. REMOVE ROOF SHEATHING AS REQUIRED TO REPAIR BEAM.  
2. PLACE NEW STEEL PLATES ON EACH SIDE OF BEAM AND INSTALL BOLTS PER DETAIL 4.  
3. REPLACE SHEATHING AS REQUIRED.
3. NEW CONTINUITY TIES  
1. REMOVE ROOF SHEATHING AS REQUIRED FOR INSTALLATION.  
2. INSTALL NEW STEEL TIES ACROSS EACH COLUMN PER DETAIL 5.  
3. REPLACE SHEATHING AS REQUIRED.

REVISION: 01/28/71 DRAWING NO. 1001

# GENERAL NOTES

## GENERAL REQUIREMENTS

- All materials and workmanship shall conform to the requirements of both local and 1994 Uniform Building Code (UBC), Standards.
- Contractor shall check and verify all dimensions and conditions on the job site and report any errors, omissions or possible discrepancies to the engineer prior to proceeding with the work.
- Dimensions shown on the plans shall take precedence over scale of drawings.
- Typical details and notes shall apply unless shown otherwise on the plans.
- Where "continuous inspection" is required on the plans, a special inspection department shall be responsible for the inspection and building department shall be notified by the contractor.
- The contractor shall provide safe and adequate bracing and connections to support the component parts of the structure until the structure is complete enough to adequately support itself.
- Where reference is made to various test standards for materials, such standards shall be the latest edition unless otherwise indicated.
- Construction safety provisions in accordance with Chapter 22 of the Uniform Building Code shall be provided and approved by the Building Department.
- The stamped set of plans and specifications shall be kept on the job site in an accessible location and shall be available to authorized representatives of the Building Department. There shall be no deviation from the approved plans and specifications without official consent from the Building Department. All work is designed to the minimum building standards or better.

## STRUCTURAL AND MISCELLANEOUS STEEL

- All structural steel shall conform to ASTM A-36 and shall be fabricated and erected in accordance with the AISC Specifications for the design, fabrication and erection of structural steel for buildings, latest edition.
- All structural tubing shall conform to ASTM A-500, Grade B or ASTM A-501.
- Bolts and nuts shall conform to ASTM A-307, unless otherwise indicated.
- All welding shall be performed in the shop or in a licensed fabrication shop and shall be inspected by continuous inspection by a special inspector.
- All welding is to comply with AWS D1.1 and is to be done by welders certified for the type of welding to be performed as indicated on the Building Department plans.
- All welding is to be done by electric arc process with E70XX electrodes.
- Holes for holes in structural steel shall be drilled or punched. Boring of holes shall not be permitted.

## LUMBER/MILLING

- Structural Lumber:
  - General: All structural lumber shall be stress graded Douglas Fir.
  - Grading:
    - All joists, rafters, beams, girders, posts, and braces shall be No. 1 Douglas Fir or better.
    - All studs, stringers, sills, and shales shall be No. 2 Douglas Fir or better.
  - No wood in direct contact with concrete or masonry, if either part of the contact point, shall be pressure treated wood or treatment shall be required.
- All ground shall be Douglas Fir Class or C-19 structural II LUMBER conforming to Product Standards PS-174 with [clarify] glue and shall be stamped by an approved fabricator.
- Installed Bracing: Bottom of bracing shall be attached to the bottom of joists or rafters so that steel, posts and other steel connectors shall be installed straight with no bends in the steel connectors.
  - All nails to be common wire nails, where splitting occurs, pre-drill holes. Where nailing to be permitted, continuous construction of suitable nailing, nails shall not be driven more than 1/8" into surface of boards. Where nails to be hand driven flush to plywood surface.
  - Not permitted for gyp-board sheetrock shall be 1 1/2" into sheetrock, nail heads to be recessed.
  - Pre-drilling is required for all wood screws larger than #10.
  - Flaming hangers, post caps and bases, and other connectors shall be so manufactured by WILCO Company or an approved equal.
  - Call elevations shall be shown under heads and nuts of all posts and under heads of lag bolts.

## UNREINFORCED MASONRY (U.R.M.)


- Anchor bolts shall be Corvert Injection Adhesive (CIS) (Evaluation Report No. 4461).
- Anchor Bolt Distribution: These products may be substituted for specified anchor bolt products if the substitution shall be an ICC approved product and subject to the approval of the design engineer. The size and spacing of all anchor bolts shall remain the same unless otherwise indicated in a list.
- Continuous inspection by a Registered Deputy Inspector is required for installation of all epoxy anchors.
- Five percent of all tension or combination anchors shall be tension tested to a minimum of 1000 lbs for 3 minutes.
- All anchor bolts provided in existing masonry shall conform to the following:
  - Spacing shall be done in electric masonry cut.
  - Drilled holes shall be cleaned or recommissioned by anchor bolt manufacturer.
  - Joints shall be coated by epoxy from the vertical boundaries of the joint openings.
  - Test bolts by manual testing as follows:
    - 2" dia bolts - 25 FT lbs
- Impact type tools shall not be used on any existing masonry buildings. Impacting shall include damage to existing construction.
- Masonry walls in area of work having deteriorated mortar joints shall be properly pointed. Such work shall be done according to UBC Standards No. 24-9.
  - Before applying concrete or mortar to existing masonry the following must be done:
    - Clean and brush all contact areas to fresh surface.
    - Remove loose bricks and reset same with clean mortar.
    - Substrate masonry surface to reduce absorption.
- Before applying concrete or mortar to existing masonry the following must be done:
  - Clean and brush all contact areas to fresh surface.
  - Remove loose bricks and reset same with clean mortar.
  - Substrate masonry surface to reduce absorption.

## CONCRETE


- Concrete shall be a 3 sack per cubic yard minimum mixture. All concrete that is placed shall be placed within a maximum strength of 7000 psi on UBC 41.28 days. Special inspection by a registered specialty building inspector is required for all concrete with 10% air content.
- All concrete shall be regular weight hard pack type concrete unless noted otherwise. Aggregates shall conform to ASTM C-33.
- Concrete shall conform to ASTM C-150 (Type II) unless otherwise noted.
- Concrete shall be maintained in a moist condition for a minimum of 3 days after placement. Alternate methods of curing may be accepted.
- Concrete shall not freeze for more than 6 feet. Use straw or burlap.
- Prior to placing concrete, reinforcing steel and embedded items shall be in place and well secured in position.
- Stairs not specifically shown on the drawing shall be located by the trades involved and the location reviewed by the engineer before concrete is placed. Check with all trades to ensure proper placement of openings, stairs, curbs, etc. relating to work.
- All steel and anchors in existing concrete shall be 1/2" W/8MSCT ICC E-800 Stud Anchors (ICC Evaluation Report No. 2720).

## REINFORCING STEEL

- Reinforcing steel shall be deformed steel conforming to the requirements of ASTM A-618, Grade 60.
- Detailing, fabrication and erection of reinforcing bars shall conform to A.C.I. "Manual of Standard Practice for Building Reinforced Concrete Structures", the most recent edition.
- Visible wire fabric shall conform to ASTM A-428 and A-429, Type I and II, unless otherwise indicated.
- All rebar is to comply with AWS D1.1 and is to be done by welders certified for the type of welding to be performed as required by the Department of Building and Safety.
- Three electrodes shall be used to weld reinforcing bars. In addition to the requirements of AWS D1.1, a report shall be provided by the reinforcing manufacturer to verify the material properties and show necessary pre-conditioning and welding procedures specified in AISC 308, "Structural Steelwork Code - Reinforcing Steel". In the case of specifying a supplemental report, bars conforming to ASTM A-706 may be used.
- Concrete protection for reinforcement shall be at least equal to the diameter of the bars. Minimum cover for cast in place concrete shall be as follows:
  - Placed against formwork: 2 in.
  - Placed against formwork: 2 in.
  - Slabs on grade (from top of slab): 1 in.
- Bars shall be clean of rust, grease or other material likely to impair bond. Bars shall be made cold.
- Minimum UBC on the plans shall be 48 bar diameters.
- All grade 60 reinforcement shall be clearly marked to differentiate it from grade 40 reinforcement if both are concurrently on the job.



VICINITY MAP  
SCALE 1/4" = 100'



SITE MAP  
SCALE 1/2" = 100'




**BLUE SET**  
NO CHANGES PERMITTED  
DATE: 10/15/2010


## INDEX TO DRAWINGS

NO.	DESCRIPTION
5-1	GENERAL NOTES, SITE PLAN, VICINITY MAP, AND SHEET INDEX
5-2	FOUNDING AND FOUNDATION PLAN
5-3	ADDITONAL AND VARIOUS LEVEL FINISHING PLAN, DETAILS
5-4	SECTION AND DETAILS
5-5	SECTION AND DETAILS

## DRAWING SYMBOLS



## MATERIAL INDICATIONS



GENERAL NOTES,  
VICINITY MAP,  
SITE MAP, AND  
SHEET INDEX


CONSTRUCTION PLAN FOR  
PIPER'S OPERA HOUSE  
NEVADA  
VIRGINIA CITY,

SCALE: 1/4" = 100'  
DATE: 10/15/2010

J.P. COPPOLAS  
ARCHITECT ©  
P.O. BOX 1917  
CARSON CITY  
NEVADA  
89702  
702-885-7307

1/4" = 100'


C:\Users\jgma\OneDrive\Folder\Projects\Files\Proposals\2020\12\24\ACAD\DWG\_02/2020 14:33:33 PM



PARTIAL FOUNDATION PLAN  
SCALE 1/8" = 1'-0"

REVISED FOOTING SCHEDULE

MARK	SIZE	THICKNESS	REINFORCING	NOTE
	LENGTH	WIDTH	STEEL	
A	2'-2"	1'-0"	16 # 6 @ 12"	
B	3'-2"	1'-0"	16 # 6 @ 12"	
C	3'-2"	1'-0"	16 # 6 @ 12"	
D	4'-0"	1'-0"	16 # 6 @ 12"	
E	6'-0"	1'-0"	16 # 6 @ 12"	
F	3'-6"	1'-0"	16 # 6 @ 12"	
G	9'-2"	1'-0"	16 # 6 @ 12"	
H	4'-0"	1'-0"	16 # 6 @ 12"	
I	2'-6"	2'-0"	14 # 12 @ 12"	
J	2'-6"	1'-6"	16 # 6 @ 12"	
K	3'-0"	2'-0"	14 # 12 @ 12"	
L	2'-6"	1'-0"	16 # 6 @ 12"	
M	1'-6"	1'-6"	16 # 6 @ 12"	
N	2'-0"	2'-0"	14 # 12 @ 12"	
O	2'-0"	2'-0"	14 # 12 @ 12"	
P	2'-0"	2'-0"	14 # 12 @ 12"	
Q	2'-0"	2'-0"	14 # 12 @ 12"	



'B' STREET LEVEL  
FRAMING PLAN  
SCALE 1/8" = 1'-0"



INDICATES ON 2ND FLOOR  
JUST 8" IN DE. OF  
TOP OF FLOOR FINISH,  
TOP OF

INDICATES ON 1ST FLOOR,  
TOP OF

INDICATES TO VERIFY LEVEL, DIMENSIONS AND  
200 PLS. CHECK PLAN ON SHEET 2 FOR  
BRIDGE & DIMENSIONS

WORK ITEM DESCRIPTION

- 1 Remove existing brick wall and construct new 2 x 6 stud wall and insulation.
- 2 Remove (C) and (D) floor and stud wall where as required. Remove (E) floor.
- 3 Construct (H) concrete foundation per detail on sheet 201.
- 4 Construct (M) 2x8 4" a/c stud wall.
- 5 Keep (I) beam and joist in place. Level and integrate (K) stud wall. New flooring and stud wall per detail.
- 6 Remove (J) floor joists. Construct (L) floor joists.
- 7 Use (N) 1x12 beam that contains no split.
- 8 Chop out (E) brick footing as required. Construct (G) concrete footing per detail.
- 9 Remove (B) 2x12 2x12 2" nominal w/ floor 8" a/c edge. Floor 8" 2" a/c edge.
- 10 Cut new opening in (I) brick wall per detail 109.
- 11 Existing column above (I) floor above. Reinforce (I) column and footing as directed.
- 12 Use (N) 1x12 beam that contains no split.
- 13 Use (N) 1x12 Beams. Reinforce beam. Select structural beam that contains no split greater than 6"

FLOOR,  
FRAMING AND  
FOUNDATION  
PLAN

CONSTRUCTION PLAN for  
PIPER'S OPERA HOUSE  
VIRGINIA CITY, NEVADA

SCALE 1/8" = 1'-0"  
JOB 1024  
DATE February 1998  
DRAWN AC

J.P. COPPOLDO ARCHITECT  
704 BAY ST.  
CAPRI, CA 94010  
PHONE 415-972-7902  
FAX 415-972-7907

BID SET

REVISION 1/15/98 BY AC  
REVISION 3/16/98 BY AC

S\*2













C:\Users\jagrad\OneDrive\Documents\2020\Projects\Opera\3\_Temporary\012020\DWG\072120\011502.DWG, 07/21/2020 11:56:26 PM



EAST ELEVATION  
SCALE: 1/4" = 1'-0"



NORTH ELEVATION  
SCALE: 1/8" = 1'-0"



WEST ELEVATION  
SCALE: 1/4" = 1'-0"

ELEVATIONS

CONSTRUCTION PLAN FOR  
PIPER'S OPERA HOUSE  
VIRGINIA CITY,  
NEVADA

SCALE	1/2" = 1'-0"
DATE	1/20
SITE	February 1978
DRAWN BY	JB

J.P. COPPOLAS  
ARCHITECT ©  
P.O. BOX 2507  
CARSON CITY,  
NEVADA  
89102  
702-685-7997



## **3.0 | BIBLIOGRAPHY OF RECORD DRAWINGS 1995 – 2009**

Piper's Opera House  
Bibliography of Record Drawings  
1995 - 2009

1997

---

**Reroof of Piper's Opera House**

J.P. Copoulos Architect (architecture)

Melvyn Green & Associates, Inc. (structural engineering)

Architectural Scope of Work:

- Remove and replace roofing with new cedar shingles over new felt
- Inspect sheathing for defects, repair as required with 1x12, ¾" CDX plywood, or other approved sheathing material to match thickness
- Install new z-flashing
- Repair or replace 1x4 T&G soffit boards
- Install new continuous soffit strip vent
- Repair or replace crown molding, fascia, misc. trim
- Install new roof hatch, 36" x 30", primed and painted
- Install (2) acoustical fire vents, 60" x 96"

Structural Scope of Work:

- Repair (1) existing 8x wood column with new steel columns and connections to 4x girts
- Repair (1) existing cracked roof beam with new steel plates on each side
- Add continuity ties across each column on every wall

1998

---

**Phase One Restoration of Piper's Opera House**

J.P. Copoulos Architect (architecture)

Melvyn Green & Associates, Inc. (structural engineering)

Peterson & Associates, Ltd. (mechanical engineering) - *missing*

Barrett Engineering, Inc. (electrical engineering)

Architectural Scope of Work:

- Remove and replace main interior stairs
- Remove and replace walls and columns in Corner Bar and Lobby
- Demo miscellaneous interior non-bearing partition walls on second floor at former apartment in 1863 brick building and carriage house
- Add exterior egress stairs from balconies, one each at north and south sides
- Cut in new pair of exit doors from stage on north side
- Install new sump pump in basement
- New ADA restrooms on Auditorium level, typical of 2
- Install temporary ramp from north auditorium exit doors to B Street

Piper's Opera House  
Bibliography of Record Drawings  
1995 - 2009

Structural Scope of Work:

- Remove interior brick wall and construct new 2x6 stud wall and foundation between Lobby and Corner Bar
- New footings, beams, and floor joists in Corner Bar
- New floor framing at auditorium and balcony level Lobby

Plumbing Scope of Work:

- Install new 4" sewer lateral - *shown on architectural*
- Install new 2" water service line - *shown on architectural*
- Index to Drawings references basement and first floor plumbing plans - *missing*

Life Safety Scope of Work:

- Install new 4" fire sprinkler line with post indicator valve and new fire riser inside building in closet - *shown on architectural*
- Install new sprinkler heads – concealed heads in locations - *shown on architectural*
- Index to Drawings references fire protection sheets - *missing*

Electrical Scope of Work:

- Install new 1000 amp switchboard and 225 KVA transformer at south elevation
- New 15 AMP circuit – light switch, ceiling mounted fixture, and Broan exhaust fan per single use restroom at auditorium level, typical of two restrooms

1999

---

**Phase Two-B Siding for Piper's Opera House**

J.P. Copoulos Architect (architecture)

Architectural Scope of Work:

- Remove existing exterior siding at 1885 building
- Install new 2x4 studs at 24" o.c. vertically between existing 4x6 purlins
- Install new R-19 insulation batts
- Install new 1x12 horizontal lap siding over vapor barrier over 5/8" gyp.bd. over 1/2" plywood
- Remove and replace (1) door on west wall and (2) doors on south wall
- *Notes roof insulation under separate contract*

Electrical Scope of Work:

- Rewire (10) existing wall mount lights back to electrical panel - *shown on architectural*
- Add (11) new 110v outlets - *shown on architectural*

Piper's Opera House  
Bibliography of Record Drawings  
1995 - 2009

2001

---

**Elevator for Piper's Opera House**

J.P. Copoulos Architect (architecture)

Architectural Scope of Work:

- Install new elevator in one-hour rated shaft
- New elevator equipment room
- New fire sprinkler riser enclosure
- *References structural drawings for pit details – missing*
- *What about electrical drawings?*

**Elevator Shop Drawings**

AMLIFT International on behalf of High Sierra Elevator (specialty contractor)

Scope of Work:

- Installation of new 2100 lb, 2-stop passenger elevator
- New hoistway
- New elevator equipment room

2002

---

**Piper's Opera House Façade Stabilization**

van Dijk Westlake Architects (architecture)

Ferrari Shields & Associates (structural engineering)

Architectural Scope of Work:

- Historic balcony hangers to be salvaged and returned to owner
- All doors and windows to be refurbished / rebuilt from historic stock or new to match (by owner)
- New redwood drop cove shiplap siding to match historic profile at south elevation over original brick using new mechanical fasteners and wood blocking
- Repair / reconstruct area of heavy brick deterioration on B Street elevation
- Repoint and rebuild entire brick column and capitol on B Street elevation

Structural Scope of Work:

- Shore 1877 Façade and install new concrete rigid frame, typical east and south elevations

Electrical Scope of Work:

- Provide new surface mounted j-box at historic light locations on B Street elevation – *shown on architectural*

Piper's Opera House  
Bibliography of Record Drawings  
1995 - 2009

2006

---

**A Historic Restoration for Piper's Opera House**

Anthony Smith Architecture (architecture)

Ferrari Shields & Associates (structural engineering)

Architectural Scope of Work:

- Install new stairs in Lobby connecting first and second level (balcony access shown as future)
- New plaster finish at existing masonry and concrete walls
- New beadboard finish on existing 2x walls, new stairs pony wall, and ceiling
- New wood plank flooring

Structural Scope of Work:

- New concrete footings, tube steel columns, and wide flange beams to support framing

2008

---

**Theater Modernization**

Flex-a-Lite West (specialty contractor)

Scope of Work:

- New curtains and canvas drop
- Curtain tracks
- Pipe supports, grid, raceways, etc.
- Lighting

2010

---

**Piper's Opera House Electrical Asbuilt**

Construction Design Services, Inc. (electrical engineering)

Electrical Scope of Work:

- Document existing conditions
- Evaluation of existing conditions
- Suggested remedies for code compliance

Piper's Opera House  
Bibliography of Record Drawings  
1995 - 2009

2011

---

**Restroom Improvements to the Piper's Opera House**

Dubé Group Architecture (architecture)

Architectural Scope of Work:

- Complete partially constructed accessible public restrooms, allowing dual access from Corner Bar and Piper's Opera House via gate-controlled corridor

Plumbing Scope of Work:

- Install new and owner-supplied fixtures – *shown on architectural*

Mechanical Scope of Work:

- Reconfigure new and existing HVAC ductwork and registers - *shown on architectural*
- Reconfigure and add new exhaust fans - *shown on architectural*

Life Safety Scope of Work:

- Reconfigure and add new sprinkler heads - *shown on architectural*

Electrical Scope of Work:

- Install new light fixtures and power receptacles - *shown on architectural*

**Loading Dock and Driveway Improvements to the Piper's Opera House**

Dubé Group Architecture (architecture)

Civil Scope of Work:

- Provide new concrete landing (9'-9" x 11'-10") and ac driveway (65'-0" x 11'-10") consisting of 3 inch ac over 6 inch compacted aggregate base, pipe bollards, and traffic-rated boxes - *shown on architectural*

Electrical Scope of Work:


- Install new exterior snowmelt system under concrete landing - *shown on architectural*



## 4.0 | PLANS

Historic American Buildings Survey Piper's Opera House  
Reroof of Piper's Opera House  
Phase One Restoration of Piper's Opera House  
Phase 2-b Siding for Piper's Opera House  
Elevator for Piper's Opera House  
Elevator Shop Drawings  
Piper's Opera House Façade Stabilization  
A Historic Restoration for Piper's Opera House  
Theater Renovation  
Piper's Opera House Electrical Asbuilt  
Loading Dock and Driveway Improvements to the Piper's Opera House  
Restroom Improvements to the Piper's Opera House  
Piper's Opera House Existing Conditions

THIS PROJECT WAS UNDERTAKEN BY THE HISTORIC AMERICAN BUILDINGS SURVEY IN COOPERATION WITH THE NEVADA STATE PARK SYSTEM. UNDER THE DIRECTION OF JOHN POPPELIERS, CHIEF OF HABS, THE PROJECT WAS COMPLETED DURING THE SUMMER OF 1973 AT THE HISTORIC AMERICAN BUILDINGS SURVEY FIELD OFFICE, CARSON CITY, NEVADA, BY ROBERT L. HARTWIG (HARVARD UNIVERSITY), PROJECT SUPERVISOR; AND STUDENT ASSISTANT ARCHITECTS JOHN T. MCCREERY (UNIVERSITY OF UTAH), ROBERT P. MIZELL (UNIVERSITY OF FLORIDA), AND JACK W. SCHAFER (UNIVERSITY OF CINCINNATI).




PIPER'S OPERA HOUSE IS ONE OF THE BIRTHPLACES OF AMERICAN STAGE IN THE WEST.

THE FIRST LARGE VIRGINIA CITY THEATRE WAS TOPLIFFE'S ON C STREET, BUILT IN 1862. TOM MAGUIRE'S D STREET THEATRE FOLLOWED THE NEXT YEAR, AND IT WAS PURCHASED BY JOHN PIPER IN 1868. DESTROYED BY FIRE IN 1875, HE REBUILT ON B STREET. THIS SECOND THEATRE OPENED ON JANUARY 8, 1878. THE DRESS CIRCLE, PARQUET, AND GALLERY SEATED 900. IT, TOO, BURNED FOLLOWING A MASKED BALL, ON FEBRUARY 13, 1883.


OPENING IN 1885, THE THIRD HAS MUSLIN SURFACED WALLS, ONCE WALLPAPERED, A SPRING SUPPORTED FLOOR, AND A RAKE STAGE. ELIZABETHAN STRAPWORK DESIGNS DECORATE THE PROSCENIUM ARCH, HIGHLIGHTED WITH GEORGE PIPER'S PORTRAIT OF WILLIAM SHAKESPEARE. TWO-TIERED BOXES FLANK THE STAGE AND A SUSPENDED BACONY SURROUNDS THE PARQUET.

PERFORMERS APPEARING AT PIPER'S INCLUDED MAUDE ADAMS, LILY LANGTRY, EDWIN BOOTH, HENRY WARD BEECHER, JOSEPH JEFFERSON, HELEN MODJESKA, ENRICO CARUSO, LILLIAN RUSSELL, E. H. SOUTHERN, HOUDINI, MARIE DRESSLER, MARK TWAIN, MAY ROBSON, FAY TEMPLETON, LOLA MONTEZ. DAVID BELASCO WAS STAGE MANAGER IN THE EARLY DAYS OF HIS CAREER.

PRODUCTIONS RANGED FROM SHAKESPEARE, WITH "HAMLET" MOST OFTEN PRESENTED, TO BALLET, MINSTRAL SHOWS, MUSICALS AND MELODRAMAS. POLITICAL AND SOCIAL MEETINGS HELD IN PIPER'S INCLUDE RAFFLES, LECTURES, POLITICAL DEBATES, AND RELIGIOUS SERVICES. OTHER ENTERTAINMENT FILLING THE HALL IN THE 19TH CENTURY WERE DANCES, BEARFIGHTS, AND WRESTLING MATCHES. BETWEEN 1907 AND ITS CLOSING IN 1929, MOVIES, ROLLER SKATING AND BASKETBALL GAMES WERE HELD IN THE THEATRE.




SITE PLAN - SECTION




PIPER'S OPERA HOUSE

PROJECT NO. 15-7  
 HISTORIC AMERICAN BUILDINGS SURVEY SHEET 1 OF 7 SHEETS  
 CARSON CITY PROJECT, 1973  
 OFFICE OF ARCHAEOLOGY & HISTORIC PRESERVATION  
 DIVISION OF STATE DEPARTMENT OF THE INTERIOR  
 U.S. DEPARTMENT OF THE INTERIOR  
 VIRGINIA CITY, STONEY COUNTY, NEVADA  
 PIPER'S OPERA HOUSE  
 B STREET AT UNION STREET, VIRGINIA CITY, NEVADA


**BUILDING CHRONOLOGY**  
NO SCALE




**PRE-1875 VIRGINIA CITY FIRE**  
OPERA HOUSE ON D STREET AT UNION, BUILT IN 1863 BY TOM MAQUIRE, PURCHASED BY JOHN PIPER IN 1865  
COMMERCIAL PROPERTY ON B STREET IS OWNED BY PIPER FAMILY.



**1878-1883 THEATRE FIRE**  
OPERA HOUSE RE-BUILT ON B STREET, BEHIND COMMERCIAL BUILDINGS. MAJOR ENTRANCE IS ON UNION STREET.  
COMMERCIAL BUILDINGS IN FRONT INCLUDE THEATRE OFFICES, BAR, AND APARTMENT.



**1883-1973 PRESENT**  
OPERA HOUSE RE-BUILT ON SAME SITE. HOWEVER, FLOORS ARE LOWERED, AND THEATRE IS EXTENDED 20 FEET INTO THE SURVIVING COMMERCIAL BUILDINGS.  
COMMERCIAL BUILDINGS ALTERED TO ACCOMMODATE THEATRE'S NEW MAJOR ENTRANCE ON B STREET.  
BALCONY PORCH REMOVED 1917; DRESSING ROOMS, 1962.




GROUND PLAN



DRAWN BY: ROBERT L. HARTWIG  
CARSON CITY PROJECT 1973  
OFFICE OF ARCHAEOLOGY & HISTORIC PRESERVATION  
UNIVERSITY OF NEVADA SYSTEM  
8 STREET AT UNION STREET, VIRGINIA CITY, STOREY COUNTY, NEVADA  
SURVEY NO. NEV 15-7  
HISTORIC AMERICAN BUILDINGS SURVEY SHEET 2 OF 7 SHEETS

TRIM LINE



AUDITORIUM PLAN



DRAWN BY: ROBERT L. HARTWIG  
 CARSON CITY PROJECT, 1973  
 OFFICE OF ARCHAEOLOGY & HISTORIC PRESERVATION  
 DIVISION OF CULTURAL AFFAIRS  
 STATE OF NEVADA


PROJECT AND LOCATION: PIPERS OPERA HOUSE  
 8 STREET AT UNION STREET, VIRGINIA CITY, STOREY COUNTY, NEVADA

DRAWING NO.: NEV 15-7  
 HISTORIC AMERICAN BUILDINGS SURVEY  
 SHEET 3 OF 7 SHEETS

AGE OF 1742 173 HORN

TRIM LINE

TRIM LINE



BALCONY PLAN

0 1 2 3 4 5  
SCALE: 3/8" = 1'-0"



DRAWN BY: ROBERT L. HARTING  
 CARSON CITY PROJECT, 1973  
 OFFICE OF ARCHAEOLOGY & HISTORIC PRESERVATION  
 UNITED STATES DEPARTMENT OF THE INTERIOR

8 STREET AT UNION STREET, VIRGANA, CITY, STOREY COUNTY, NEVADA


PIPER'S OPERA HOUSE

SURVEY NO. NEV 15-7  
 HISTORIC AMERICAN BUILDINGS SURVEY SHEET 4 OF 7 SHEETS


ARC 01 12 100 3/17 1973

TRIM LINE

TRIM LINE




PARTIAL SOUTH ELEVATION WITH RESTORED OPENINGS



EAST (FRONT) ELEVATION WITH RESTORED OPENINGS

ELEVATIONS



DRAWN BY: ROBERT J. MARTIN  
 CARSON CITY PROJECT 1973  
 OFFICE OF ARCHAEOLOGY & HISTORIC PRESERVATION  
 DIVISION OF CULTURAL AFFAIRS, DEPARTMENT OF TOURISM  
 AND RECREATION, STATE OF NEVADA

PROJECT: PIPER'S OPERA HOUSE  
 LOCATION: VIRGINIA CITY, STOREY COUNTY, NEVADA  
 B STREET AT UNION STREET


DRAWING NO.  
 NEV 15-7  
 HISTORIC AMERICAN  
 BUILDINGS SURVEY  
 SHEET 5 OF 7 SHEETS

2

TRIM LINE

DATE: 11-18-73

FRAM LINE



LONGITUDINAL SECTION



FRAM LINE


DRAWN BY: ROBERT HAZELL  
 CARSON CITY PROJECT, 1973  
 OFFICE OF ARCHITECTURE & HISTORIC PRESERVATION  
 UNITED STATES DEPARTMENT OF THE INTERIOR

PROJECT NO. 15-7  
 HISTORIC AMERICAN  
 SERIES 6 OF 7 SHEETS


PART OF THE CITY OF VIRGINIA  
 PIPER'S OPERA HOUSE  
 VIRGINIA CITY, SPARKE COUNTY, NEVADA  
 B STREET AT UNION STREET

PAGE 07 OF 10 SHEETS

TRIM LINE



SECTION A-A



SECTION B-B

TRANSVERSE SECTIONS



DRAWN BY: JILL B. SCHNEIDER  
 CARSON CITY PROJECT, 1973  
 OFFICE OF ARCHAEOLOGY & HISTORIC PRESERVATION  
 UNITED STATES DEPARTMENT OF THE INTERIOR

PROJECT AND LOCATION:  
 PIPER'S OPERA HOUSE  
 VIRGINIA, CITY, SIOCKEY COUNTY, NEVADA  
 8 STREET AT UNION STREET

DATE OF FILE:  
 NEV  
 15-7

HISTORIC AMERICAN  
 ARCHITECTURAL RECORD  
 SHEET 7 OF 7 SHEETS

SEE CIV. 15 FOR SITE HISTORY

TRIM LINE




ARCHITECTURAL DRAWINGS

- A-1 COVER SHEET
- A-2 ROOF PLAN, DETAILS
- A-3 ELEVATIONS
- A-4 ELEVATIONS
- A-5 BUILDING SECTIONS

STRUCTURAL DRAWINGS

- S1 ROOF PLAN, GENERAL NOTES
- S2 DETAILS, NORTH ELEVATION



INDEX TO DRAWINGS

15

15

Avoid cutting underground utility lines. It's costly.

**CALL  
BEFORE YOU  
DIG.**

1-800-227-2600

UNDERGROUND SERVICE ALERT (USA)

CODE DATA

OCCUPANCY CLASSIFICATION	A2, B
OCCUPANT LOAD	364
TYPE OF CONSTRUCTION	V-IHR
FIRE SPRINKLERS IN LIEU OF IHR CONST.	
LOCATION ON PROPERTY	OPEN ALL SIDES
TOTAL FLOOR AREA	11,114 SF.
HEIGHT	58'-0"
NUMBER OF STORIES	TWO/ONE BASEMENT

254021

SERVICE ALERT

NO SCALE

14



14

# REROOF OF PIPER'S OPERA HOUSE

MELVYN GREEN & ASSOCIATED INC.  
7107 HAWTHORNE BOULEVARD SUITE 250  
TORRANCE, CALIFORNIA 90503  
310-757-9252

J.P. COPOLOS ARCHITECT ©  
P.O. BOX 2511  
CARSON CITY, NV 89102  
702-865-1901

13 SITE PLAN



1"=10'-0"




**REROOF  
PIPER'S OPERA HOUSE  
NEVADA**  
 VIRGINIA CITY

SEP 17 1997


LEGAL PLAN  
MAYNILE RECORDS  
RECORDED  
COUNTY CLERK  
CLERK'S OFFICE  
CLERK'S OFFICE

J.P. COPOLOS  
ARCHITECT ©  
P.O. BOX 2511  
CARSON CITY  
NEVADA  
89102  
702-865-1901


A#1




EAVE DETAIL 1/2" x 1'-0" 15




EAVE DETAIL 3" x 1'-0" 12




'Z' FLASHING 3" x 1'-0" 13



EAVE DETAIL 3" x 1'-0" 11




'Z' FLASHING 3" x 1'-0" 14



'Z' FLASHING 3" x 1'-0" 13

- GENERAL NOTES**
1. COMPLETELY REMOVE ROOFING DOWN TO SHEATHING
  2. INSPECT SHEATHING FOR DEFECTS. REPAIR SHEATHING AS PER NOTE 3
  3. REPAIR ROOF SHEATHING AS FOLLOWS:  
REMOVE DETERIORATED SHEATHING TO NEXT ROOF JOIST  
REPLACE WITH 1/2, 3/4" CDX PLYWOOD OR OTHER APPROVED SHEATHING MATERIAL TO MATCH EXISTING THICKNESS  
NAILING TO BE 12D @ 6" EDGES, 12" FIELD. IF EXISTING NAILING IS MORE STRINGENT MATCH EXISTING.
  4. INSTALL NEW FELT, CEDAR SHINGLES ROOFING. EAVE FLASHING # Z FLASHING AS PER DETAILS + SPECIFICATIONS

ROOF PLAN



1/8" x 1'-0" 1

REROOF  
**PIPER'S OPERA HOUSE**  
 NEVADA  
 VIRGINIA CITY


SEP 15 1997

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2911  
 CARSON CITY  
 NEVADA  
 89402  
 702-688-1901

A-2





	15		12
	14		11
13	'Z' FLASHING	3'-11"-0"	Ø



WEST ELEVATION

1/8"=1'-0" 2



EAST ELEVATION


1/8"=1'-0" 1

REROOF  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA

SEP 15 1997


J.P. CORQUOLLOS  
 ARCHITECT ©  
 P.O. BOX 2511  
 CARSON CITY,  
 NEVADA  
 89102  
 702-885-1301

A\*3



NORTH ELEVATION

1/8" = 1'-0" 2



SOUTH ELEVATION


1/8" = 1'-0" 1

REEROOF  
PIPER'S OPERA HOUSE  
NEVADA  
VIRGINIA CITY

SEP 15 1997


J.P. COFOULOS  
ARCHITECT-IC  
P.O. BOX 3831  
CARSON CITY  
NEVADA  
89102  
702-686-1301

A-4




BUILDING SECTION 'C-C'

1/8" = 1'-0" 2



BUILDING SECTION 'A-A'

1/8" = 1'-0" 1



BUILDING SECTION 'B-B'

1/8" = 1'-0" 1

REEROOF  
 PIPER'S OPERA HOUSE  
 VIRGINIA CITY  
 NEVADA

SEP 15 1997

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2911  
 CARSON CITY  
 NEVADA  
 89102  
 702-886-1967

A-5

# GENERAL NOTES

## GENERAL REQUIREMENTS


- All materials and workmanship shall conform to the requirements of both local and 1994 Uniform Building Code (U.B.C.) standards.
- Contractor shall check and verify all dimensions and conditions on the job site and report any errors, omissions or possible discrepancies to the engineer prior to proceeding with the work.
- Dimensions shown on the plans shall take precedence over scale of drawings.
- Typical details and notes shall apply unless shown otherwise on the plans.
- Where "continuous inspection" is required on the plans, a special inspector, approved by and responsible to the engineer and building department, shall be employed by the owner.
- The contractor shall provide safe and adequate bracing and connections to support the component parts of the structure until the structure itself (including the floor and roof slabs) is complete enough to adequately support itself.
- Where reference is made to various test standards for materials, such standards shall be the latest edition and/or addendum.
- Construction safety provisions in accordance with Chapter 33 of the Uniform Building Code shall be provided and approved by the Building Department.
- The stamped set of plans and specifications shall be kept on the job site in an accessible location and shall be available to authorized representatives of the Building Department. There shall be no deviation from the approved plans and specifications without official approval from the Building Department. All work is designed to the minimum building standards or better.

## STRUCTURAL AND MISCELLANEOUS STEEL

- All structural steel shall conform to ASTM A-36/47 and shall be fabricated and erected in accordance with the A. I. S. C. Specifications for the design fabrication and erection of structural steel for buildings, latest edition.
- All structural tubing shall conform to ASTM A-500, Grade B or ASTM A-501.
- Bolts and nuts shall conform to ASTM A-307, u.n.f.
- All welding shall be performed in the shop of a licensed fabricator, approved by the engineer or with continuous inspection by a special inspector.
- All welding is to comply with A. W. S. Standards, and is to be done by welders certified for the type of welding to be performed as required by the Building Department.
- All welding is to be done by electric arc process with E70XX electrodes.
- Holes for bolts in structural steel shall be drilled or punched. Burning of holes shall not be permitted.

## LUMBER/NAILING

- Structural Lumber:
  - General: All structural lumber shall be stress graded Douglas Fir.
  - Grading:
    - All joists, rafters, beams, girders, posts, and braces shall be No. 1 Douglas Fir and better.
    - All studs, struts, sills, and plates shall be No. 2 Douglas Fir or better.
  - All wood in direct contact with concrete or masonry, or within 48" of the nearest ground, shall be pressure treated wood or foundation grade railwaywood.
- All plywood shall be Douglas Fir CDX or CDX, C-C Structural II (S.N.C.) conforming to Product Standards PS-174 with Exterior Glue and shall be stamped by an approved fabricator.
- Installed Blocking: Bottom of blocking shall be installed exactly flush with bottom of joists on rafters so that steel straps and other steel connectors shall be installed straight with no bend in the steel connectors.
- All nails to be common wire nails. Where splitting occurs, pre-drill holes. Machine nailing to be permitted upon continued demonstration of suitable nailing. Nails shall not be driven more than 1/16" below surface of plywood. Under-driven nails to be hand driven flush to plywood surface.
- Nail penetration for plywood sheathing shall be 1 1/2" and blocking, nail misses to be re-nailed.
- Pie-ricing is required for all wood screws larger than #10.
- Framing hangers, post caps, seat bases, and other connectors shall be as manufactured by HARLEN Company or an approved equal.
- Cut washers shall be placed under heads and nuts of all bolts and under heads of lag bolts.



**AUDITORIUM LEVEL PLAN**  
SCALE: 1/8" = 1'-0"




FEASIBILITY PLAN FOR  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA


SCALE: 1/8" = 1'-0"  
 JOB: 11124  
 DATE: JAN 1997  
 DRAWN: BH

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2811  
 CARSON CITY  
 NEVADA  
 89703  
 703-695-7407


**S\*1**



**TRUSS SUPPORT DETAIL 1**




**GIRT CONNECTION 2**




**COLUMN BASE DETAIL 3**


HEAD OFF JOIST IF NECESSARY. USE HJ HANGER.



**NORTH ELEVATION**  
SCALE: 1/8" = 1'-0"



**BEAM REPAIR DETAIL 4**



**TIE DETAIL 5**

**STRUCTURAL REPAIRS**

- 1 COLUMN REPAIR PROCEDURE**  
CONTRACTOR SHALL SUBMIT PROCEDURE FOR INSTALLATION OF NEW STEEL SUPPORTS AND REPAIR OF EXISTING COLUMN TO ARCHITECT FOR REVIEW. AS A MINIMUM THE SUBMITTAL SHALL INCLUDE:  
1. SHORE EXISTING TRUSS - PROVIDE DETAILS FOR SUPPORT OF TRUSS DURING COLUMN REPAIR WORK.  
2. JACKING THE COLUMN INTO ITS ORIGINAL POSITION TO REMOVE THE BUCKLE AND TO PLUMB THE COLUMN.  
3. SUPPORT FOR THE EXISTING FLOOR JOISTS DURING ANY REQUIRED JOIST HEADER CONSTRUCTION.  
4. INSTALLATION OF NEW STEEL COLUMNS TO SUPPORT THE EXISTING TRUSS.  
5. INSTALLATION OF NEW TRUSS SUPPORT AND ANCHORAGE PER DETAILS 1 AND 3.  
OTHER WORK REQUIRED, BUT NOT LIMITED TO:  
6. REMOVE EXISTING SIDING AND BATTIS AS REQUIRED TO PERFORM THE WORK AND STORAGE OF THE SIDING AND BATTIS FOR REINSTALLATION.  
7. CONNECTION OF EXISTING GIRTS TO NEW STEEL COLUMNS PER DETAIL 2.  
8. REINSTALL EXISTING SIDING AND BATTIS.
- 2 ROOF BEAM REPAIR PROCEDURE**  
1. REMOVE ROOF SHEATHING AS REQUIRED TO REPAIR BEAM.  
2. PLACE NEW STEEL PLATES ON EACH SIDE OF BEAM AND INSTALL BOLTS PER DETAIL 4.  
3. REPLACE SHEATHING AS REQUIRED.
- 3 NEW CONTINUITY TIES**  
1. REMOVE ROOF SHEATHING AS REQUIRED FOR INSTALLATION.  
2. INSTALL NEW STEEL TIES ACROSS EACH COLUMN PER DETAIL 5.  
3. REPLACE SHEATHING AS REQUIRED.

ELEVATION AND DETAILS

PHASE ONE RESTORATION OF  
**PIPER'S OPERA HOUSE**  
NEVADA  
VIRGINIA CITY.

SCALE: 1/8"=1'-0"  
JOB: 17121  
DATE: JAN 1981  
DRAWN: SH

J.P. COPOLLOS  
ARCHITECT ©  
P.O. BOX 2511  
CARSON CITY  
NEVADA  
89402  
702-695-7107



**S\*2**

**SITE DRAWINGS**

- A\*1 COVER SHEET, SITE PLAN
- UTILITY PLAN
- A\*10 UTILITY DETAILS

**ARCHITECTURAL DRAWINGS**

- A\*2 "B" STREET DEMOLITION PLAN, DEMOLITION SCHEDULE
- A\*3 AUDITORIUM DEMOLITION PLAN, DEMOLITION SCHEDULE
- A\*4 BALCONY DEMOLITION PLAN, DEMOLITION SCHEDULE
- A\*5 "B" STREET FLOOR PLAN, DOOR SCHEDULE, DOOR TYPES
- A\*6 AUDITORIUM FLOOR PLAN, WINDOW SCHEDULE, WINDOW TYPES, TOILET DETAILS
- A\*7 BALCONY FLOOR PLAN, DOOR DETAILS
- A\*8 "B" STREET REFLECTED CEILING PLAN
- A\*9 AUDITORIUM REFLECTED CEILING PLAN
- A\*10 BALCONY REFLECTED CEILING PLAN
- A\*11 ENLARGED STAIR PLAN, ENLARGED STAIR SECTION, DETAILS
- A\*12 ELEVATIONS, DOOR DETAILS
- A\*13 ELEVATIONS
- A\*14 BUILDING SECTIONS, WALL SECTION

**STRUCTURAL DRAWINGS**

- S1 GENERAL NOTES, SITE PLAN, VICINITY MAP, SHEET INDEX
- S2 "B" STREET LEVEL FRAMING AND FOUNDATION PLAN
- S3 AUDITORIUM AND BALCONY LEVEL FRAMING PLAN, ROOF PLAN
- S4 SECTION AND DETAILS
- S5 SECTION AND DETAILS

**MECHANICAL DRAWINGS**

- FP.1 PLUMBING NOTES, SCHEDULES, LEGEND AND ABBREVIATIONS
- FP.2 BASEMENT LEVEL PLUMBING PLAN
- FP.2.1 FIRST FLOOR PLUMBING PLAN
- FP.2.2 FIRST FLOOR FIRE PROTECTION
- FP.2.3 SECOND FLOOR FIRE PROTECTION

**ELECTRICAL DRAWINGS**


- E1 "B" STREET ELECTRICAL PLAN, AUDITORIUM TOILET ELECTRICAL PLAN
- E2 NOT USED
- E3 NOT USED
- E4 SINGLE LINE DIAGRAM



**LOCATION MAP**

OCCUPANCY CLASSIFICATION	A-2, B
OCCUPANT LOAD	964
TYPE OF CONSTRUCTION	V- 1 HR SPRINKLERS IN LIEU OF 1 HR CONSTRUCTION
LOCATION ON PROPERTY	OPEN 3 SIDES
EXISTING AREA	11,774 S.F.
FUTURE ADDITION	4,402 S.F.
TOTAL FLOOR AREA	16,176 S.F.
HEIGHT	58'-0"
NUMBER OF STORIES	TWO W/ BASEMENT

**INDEX TO DRAWINGS**



RETAINING WALL/PAD 1/2"=1'-0" 14

**PHASE ONE RESTORATION  
OF  
PIPER'S OPERA HOUSE**



MELVIN GREEN & ASSOCIATES  
21207 HAWTHORNE BLVD #250  
TORRENCE, CALIFORNIA 90503  
310-792-9252

PETERSON & ASSOCIATES, LTD.  
8170 REDGROVE CIRCLE SUITE C  
RENO, NV 89509  
702-856-6133

J.P. COPOULOS ARCHITECT ©  
P.O. BOX 2517  
CARSON CITY, NV 89702  
702-885-7907

BARRETT ENGINEERING, INC.  
P.O. BOX 3590  
CARSON CITY, NV 89702  
702-882-8222

- GENERAL NOTES**
- SEE SHEET A\*10 FOR STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION
  - SEE 11/A\*10 FOR SITE NOTES



**RESTORATION of  
PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA

J.P. COPOULOS  
ARCHITECT ©  
P.O. BOX 2517  
CARSON CITY  
NEVADA  
89702  
702-885-7907

A\*1





15

12

9




6

3



**SITE NOTES**

- ALL WORK SHALL CONFORM TO STOREY COUNTY CODES "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION" AND STANDARD DETAILS (HEREIN REFERRED TO AS "STD. DETAILS"). IT IS THE CONTRACTOR'S RESPONSIBILITY TO BE FAMILIAR WITH ABOVE STANDARDS AND CODES AT ALL TIMES.
- ALL TRAFFIC CONTROL AND BARRICADING WITHIN THE STOREY COUNTY RIGHT-OF-WAY SHALL CONFORM TO SECTION 330 OF THE STANDARD SPECIFICATIONS AND PART VI OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION. NO STREET CLOSURES WILL BE ALLOWED WITHOUT PRIOR APPROVAL OF A TRAFFIC CONTROL PLAN BY STOREY COUNTY.
- CALL UNDERGROUND SERVICE ALERTS 48 HRS PRIOR TO START OF CONSTRUCTION 1-800-227-2800
- UTILITIES AND STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED FROM A SEARCH OF AVAILABLE RECORDS. ANY EXISTING UTILITIES SHOWN ARE FOR THE CONTRACTOR'S REFERENCE ONLY. THE ARCHITECT DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE LOCATION, DEPTH, OR EXISTENCE OR NON-EXISTENCE OF ANY UNDERGROUND UTILITY, PIPE OR STRUCTURE WITHIN THE LIMITS OF THE PROJECT.




14

11

8

5

2



**NOTES:**



- THRUST BLOCKS TO BE CONSTRUCTED OF CLASS "C" CONCRETE.
- AREAS GIVEN ARE FOR CLASS 150 PIPE AT TEST PRESSURE OF 150 P.S.I., WITH 2000 P.S.F. BEARING CAPACITY. INSTALLATIONS USING DIFFERENT PIPE, TEST PRESSURES, AND/OR SOIL TYPES SHOULD ADJUST AREAS ACCORDINGLY, SUBJECT TO APPROVAL OF ENGINEER.
- BLOCKS TO BE POURED AGAINST UNDISTURBED SOIL.
- JOINTS AND FACE OF PLUGS TO BE KEPT CLEAR OF CONCRETE.

255004

13 TYPICAL THRUST BLOCK BEARING AREAS

NO SCALE


7



13


4

1



15 SUMP PIT 1 1/2"=1'-0" 12

14				11			
REMOVAL BY				REMOVAL BY			
ITEM	CONTRACTOR	OWNER	REMOVAL BY	ITEM	CONTRACTOR	OWNER	REMOVAL BY
1	*	*	REMOVE FROM SITE	9	*	*	REMOVE FROM SITE
2	*	*	SALVAGE TO OWNER	10	*	*	SALVAGE TO OWNER
3	*	*	REUSE IN REMODEL	11	*	*	REUSE IN REMODEL
4	*	*	ITEM TO REMAIN IN PLACE PROTECT FROM DAMAGE	12	*	*	ITEM TO REMAIN IN PLACE PROTECT FROM DAMAGE
5	*	*	REMOVE AND REUSE FOR NEW CONSTRUCTION	13	*	*	REMOVE AND REPLACE FOR NEW CONSTRUCTION
6	*	*		14	*	*	
7	*	*		15	*	*	
8	*	*		16	*	*	
	*	*		17	*	*	
	*	*		18	*	*	
	*	*		19	*	*	



- GENERAL NOTES**
1. VERIFY ALL UTILITY INFORMATION PRIOR TO START OF DEMOLITION
  2. COORDINATE DEMOLITION WORK WITH OWNER. PROVIDE PROTECTION TO EXISTING SURFACES TO REMAIN
  3. PROVIDE BARRICADES TO PROTECT PUBLIC FROM ADJACENT DEMOLITION
  4. PROVIDE SHORING WHERE EXISTING BEARING IS BEING REMOVED UNTIL NEW STRUCTURAL BEARING IS IN PLACE.




DEMOLITION SCHEDULE

10 "B" STREET DEMOLITION PLAN


1/8"=1'-0" 1

RESTORATION of  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 3517  
 CARSON CITY  
 NEVADA  
 89702  
 702-885-7907



REMOVAL BY		REMOVAL BY	
ITEM	CONTRACTOR OWNER	ITEM	CONTRACTOR OWNER
1 BRICK WALLS	* * REMOVE FROM SITE	9 EXIST. WATER SERVICE	* * REMOVE FROM SITE
2 STAIRS	* * SALVAGE TO OWNER	10 CANVAS WALL COVERING	* * REMOVE FROM SITE
3 FLOORING/FRAMING	* * REUSE IN REMODEL	11 BASE	* * REUSE IN REMODEL
4 WOOD STUD WALL	* * ITEM TO REMAIN IN PLACE PROTECT FROM DAMAGE	12 WAINSCOT	* * REUSE IN REMODEL
5 TOILETS	* * REMOVE FOR NEW CONSTRUCTION	13 BALCONY SEAT BOARDS	* * REMOVE AND REPLACE FOR NEW CONSTRUCTION
6 SINK	* * REMOVE FOR NEW CONSTRUCTION	14 BENCH	* * REMOVE AND REPLACE FOR NEW CONSTRUCTION
7 DOOR/HARDWARE	* * REMOVE FOR NEW CONSTRUCTION	15 FLOOR SHEATHING	* * REMOVE AND REPLACE FOR NEW CONSTRUCTION
8 DIRT/DEBRIS	* * REMOVE FOR NEW CONSTRUCTION	16 WOOD TRIMMED ARCH	* * REMOVE AND REPLACE FOR NEW CONSTRUCTION
10 COLUMN	* * REMOVE FOR NEW CONSTRUCTION	17 DOORS	* * REMOVE AND REPLACE FOR NEW CONSTRUCTION
		18 WAINSCOT/BASE/TRIM	* * REMOVE AND REPLACE FOR NEW CONSTRUCTION



**GENERAL NOTES**

1. VERIFY ALL UTILITY INFORMATION PRIOR TO START OF DEMOLITION
2. COORDINATE DEMOLITION WORK WITH OWNER. PROVIDE PROTECTION TO EXISTING SURFACES TO REMAIN
3. PROVIDE BARRICADES TO PROTECT PUBLIC FROM ADJACENT DEMOLITION
4. PROVIDE SHORING WHERE EXISTING BEARING IS BEING REMOVED UNTIL NEW STRUCTURAL BEARING IS IN PLACE.



RESTORATION of  
**PIPER'S OPERA HOUSE**  
 NEVADA  
 VIRGINIA CITY,

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89102  
 762-885-7907

AUDITORIUM DEMOLITION PLAN

1/8"=1'-0"

REMOVAL BY		REMOVAL BY	
ITEM	CONTRACTOR OWNER	ITEM	CONTRACTOR OWNER
1	BRICK WALLS	4	EXIST. WATER SERVICE
2	STAIRS	10	CANVAS WALL COVERING
3	FLOORING/FRAMING	11	BASE
4	WOOD STUD WALL	12	WAINSCOT
5	TOILETS	13	BALCONY SEAT BOARDS
6	SINK	14	BENCH
7	DOOR/HARDWARE	15	FLOOR SHEATHING
8	DIRT/DEBRIS	16	WOOD TRIMMED ARCH
9	COLUMN	17	DOORS
		18	WAINSCOT/BASE/TRIM



**GENERAL NOTES**

1. VERIFY ALL UTILITY INFORMATION PRIOR TO START OF DEMOLITION
2. COORDINATE DEMOLITION WORK WITH OWNER. PROVIDE PROTECTION TO EXISTING SURFACES TO REMAIN
3. PROVIDE BARRICADES TO PROTECT PUBLIC FROM ADJACENT DEMOLITION
4. PROVIDE SHORING WHERE EXISTING BEARING IS BEING REMOVED UNTIL NEW STRUCTURAL BEARING IS IN PLACE.


J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702  
 702-885-7907

DEMOLITION SCHEDULE

10 BALCONY DEMOLITION PLAN

1/8"=1'-0" 1

DOOR NO.	DOOR		FRAME		FIRE RATING	HARDWARE		REMARKS		
	SIZE	TYPE	TYPE	DETAIL		SFT NO	CLOSER		PANIC BAR	
	W	H	T	GLASS	HEAD	JAMB	THRESH			
1	3'-0"	8'-0"	E	D	WD	3/A*7	3/A*7	--	1	REFURBISH EXISTING
2	5'-0"	10'-0"	E	B	WD	6/A*7	7/A*7	5/A*7	2	REFURBISH EXISTING
3	5'-0"	10'-0"	E	B	WD	6/A*7	7/A*7	5/A*7	3	REFURBISH EXISTING
4	5'-0"	10'-0"	E	B	WD	6/A*7	7/A*7	5/A*7	3	REFURBISH EXISTING
5	3'-0"	7'-0"	1/4"	D	WD	3/A*7	3/A*7	---	4	
6	3'-0"	7'-0"	1/4"	D	WD	3/A*7	3/A*7	---	4	
7	3'-0"	7'-0"	1/4"	D	WD	3/A*7	3/A*7	---	4	
8	3'-0"	7'-0"	1/4"	D	HM	2/A*7	2/A*7	1 HOUR	5	PAIR
9	3'-0"	7'-0"	1/4"	D	WD	11/A*12	12/A*12	10/A*12	6	
10	3'-0"	7'-0"	1/4"	D	WD	11/A*12	12/A*12	10/A*12	6	
11										
12										
13										




DOOR TYPES

FINISH KEY	FLOOR	BASE	WALLS	CEILING	REMARKS
A	---	UN	FINISH	E	EXISTING TO REMAIN
B	SHEET VINYL	6" SHEET WHITE COVE	GYPSPUM BOARD	GYPSPUM BOARD	EPOXY PAINT

WALL LEGEND



- EXISTING CONSTRUCTION
- 2 X 6 WOOD STUDS @ 15" O.C. 5/8" GYPSPUM BOARD STAR SIDE
- 2 X 4 WOOD STUDS @ 15" O.C. W/ R-11 INSUL. 5/8" GYPSPUM BOARD EACH SIDE
- 6" CMU RETAINING WALL



100220

ROOM FINISH LEGEND

12



GENERAL NOTES



- PATCH TO MATCH ALL SURFACES DAMAGED FROM DEMOLITION AND REMODEL WORK TO PROVIDE FINISHED APPEARANCE.
- VERIFY ALL DIMENSIONS. REPORT ANY DISCREPANCIES TO THE ARCHITECT.

RESTORATION of  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA



J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702  
 702-885-7507

1/8"=1'-0"

SYMBOL	SIZE		M'FGR	DETAIL	GLASS
	W	H			
A	3'-6"	5'-8"	EXIST.		
B	3'-6"	6'-6"	EXIST.		
C	3'-6"	6'-6"	EXIST.		





WINDOW TYPES 1/4" = 1'-0" 15 TEMP RAMP 1" = 1'-0" 12




ENLARGED TOILET 1/2" = 1'-0" 14 HANDICAP SIGNS NO SCALE 11


- SEE 13/A\*6 FOR MTG HGTS
- ① 48" GRAB BAR
  - ② 36" GRAB BAR
  - ③ SIGN SEE 11/A\*6
  - ④ TOILET PAPER DISPENSER
  - ⑤ SANITARY NAPKIN DISPOSAL
  - ⑥ 24" X 36" MIRROR
  - ⑦ RECESSED TRASH & PAPER TOWEL DISPENSER



13 MOUNTING HEIGHTS 1/4" = 1'-0" 1 AUDITORIUM FLOOR PLAN




FRESH KEY	FLOOR	BASE	WALLS	CEILING	REMARKS
A	UNFINISH	C-B	EXISTING TO REMAIN		
B	SHEET VINYL	6" SHEET VINYL COVE	GYP-SUM BOARD	GYP-SUM BOARD	EPDXY PAINT





- GENERAL NOTES
- PATCH TO MATCH ALL SURFACES DAMAGED FROM DEMOLITION AND REMODEL WORK TO PROVIDE FINISHED APPEARANCE.
  - VERIFY ALL DIMENSIONS, REPORT ANY DISCREPANCIES TO THE ARCHITECT.

RESTORATION of  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA



J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702 702-885-7907




DOOR JAMB 3'-1'-0" 4



DOOR HEAD 3'-1'-0" 6 DOOR JAMB (HEAD SIMILAR) 3'-1'-0" 3



THRESHOLD 3'-1'-0" 5 DOOR JAMB (HEAD SIMILAR) 3'-1" 2




BALCONY FLOOR PLAN 1/8"=1'-0" 1

FINISH KEY	FLOOR	BASE	WALLS	CEILING	REMARKS
A	UNFINISHED	EXISTING TO REMAIN			
B	SHEET VINYL	6" SHEET GYPSUM BOARD	GYPSUM BOARD	EPOXY PAINT	



ROOM FINISH LEGEND

WALL LEGEND





RESTORATION of  
**PIPER'S OPERA HOUSE**  
 NEVADA  
 VIRGINIA CITY.

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2511  
 CARSON CITY  
 NEVADA 89702  
 702-885-7907

A\*17

15 12

14 11



13


10 "B" STREET REFLECTED CEILING PLAN

1/8"=1'-0" 1

RESTORATION of HOUSE  
PIPER'S OPERA HOUSE  
VIRGINIA CITY,  
NEVADA

J.P. COPQULOS  
ARCHITECT ©  
P.O. Box 2517  
CARSON CITY  
NEVADA  
89702  
732-885-7907








RESTORATION of  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY,  
 NEVADA  
 89702  
 702-885-7907

13



10 AUDITORIUM REFLECTED CEILING PLAN

1/8"=1'-0" 1



BALUSTRADE 1/2"=1'-0" 5 STAIR PLAN



1/4"=1'-0" 9



HANDRAIL DTL 3/4"=1'-0" 14 STAIR PLAN


1/4"=1'-0" 8 STAIR SECTION

1/4"=1'-0" 2



COLUMN FTG. 1"=1'-0" 13 STAIR PLAN

1/4"=1'-0" 7




1/2"=1'-0" 1 EXTERIOR STAIR SECTION


1/2"=1'-0" 1

RESTORATION of  
**PIPER'S OPERA HOUSE**  
 NEVADA  
 VIRGINIA CITY,


J.P. COPPOLA  
 ARCHITECT ©  
 P.O. Box 2517  
 CARSON CITY  
 NEVADA  
 89702  
 702-885-7907




15 DOOR JAMB 3"=1'-0" 12



14 DOOR HEAD 3"=1'-0" 11




13 DOOR SILL 3"=1'-0" 10



WEST ELEVATION

1/8"=1'-0" 2




EAST ELEVATION

1/8"=1'-0" 1

RESTORATION of  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY,  
 NEVADA

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702  
 702-885-7907


15



NORTH ELEVATION

1/8"=1'-0" 2

14





13 SOUTH ELEVATION

1/8"=1'-0" 1


RESTORATION of  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY,  
 NEVADA

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 3517  
 CARSON CITY,  
 NEVADA  
 89702  
 702-885-7907




BUILDING SECTION "C-C"

1/8"=1'-0" 2



3/8"=1'-0" 13 BUILDING SECTION "A-A"



1/8"=1'-0" 10 BUILDING SECTION "B-B"

1/8"=1'-0" 1

WALL SECTION

RESTORATION of  
**PIPER'S OPERA HOUSE**  
 NEVADA  
 VIRGINIA CITY,

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702  
 702-885-7907

# GENERAL NOTES

## GENERAL REQUIREMENTS

- All materials and workmanship shall conform to the requirements of both local and 1994 Uniform Building Code (UBC) standards.
- Contractor shall check and verify all dimensions and corners on the job site and report any errors, omissions or possible discrepancies to the engineer prior to proceeding with the work.
- Dimensions shown on the plans shall take precedence over scale of drawings.
- Typical notes and notes shall apply unless shown otherwise on the plans.
- Where "continuous inspection" is required on the plans, a special inspector, approved by and responsible to the engineer and Building Department, shall be employed by the owner.
- The contractor shall provide safe and separate bracing and connections to support the components of the structure until the structure itself including the floor and roof diaphragms is complete enough to adequately support itself.
- Where reference is made to various test standards for materials, such standards shall be the latest edition unless otherwise noted.
- Construction safety provisions in accordance with Chapter 33 of the Uniform Building Code shall be provided and approved by the Building Department.
- The stamped set of plans and specifications shall be kept on the job site in an accessible location and shall be available to authorized representatives of the Building Department. There shall be no deviation from the stamped and signed and approved set of plans without official approval from the Building Department. All work is designed to the minimum Building standards or better.

## STRUCTURAL AND MISCELLANEOUS STEEL

- All structural steel shall conform to ASTM A-36-F and shall be fabricated and erected in accordance with the AISC Specifications for the design, fabrication and erection of structural steel for buildings, latest edition.
- All structural tubing shall conform to ASTM A-500, Grade B or ASTM A-501.
- Bolts and nuts shall conform to ASTM A-325, and.
- All welding shall be performed in the shop of a licensed fabricator and erection in accordance with continuous inspection by a special inspector.
- All welding is to comply with AWS Standards and is to be done by welders certified for the type of welding to be performed as required by the Building Department.
- All welding is to be done by electric arc process with E70XX electrodes.
- Notes for notes in structural steel shall be limited or punched. Burning of holes shall not be permitted.

## LUMBER/NAILING

- Structural Lumber
  - All structural lumber shall be stress graded Douglas Fir.
  - All joists, rafters, beams, girders, posts, and braces shall be No. 1 Douglas Fir and better.
  - All studs, struts, sills, and plates shall be No. 2 Douglas Fir or better.
  - All wood in direct contact with concrete or masonry, or within 4" of the nearest ground, shall be pressure treated wood or Foundation grade treated wood.
- All plywood shall be Douglas Fir, CDX or C-D, C-C structural II (DWD) conforming to Product Standards PS-174 with Exterior glue and shall be stamped by an approved fabricator.
- Installed blocking: Bottom of blocking shall be installed exactly flush with bottom of joists on rafters so that steel straps and other steel connectors shall be installed straight with no bend in the steel connectors.
- All nails to be common wire nails. Where splitting occurs, pre-drill holes. Machine nailing to be permitted upon continued demonstration of suitable nailing. Nails shall not be driven more than 1/8" into surface of plywood. Other nails to be hand driven flush to plywood surface.
- No penetration for plywood diagonals shall be 1 1/2" into blocking, near studs to be re-framed.
- Pre-nailing is required for all wood screws larger than #10.
- Truss hangers, post caps and caps, and other connectors shall be as manufactured by HANLEY Company or an approved equal.
- Cut washers shall be placed under heads and nuts of all bolts and under heads of lag bolts.

## UNREINFORCED MASONRY (URM)


- Anchor bolts shall be Covert Injection Anchors (ICB Evaluation Report No. 4946).
- Wedge-Bolt Substitution: Other products may be substituted for specified anchor bolt products. Any substitution shall be an ICB approved product and subject to the approval of the design engineer. The size and spacing of all anchor bolts shall remain the same even an alternate product is used.
- Continuous inspection by a Registered Deputy Inspector is required for installation of all epoxy anchors.
- Five percent of all tension or compression anchors shall be tension tested to a minimum of 2000 lbs for 3 minutes.
- All anchor bolts embedded in existing brick walls shall conform to the following:
  - Drilling shall be done with electric rotary drill.
  - Drill holes shall be cleaned as recommended by anchor bolt manufacturer.
  - Bolts shall be placed 6" away from the vertical boundaries of the joint sockets.
  - Test bolts by torque testing at follow:
    - 3/4" bolts - 33 FT-LBS
- Impact type hammers shall not be used on any existing masonry buildings. Workmanship shall minimize damage to existing construction.
- Masonry walls in area of work having deteriorated mortar joints shall be properly pointed. Such work shall be done according to UBC, Standard No. 2409.
- Before applying concrete or mortar to existing masonry the following must be done:
  - Clean and brush all contact areas to fresh surface.
  - Remove loose bricks and reset same with cement mortar.
  - Saturate masonry surface to reduce absorption.

## CONCRETE


- Concrete shall be 5 sack per cubic yard minimum volume. All concrete and grout shall be grade C and attain a minimum strength of FC-3000 or 10,000 psi at 28 days. Special inspection by a registered deputy making inspector is required for all concrete with FC 3250 psi.
- All concrete shall be regular weight para-rack type concrete unless noted otherwise. Aggregates shall conform to ASTM C-778.
- Control joints conform to ASTM C-103 (Type II) unless otherwise noted or specified.
- Concrete shall be maintained in a moist condition for a minimum of 3 days after placement. Alternate methods of curing may be accepted.
- Concrete shall not free-fall more than 5 feet. Use crane or pump.
- Prior to placing concrete, reinforcing steel and embedded items shall be in place and well secured in position.
- Streets not specifically shown on the drawing shall be located by the contractor and the locations marked by the engineer before concrete is placed. Check with all trades to ensure proper placement of conduits, sleeves, cables, etc. prior to work.
- All rebar and anchors in existing concrete shall be TYPED/SET 203 ROAD Stud Anchors (ICB Evaluation Report No. 1370).

## REINFORCING STEEL

- Reinforcing steel shall be deformed steel conforming to the requirements of ASTM A-615, GRADE 60.
- Detailing, fabrication and erection of reinforcing bars shall conform to ACI Manual of Standard Practice for Detailing Reinforced Concrete Structures, the most recent edition.
- Welded wire fabric shall conform to ASTM A-95 and A-955, Lap 3/8" sheets, 19" x 19" mesh.
- All welding is to comply with AWS Standards and is to be done by welders certified for the type of welding to be performed as required by the Department of Building and Safety.
- E70XX electrodes shall be used to weld reinforcing bars. In addition to the requirements of ASTM A-615, a report shall be provided by the reinforcing manufacturer to verify that material properties are those necessary for conformance with welding procedures specified in A-6.3.11 Structural Welding Code - Reinforcing Steel. In lieu of supplying a supplemental report, bars conforming to ASTM A-615 may be used.
- Concrete protection for reinforcement shall be at least equal to the diameter of the bars. Minimum cover for cast in place concrete shall be as follows:
  - Placed against form: 3" min.
  - Placed against forms below grade: 2" min.
  - Joists on grade from top of slab: 1" min.
- Bars shall be clear of mud, grease or other material likely to impair bond. Bends shall be made cold.
- Minimum lap, UNO on the plans, shall be 40 bar diameters.
- All grade 60 reinforcement shall be clearly marked to differentiate it from grade 65 reinforcement if both are concurrently on one job.



VICINITY MAP  
SCALE NONE  
NORTH



SITE MAP  
SCALE 1/8" = 1'-0"  
NORTH

BID SET  
REVISION 02/26/20  
BY AK

GENERAL NOTES,  
VICINITY MAP,  
SITE MAP, AND  
SHEET INDEX


CONSTRUCTION PLAN FOR  
PIPER'S OPERA HOUSE  
NEVADA  
VIRGINIA CITY.

SCALE 1/8" = 1'-0"  
JOB 9709  
DATE February 1998  
DRAW AK

J.P. COPPOLIGUS  
ARCHITECT ©  
P.O. BOX 2517  
CARSON CITY  
NEVADA  
89702  
702-885-7907

S\*1







	L1			L2			L3		
NO. OF TRIMMERS	4	5	2	3	2	2	1	1	1
LEVEL '5'		4.0	4.8	4.5	4.8	4.5	4.5	4.4	

NOTE: THIS DETAIL TO BE USED AT BEARING WALL ONLY WHEN NOT SPECIFIED OTHERWISE


LINTELS AND TRIMMERS  
SCALE: NONE



TYP. JOIST TO STUD WALL CONN.  
SCALE: NONE




TYPICAL STAIR DETAIL



BALCONY LEVEL FRAMING PLAN  
SCALE: 1/8" = 1'-0"

GRID	FROM GRID	TO GRID	BOLT SPACING (C)	REF. DETAIL
3	A	B		⊕

NOTE: 1. FIRST BOLT SHALL BE INSTALLED 4" MIN. OF 2" FROM FACE OF GLAZED WALL.



AUDITORIUM LEVEL FRAMING PLAN @ LOBBY AND ATTIC FRAMING PLAN  
SCALE: 1/8" = 1'-0"

GRID	FROM GRID	TO GRID	BOLT SPACING (C)	REF. DETAIL
A	1	3		⊕
1	A	B		⊕
3	A	B		⊕

NOTE: 1. FIRST BOLT SHALL BE INSTALLED 4" MIN. OF 2" FROM FACE OF GLAZED WALL.

BID SET

REVISION 4/15/08  
BY: KJ  
REVISION 10/30/08  
BY: KJ

CONSTRUCTION PLAN for  
PIPER'S OPERA HOUSE  
VIRGINIA CITY, NEVADA


SCALE: 1/8"=1'-0"  
JOB: 0709  
DATE: February 1998  
DRAWN: AKC

J.P. COPPELLAS ARCHITECT  
P.O. BOX 2317  
CARSON CITY NEVADA  
89702  
702-685-7907


3x3




C:\Users\mrcor\OneDrive\F Drive\Non-sub\Files\Proposals\2020\Pipes Opera - Temp\1971901-14A-ACAD.DWG 6/27/2020 1:47:22 PM




COMBINATION ANCHOR DETAIL  
JOIST PERP TO WALL



COMBINATION ANCHOR DETAIL  
JOIST PERP TO WALL



FOUNDATION DETAIL



SECTION  
SCALE 1/4\"/>

**BID SET**  
REVISION 4/15/18  
BY ARC

SECTION AND  
DETAILS


CONSTRUCTION PLAN for  
**PIPER'S OPERA HOUSE**  
NEVADA  
VIRGINIA CITY,

SCALE	1/4" = 1'-0"
DATE	February 2018
DRAWN	ARC


J.P. COPPOULOS  
ARCHITECT ©  
1101 BOX 2517  
CARSON CITY  
NEVADA  
89702  
702-885-7907

S\*4

C:\Users\mpm\OneDrive\Drawings\Proposals\2020\Piper's Opera House - Final\071719b-USA-A\AU.DWG, 02/20/20 1:48:18 PM





COMBINATION ANCHOR DETAIL  
JOIST PARALLEL TO WALL




TYPICAL POST FOOTING

TYPICAL POST FOOTING




RETAINING WALL DETAILS



WALL SECTION

WALL SECTION



SECTION A

SECTION AND  
DETAILS


CONSTRUCTION PLAN for  
PIPER'S OPERA HOUSE  
VIRGINIA CITY,  
NEVADA

SCALE: 1/8" = 1'-0"  
JOB: 1908  
DATE: February 1988  
DRAWN BY: HCS


J.P. COPPOLANO ARCHITECT ©  
P.O. BOX 3517  
CARSON CITY, NEVADA  
89702  
702-885-7907

BID SET  
REVISION 4/15/88  
BY: K

S\*5



10' STREET ELECTRICAL PLAN  
SCALE 1/4" = 1'-0"



10' STREET ELECTRICAL PLAN

NO. 10  
10' STREET  
10' STREET  
10' STREET  
10' STREET  
10' STREET

See notes for  
all wiring  
are shown  
on sheets  
10' STREET

20' Street → 20' Street  
30' Street → 30' Street  
40' Street → 40' Street  
50' Street → 50' Street  
60' Street → 60' Street  
70' Street → 70' Street  
80' Street → 80' Street  
90' Street → 90' Street  
100' Street → 100' Street

RESTORATION OF  
MAYERS OFFICE HOUSE  
NEVADA


RESTORATION OF  
MAYERS OFFICE HOUSE  
NEVADA

RESTORATION OF  
MAYERS OFFICE HOUSE  
NEVADA


1. Check the main power supply and ensure it is connected correctly.  
 2. Verify the voltage levels at the input and output of the transformer.  
 3. Inspect the primary and secondary windings for any signs of damage or short circuits.  
 4. Ensure the transformer is properly grounded to prevent electrical shock.  
 5. Measure the current draw of the load connected to the secondary winding.  
 6. Compare the measured current with the rated current of the transformer.  
 7. If the current is significantly higher than the rated current, there may be a fault in the load or the transformer itself.  
 8. Check the temperature of the transformer windings and the surrounding area.  
 9. If the transformer is overheating, it may be overloaded or there may be a problem with the cooling system.  
 10. Consult the manufacturer's specifications for the correct operating conditions and safety precautions.

1. The transformer is a device that transfers electrical energy from one circuit to another through inductively coupled conductors.  
 2. It consists of two or more coils of insulated wire wound on a common magnetic core.  
 3. The primary winding is connected to the AC power source, and the secondary winding is connected to the load.  
 4. The voltage induced in the secondary winding is proportional to the number of turns in the secondary winding relative to the primary winding.  
 5. This relationship is known as the turns ratio, and it determines the voltage transformation ratio of the transformer.  
 6. Transformers are used in a wide variety of applications, including power distribution, signal processing, and impedance matching.  
 7. They are essential components in many electrical systems, and their proper operation is critical for the safety and efficiency of the system.

1. Transformer
2. Core
3. Winding
4. Primary winding
5. Secondary winding
6. Turns ratio
7. Voltage transformation
8. Power transfer
9. Efficiency
10. Losses
11. Regulation
12. Impedance matching
13. Isolation
14. Safety
15. Maintenance
16. Troubleshooting
17. Applications
18. Specifications
19. Standards
20. Testing
21. Installation
22. Operation
23. Protection
24. Cooling
25. Grounding
26. Labeling
27. Documentation
28. Training
29. Safety protocols
30. Emergency procedures




1. The transformer is a device that transfers electrical energy from one circuit to another through inductively coupled conductors.  
 2. It consists of two or more coils of insulated wire wound on a common magnetic core.  
 3. The primary winding is connected to the AC power source, and the secondary winding is connected to the load.  
 4. The voltage induced in the secondary winding is proportional to the number of turns in the secondary winding relative to the primary winding.  
 5. This relationship is known as the turns ratio, and it determines the voltage transformation ratio of the transformer.  
 6. Transformers are used in a wide variety of applications, including power distribution, signal processing, and impedance matching.  
 7. They are essential components in many electrical systems, and their proper operation is critical for the safety and efficiency of the system.



1. The transformer is a device that transfers electrical energy from one circuit to another through inductively coupled conductors.  
 2. It consists of two or more coils of insulated wire wound on a common magnetic core.  
 3. The primary winding is connected to the AC power source, and the secondary winding is connected to the load.  
 4. The voltage induced in the secondary winding is proportional to the number of turns in the secondary winding relative to the primary winding.  
 5. This relationship is known as the turns ratio, and it determines the voltage transformation ratio of the transformer.  
 6. Transformers are used in a wide variety of applications, including power distribution, signal processing, and impedance matching.  
 7. They are essential components in many electrical systems, and their proper operation is critical for the safety and efficiency of the system.

ARCHITECTURAL DRAWINGS

- A\*1 COVER SHEET
- A\*2 AUDITORIUM LEVEL PLAN, DOOR SCHEDULE AND TYPE
- A\*3 ELEVATIONS, DETAILS
- A\*4 ELEVATIONS
- A\*5 BUILDING SECTIONS AND WALL SECTION



INDEX TO DRAWINGS

15

15

Avoid cutting underground utility lines. It's costly.

**CALL BEFORE YOU DIG.**

1-800-227-2600

UNDERGROUND SERVICE ALERT (USA)

254001

CODE DATA

OCCUPANCY CLASSIFICATION	A2, B
OCCUPANT LOAD	964
TYPE OF CONSTRUCTION	V-1HR
FIRE SPRINKLERS IN LIEU OF 1HR CONST.	
LOCATION ON PROPERTY	OPEN ALL SIDES

TOTAL FLOOR AREA	11,774 S.F.
HEIGHT	58'-0"
NUMBER OF STORIES	TWO/W BASEMENT

SERVICE ALERT



NO SCALE

14

14

PHASE TWO-B SIDING  
for  
PIPER'S OPERA HOUSE  
VIRGINIA CITY, NEVADA

J.P. COPOULOS ARCHITECT ©  
P.O. BOX 2517  
CARSON CITY, NV 89702  
775-885-7907



1"=10'-0" 1

PHASE 2 B - SIDING for  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702  
 775-885-7907


A\*1

13 SITE PLAN


DOOR NO.	DOOR		FRAME			FIRE RATING	HARDWARE		REMARKS	
	SIZE	TYPE	TYPE	DETAIL	DETAIL		SET NO.	CLOSER		
	W	H	T	GLASS	HEAD	JAMB	THRESH			
1	3'-0"	7'-0"	3/4"	A	WD 11/A*2	13/A*2	10/A*2	1	● ●	REMOVE (E) DOOR
2	3'-0"	7'-0"	3/4"	A	WD 11/A*2	13/A*2	10/A*2	2		REMOVE (E) DOOR
3	3'-0"	7'-0"	3/4"	A	WD 11/A*2	13/A*2				REMOVE (E) DOOR

1. 1 1/2" PAIR BUTTS CLOSER LCN 330 SERIES PANIC BAR (VON GUPPIN 8837L SERIES) WEATHERSTRIP 313 & 316 THRESHOLD 2180AK  
 2. 1 1/2" PAIR BUTTS LATCHSET D73PD WEATHERSTRIP 313 & 316 THRESHOLD 2180AK  
 FINISH: POLISHED BRASS (US3)  
 LATCHSET: SCHLAGE ATHENS SERIES D W/ CIRCULAR LATCH PLATE  
 A: SOLID CORE WOOD RAISED PANEL MATCH EXIST.  
 800001


DOOR TYPES 1/4"=1'-0" HARDWARE SETS 12



1 4 DOOR HEAD 3"=1'-0" 11








DOOR JAMB 3"=1'-0" 13 DOOR SILL 3"=1'-0" 10



AUDITORIUM LEVEL PLAN 1/8"=1'-0" 1


PHASE 2.B - SIDING for  
 PIPER'S OPERA HOUSE  
 VIRGINIA CITY, NEVADA

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702  
 775-885-7907




PHASE 2 B - SIDING for  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702  
 775-885-7907




NORTH ELEVATION


1/8"=1'-0" 2



WINDOW JAMB 3"=1'-0" 14



WINDOW SILL 3"=1'-0" 13




SOUTH ELEVATION

1/8"=1'-0" 1

PHASE 2 B - SIDING for  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY, NEVADA

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702  
 775-885-7907







- (E) 1x12 VERT. SIDING TO BE REMOVED
- (E) 8x10 COLUMN w/ 3x10 LUMBER ON EACH SIDE
- (E) 1x12 HORIZ. LAP SIDING TO BE REMOVED
- (E) FABRIC WALL COVERING
- NEW 1x12 HORIZ. SIDING OVER VAPOR BARRIER
- (E) 4x6 PURLINS
- NEW 5/8" D.P.P. BO. SHTG. OVER NEW 1/2" PLYWD.
- (E) 2x4 STUDS
- NEW 2x4 STUDS @ 24" O.C.
- (E) 1x12 HORIZ. BOARD
- NEW R-19 INSUL.
- 2x6 SHAPED BOTTOM TRIM
- (E) 2x12 & 3x12 @ 18" O.C.

NOTE:  
ANY EXIST. ROMEX ENCOUNTERED DURING CONSTRUCTION OF THE SIDING, TO BE REWIRED IN CONDUIT BACK TO THE ELECTRICAL PANEL


WALL SECTION 3/8"=1'-0" 13



BUILDING SECTION "C-C" 1/8"=1'-0" 2



BUILDING SECTION "A-A" 1/8"=1'-0" 10




BUILDING SECTION "B-B" 1/8"=1'-0" 1

PHASE 2 B - SIDING for  
**PIPER'S OPERA HOUSE**  
 VIRGINIA CITY,  
 NEVADA

J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2517  
 CARSON CITY  
 NEVADA  
 89702  
 775-885-7907

A15



FIRST FLOOR PLAN

1/8"=1'-0" 10


SECOND FLOOR PLAN

1/8"=1'-0" 1

ELEVATOR for  
 PIPER'S OPERA HOUSE  
 VIRGINIA CITY NEVADA


J.P. COPOULOS  
 ARCHITECT ©  
 P.O. BOX 2317  
 CARSON CITY  
 NEVADA  
 89702  
 775-885-7907

A\*1




ELEVATOR SECTION

1/2"=1'-0"



ENLARGED ELEVATOR PLAN




3/8"=1'-0"



ELEVATOR for  
PIPER'S OPERA HOUSE  
VIRGINIA CITY  
NEVADA

J.P. COPOULOS  
ARCHITECT ©  
P.O. BOX 2317  
CARSON CITY  
NEVADA  
89702  
775-885-7907


A\*2




ELEVATOR SILL 3'-1'-0" 9

ELEVATOR HEAD 3'-1'-0" 6

ELEVATOR SILL 3'-1'-0" 3



ELEVATOR JAMB 3'-1'-0" 2



4 LADDER 1/2'-1'-0" 1




10

ELEVATOR for  
PIPER'S OPERA HOUSE  
VIRGINIA CITY NEVADA

J.P. COPOULOS  
ARCHITECT ©  
P.O. BOX 2517  
CARSON CITY  
NEVADA  
89702  
775-885-7907

A\*3





- NOTES:**
1. GROUTING AS REQUIRED BY OTHERS.
  2. (2) ASSEMBLYS REQUIRED

FRAME FINISH: PRIME  
DOOR FINISH: PRIME

REVISIONS			
REV	DATE	DRAWN BY	DESCRIPTION

**AMLIPT INTERNATIONAL INC.**

**PIPERS OPERA HOUSE**











JOB NO. 0106955-1	DRAWN BY: MCHR
ADDRESS: VIRGINIA CITY, NV	CHKD BY: JLS 08-14-01
CONTRACTOR: HIGH SIERRA ELEVATOR	FIELD: 08-01-01
ARCH/ENG:	FIELD:
FILE NO.:	CUSTOMER APPROVED SIGNATURE:

DWG. NAME: **ENTRANCE SS/RH 3'-0" x 7'-0" DW**

<input checked="" type="checkbox"/> FOR APPROVAL	<input type="checkbox"/> REVISED FOR APPROVAL	REV. C	DRAWING NO. 0106955-201
<input type="checkbox"/> RELEASED FOR INSTALLATION AND FINISHES	<input type="checkbox"/> REVISED FOR APPROVAL	SCALE NONE	REV.
<input type="checkbox"/> REVISED FOR APPROVAL	<input type="checkbox"/> REVISED FOR APPROVAL		

THIS SHEET GRAPHIC HAS APPROVED ON EQUIPMENT THIS ITEM RELEASED FOR INSTALLATION AND FINISHES MADE AFTER APPROVAL WILL RESULT IN HOISTWAY COST AND CONSTRUCTION TIME.

FINAL



**CAB PLAN VIEW**  
(1) CAB ASSEMBLY REQ'D. TOTAL

**REFLECTED CEILING**  
**TYPE 600**

- NOTES:**
1. - CAB EXTERIOR TO RECEIVE SOUND DEADENING MASTIC.
  2. - CAB VENTILATION AREA PROVIDED= 176 sq. in.
  3. - ELEVATOR CAB COMPLIES WITH ANSI ASME A17.1 SECTION 204.2 INCLUDING FIRE RATING.


CAB INTERIOR FINISHES	
WALL PANELS	14 GA. HPS (UNFINISHED)
HANDRAIL	ST. STL. #4
BASE	N/A
FRONT RETURN	(UNFINISHED)
HEADER	(UNFINISHED)
CAR DOORS	ST. STL. #4
CEILING	TYPE 600 (UNFINISHED)
ACCESSORIES	
CAR OPER. PANEL	ST. STL. #4
CAR POSITION INDICATOR	ST. STL. #4
CAR DIRECTION INDICATOR	ST. STL. #4
GRILLE	Y
SERVICE CABINET	N/A
PAN HOOKS	N/A
DOOR PROTECTION	INFRA-RED DOOR DETECTOR
FAN	2-SPEED STD.
EST. CAB WEIGHT	

REVISIONS			
REV.	DATE	DRAWN BY:	DESCRIPTION
A	10-31-01	MCHR	MADE CORRECTION AS SHOWN
B	02-04-02	HCHR	DELETE CAR POSITION INDICATOR
C	05-02-02	MCHR	CHANGE PANEL DIMENSION

<b>AMLIFT INTERNATIONAL INC.</b>	
<b>PIPERS OPERA HOUSE</b>	
JOB NO.	0106955-1
DRWN BY	MCHR
PROJECT	VIRGINIA CITY, NV
CONTRACTOR	HIGH SIERRA ELEVATOR
PROJ. NO.	04-22-02
DATE	04-22-02
SCALE	NONE
REV.	C
ENGR. NO.	0106955-301

FIN





**MAIN C.O.P. PLATE**

QTY. (1) REQ'D. R/H HINGES AS SHOWN  
 BOX SIZE: 9.75" X 51.00" X 3.50"  
 CUT OUT: BOX SIZE + 1/8"  
 FINISH: BRONZE #4  
 MAT.: 0.125" THICK.


- 0.00 FIREFIGHTERS' OPERATION**
- 0.51 To operate car
  - 0.73 To nearest floor selection
  - 1.12 To close power-operated door
  - 1.46 To open power-operated door
  - 2.53 To hold car at floor
  - 3.21 To automatically send car to recall floor
  - 3.43 To hold car at floor
  - 3.88 To operate car
  - 4.16 To nearest floor selection
- Insert fire key and turn to "OFF"  
 Press desired floor button  
 Press "CALL CANCEL" button  
 Press and hold "DOOR CLOSE" button  
 Press and hold "DOOR OPEN" button  
 With doors open, turn key to "HOLD"  
 With doors open, turn key to "OFF"

ANSI '98) PHASE II FIRE INSTRUCTIONS  
 ENGRAVE HELVETICA MEDIUM  
 RED PAINT INFILL  
 A 0.25" HIGH  
 B 0.11" HIGH


NOTE: SPECIAL HEIGHT IN ENGRAVE FIRE PHASE II




**"CLASSIC" PUSHBUTTON BASE OVERALL SIZE**



**"CLASSIC" PUSHBUTTON CUTOUT AND STUD DETAILS**




2" GRILLE TAIL



**SERVICE PLATE**

- SERVICE PLATE TO CONTAIN:
- 1.- INSPECTION SW.
  - 2.- IND. SERV. SW.
  - 3.- LIGHT SW.
  - 4.- FAN 2/SP. SW.
  - 5.- UP SW.
  - 6.- DOWN SW.
  - 7.- 2 SPARE SWS.
  - 8.- EM. LITE TEST SW.

NOTES:  
 MATERIAL: 0.065" THICK.  
 FINISH: BRONZE #4  
 TOLERANCE: ± .03  
 SHEAR ALL EDGES DOWN.



**SERVICE DOOR**

(1) REQUIRED

STD. BARREL LOCK "OD" PUNCH


REVISIONS		DESCRIPTION	
REV. A	DATE: 05-02-02	DRAWN BY: MCHR	CHANGE MATERIAL FINISH

<b>AMLIFT INTERNATIONAL INC.</b>			
<b>PIPERS OPERA HOUSE</b>			
PROJECT:	Q106955-1	DATE:	AS 08-16-01
LOCATION:	VIRGINIA CITY, NV	ISSUE:	08-03-01
OWNER:	HIGH SIERRA ELEVATOR	DATE:	04-22-02
REV. NO.		DATE:	
REV. BY:		DATE:	
<b>CONTROL OPERATING PANEL (C.O.P.)</b>		DATE:	0106955-451
REV. NO.		DATE:	
REV. BY:		DATE:	




P.N.A.




TERMINAL HALL STATION "UP" W/  
ACCESS SW. & FIRE SERV. SW.

(1) REQUIRED  
@ 1<sup>ST</sup> FLOOR  
BOX: 3.90" x 10.00" x 3.50"




TERMINAL HALL STATION "DOWN" W/  
ACCESS KEY SWITCH

(1) REQUIRED  
@ 2<sup>ND</sup> FLOOR  
BOX: 3.50" x 10.00" x 3.50"



CAR LANTERN (C.D.I.)

(1) REQUIRED  
BOX: 3.30" x 10.00" x 3.50"



"CLASSIC" PUSHBUTTON  
CUTOUT AND STUD DETAILS


FINISH: BRONZE #4  
MAT.: 0.125" THICK.

REV#		DATE	DRAWN BY:	DESCRIPTION
A	04-23-02		MCHR	CHANGE PLATE FINISH
B	05-02-02		MCHR	CHANGE MATERIAL FINISH

<b>AMLIFT INTERNATIONAL, INC.</b>	
PIPERS OPERA HOUSE	
JOB NO. 0106955-1	DRAWN BY: MCHR
ADDRESS: VIRGINIA CITY, NV	DATE: JUL 08-14-01
CONTRACTOR: HIGH SIERRA ELEVATOR	REV# 08-03-01
PROJECT: FINAL	DATE: 04-22-02
FILE NO.	DESIGNER APPROVED
HALL STATION	
FINAL DRAWING	SCALE: NONE
THIS DRAWING IS THE PROPERTY OF AMLIFT INTERNATIONAL, INC. IT IS TO BE USED FOR THE PROJECT AND NOT BE REPRODUCED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF AMLIFT INTERNATIONAL, INC.	SCALE: NONE





NORTH ELEVATION  
1/4" = 1'-0"

WEST ELEVATION  
1/4" = 1'-0"

Issued / Revised		
No.	Date	Description
1	08.15.22	CITY SUBMITTAL

- General Notes:**
- THE OWNER WILL REMOVE, RESTORE/RECREATE & REINSTALL ALL DOORS, WINDOWS & FRAMES. CONTRACTOR TO COORDINATE WITH OWNER.
  - A WOOD BRID & PLANK WALL WILL BE INSTALLED 8'-0" BEHIND THE 8' STREET FACADE AND THE PORTION OF THE SOUTH WALL INCLUDED IN THIS CONTRACT. THIS WILL BE THE CONTRACTOR'S CONSTRUCTION ZONE.
  - THIS FACILITY WILL REMAIN FULLY UTILIZED & OPERATIONAL DURING CONSTRUCTION. COORDINATE ALL CONTRACTOR OPERATIONS, SAFEGUARDS, & CLOSURES WITH THE OWNER. MAINTAIN THE SAFETY & SECURITY OF THE PUBLIC, STAFF, & USERS OF THE FACILITY.
  - NOTE THAT THIS IS A HISTORIC BUILDING OF NATIONAL LANDMARK IMPORTANCE. EXTREME CARE SHOULD BE TAKEN TO ENSURE THAT NO DAMAGE OCCURS TO THE HISTORIC FABRIC. SHOULD DAMAGE OCCUR, NOTIFY ARCHITECT IMMEDIATELY AND DO NOT PROCEED WITH REPAIRS WITHOUT EXPLICIT WRITTEN DIRECTIONS FROM THE ARCHITECT.
  - PROVIDE UNIT COST FOR ADDITIONAL REPORTING & BRICK REPAIR. SEE SPECIFICATIONS - UNIT COSTS FOR DETAILED INSTRUCTIONS.
  - UTILIZE SALVAGED BRICK FROM STRUCTURAL STABILIZATION WORK UNDER THIS CONTRACT.
  - REMOVE DAMAGED BRICK AND REPLACE IF CHIPS OR SPALLING > GREATER THAN TWO INCHES LONG OR 1" DEEP.

- Key Notes:**
- AREA OF HEAVY BRICK DETERIORATION MAY REQUIRE COMPLETE RECONSTRUCTION. UTILIZE SALVAGED BRICKS TO FULL EXTENT POSSIBLE.
  - REPORT AND REBUILD ENTIRE COLUMN AND CAPITAL.








**Piper's Opera House  
Facade Stabilization**

Commission # 22002


van Dijk Westlake Reed Leskosky  
Architects

One East Camelback Road  
Suite 690  
Phoenix, Arizona 85012  
602 212-0451  
www.vurfl.com


**Facade Stabilization  
Elevations**




SD  
A1-1




SECTION DETAIL - WINDOW SILL  
3' x 1'-0"



HISTORIC SHIPLAP PROFILE  
3' x 1'-0"



PLAN DETAIL - WINDOW JAMB  
3' x 1'-0"



PLAN DETAIL - WINDOW JAMB  
3' x 1'-0"

SECTION DETAIL - SHIPLAP  
3' x 1'-0"

Issued / Revised		
No.	Date	Description
1	08.15.02	CITY SUBMITTAL

- General Notes:**
- A WINDOWS, FRAMES, AND SILLS BY OWNER.
  - B PLASTER FINISH BY OWNER.
  - C BRICK WORK, SHEET MEMBRANE, CONCRETE & REBAR BY CONTRACTOR.
  - D REDWOOD SHIPLAP SIDING, TRIM & BRICK PAINTING BY CONTRACTOR.

**Piper's Opera House  
Facade Stabilization**

Commission # 22002

**van Dijk Westlake Reed Leskosky  
Architects**

One East Camelback Road  
Suite 600  
Phoenix, Arizona 85012  
602 212-0451  
www.vrwl.com

**Facade Stabilization  
Details**










REVISIONS	BY

**FERRARI SHIELDS & ASSOCIATES**  
CONSULTING STRUCTURAL  
ENGINEERS  
180 Capital Place  
Reno, Nevada 89509  
775-827-5559 (Fax)  
office@ferrari-shields.com


**PIPER'S OPERA HOUSE  
FACADE  
RENO, NEVADA**

SHEET TITLE: SCHEMATIC 2ND FLOOR PLAN & ROOF PLAN

DRAWN	SAS
CHECKED	PAE
DATE	5/14/22
SCALE	1/4" = 1'-0"
JOB NO.	C0403
SHEET	S-1
OF	SHEETS



**SCHEMATIC 2ND FLOOR PLAN**  
SCALE: 1/4" = 1'-0"



**ROOF PLAN**  
SCALE: 1/4" = 1'-0"

NOTE: ALL ALPHA DETAIL REFERENCES ARE ON SHEET SD-2

PLEASE NOTIFY ENGINEER & ARCHITECT IF EXISTING CONDITIONS ARE DIFFERENT THAN SHOWN ON THE DRAWINGS

REVISIONS: 10/17/2021 10:00 AM 11/15/2021 11:00 AM 11/15/2021 11:00 AM 11/15/2021 11:00 AM



REVISIONS	BY


**FERRARI SHIELDS & ASSOCIATES**  
 CIVIL & STRUCTURAL ENGINEERS  
 185 Cadence Place  
 Reno, Nevada 89509  
 775-851-9259 (fax)  
 admin@ferrari-shields.com

**PIPER'S OPERA HOUSE**  
 FACADE  
 RENO, NEVADA

SHEET TITLE: EXTERIOR ELEVATION-SHORING SUPPORT @ FRONT FACADE WALL

DRAWN	SA
CHECKED	PAF
DATE	5/14/03
SCALE	1/2" = 1'-0"
JOB NO.	C0403
SHEET	S-2

OF SHEETS



**EXTERIOR ELEVATIONS-SHORING SUPPORT @ FRONT FACADE LOOKING WEST**

SCALE: 1/2" = 1'-0"

PLEASE NOTIFY ENGINEER & ARCHITECT IF EXISTING CONDITIONS ARE DIFFERENT THAN SHOWN ON THE DRAWINGS

SEE SH1 SD-2 FOR SHORING/REINF & S-6 FOR CONSTRUCTION SEQUENCE AND PHASING PLAN



REVISIONS	BY


**FERRARI SHIELDS & ASSOCIATES**  
CONSULTING STRUCTURAL  
ENGINEERS  
185 Cobble Place  
Reno, Nevada 89509  
775-839-9572 (fax)  
admin@ferrashields.com



**PIPER'S OPERA HOUSE**  
**FACADE**  
**RENO, NEVADA**  
SHEET TITLE: INTERIOR ELEVATION NEW CONCRETE FRAME @ FRONT FACADE WALL


DRAWN	SS
CHECKED	PAF
DATE	5/14/02
SCALE	1/2" = 1'-0"
JOB NO.	02493
SHEET	

**S-4**  
OF SHEETS



**INSIDE FACE-FRONT FACADE LOOKING EAST-NEW REINFORCED CONCRETE GUNITE FRAME**

SCALE: 1/2" = 1'-0"

SEE SHIT SD-2 FOR SHORING/REINF S-6 FOR PHASING PLAN DETAILS

PLEASE NOTIFY ENGINEER & ARCHITECT IF EXISTING CONDITIONS ARE DIFFERENT THAN SHOWN ON THE DRAWINGS

JANUARY 2004 (PRINT) FERRARI SHIELDS & ASSOCIATES, RENO, NV, USA


REVISIONS	BY

**FERRARI SHIELDS & ASSOCIATES**  
CONSULTING STRUCTURAL  
& CIVIL ENGINEERS  
1400 S. RENO, SUITE 100  
RENO, NEVADA 89509  
775-828-9277 (fax)  
admin@ferrari-shields.com

**PIPERS OPERA HOUSE  
FACADE  
RENO, NEVADA**

SHEET TITLE: INTERIOR ELEVATION NEW CONCRETE FRAME & EXTERIOR ELEVATION-SHORING SUPPORTS SOUTH WALL

DRAWN	SAS
CHECKED	RFW
DATE	5/14/02
SCALE	1/2" = 1'-0"
JOB NO.	02403
SHEET	5-5



**EXTERIOR ELEVATIONS-SHORING SUPPORT  
@ EXTERIOR FACE LOOKING NORTH**  
SCALE: 1/2" = 1'-0"

PLEASE NOTIFY ENGINEER & ARCHITECT IF EXISTING CONDITIONS ARE DIFFERENT THAN SHOWN ON THE DRAWINGS

SEE S-6 FOR CONSTRUCTION PHASING - CONSTRUCT SOUTH WALL AFTER FRONT FACADE (EAST WALL) HAS BEEN REINFORCED.

**INSIDE FACE-FRONT FACADE LOOKING SOUTH  
GUNITE CONC REINF @ INTERIOR FACE**  
SCALE: 1/2" = 1'-0"

SEE SHT S-6 FOR SHORING/REINF S-6 PHASING PLAN AND NOTES

DRAWING: Pipers Opera House, Reno, NV, 5/14/02, 10:17 AM


**SHORING/CONSTRUCTION SEQUENCE:**

**Front Façade (East Wall):**

- 1.) The front, 1977 facade of the east wall shall be reconstructed first; the south wall shall follow.
- 2.) The front facade shall be shored and reconstructed in three phases, as outlined in the phasing diagram on sheet S-6 of the plans.
- 3.) Install shoring/bracing as indicated on sheets S-2, 3, 4, and SB-1, prior to removing any of the existing construction. For example, the phasing diagram on sheet S-6 indicates that the first bay of construction is to begin with shoring installed in openings between bays G-F, and F-E, as well as column shoring/bracing at grids D, F, and E.
- 4.) Brace all vertical LVL beams of the east wall grids A through G, and the entire south wall with 2" diameter pipe "sit-up" braces securely anchored to both the LVL (at 2' above the second floor level) and to the ground at a 45 degree angle. Also, install the floor and roof ties shown in detail OG/SB-2.
- 5.) Remove brick per phase plan shown on sheet S-6. Carefully remove and store the brick for future use.
- 6.) Install veneer ties, architectural nomenclature, and concrete frame reinforcing per sheet SB-2.
- 7.) Granite the vertical wall columns per the construction phasing plan.
- 8.) Remove phase 2 brick, per sheet S-6, at the roof and second floor beam areas.
- 9.) Install veneer ties, architectural nomenclature, and concrete frame reinforcing per sheet SB-2.
- 10.) Granite the horizontal wall beams per the construction phasing plan.
- 11.) Repeat steps 3 through 10 until the front facade is completed.

**South Wall:**


- 12.) Begin the reconstruction of the south wall by providing the roof and floor shoring and bracing as shown on sheet S-5.
- 13.) Remove, reinforce, and granite the roof beam shown on S-6.
- 14.) Remove the exterior wythe of brick, the vertical column masonry, and the 6" square "keys" in area 1.
- 15.) Install the reinforcing, veneer anchors, and other hardware in area 1 per plans and details.
- 16.) Granite area 1.
- 17.) Repeat steps 12 and 14 through 16 for areas 2 and 3.



**PHASES OF CONSTRUCTION**

SCALE: 3/16" = 1'-0"  
FRONT FACADE (EAST WALL)  
INSIDE LOOKING OUT

**FACADE ORDER OF CONSTRUCTION:**  
1st BAY 1  
2nd BAY 2  
3rd BAY 3  
**ORDER OF GRANITE:**  
E2E PHASE 1  
E2E PHASE 2



**SOUTH WALL PHASE OF CONSTRUCTION**

SCALE: 3/16" = 1'-0"  
INSIDE LOOKING OUT

REVISIONS	BY


**FERRARI SHIELDS & ASSOCIATES**  
CONSULTING ARCHITECTURAL  
ENGINEERS  
185 Oakeside Place  
Reno, Nevada 89509  
775-343-5555 (Fax)  
admin@ferrarshields.com

**PIPER'S OPERA HOUSE  
FACADE  
RENO, NEVADA**


SHEET TITLE: FRAME REINFORCING CONSTRUCTION SEQUENCING AND PHASING PLAN

DRAWN	SK
CHECKED	PM
DATE	5/14/02
SCALE	3/16" = 1'-0"
JOB NO.	00493
SHEET	S-6


OF SHEETS




**107**  
SHORING BRACING DETAIL  
SCALE: 1" = 1'-0"




**108**  
SHORING BRACING DETAIL  
SCALE: 1" = 1'-0"




**109**  
DETAIL  
SCALE: 1-1/2\"/>




**110**  
DETAIL  
SCALE: 3/4\"/>




**102**  
DETAIL  
SCALE: 1\"/>




**105**  
DETAIL  
SCALE: 1\"/>



**101**  
DETAIL  
SCALE: 1-1/2\"/>



**112**  
DETAIL  
SCALE: 3/4\"/>



**100**  
DETAIL  
SCALE: 1-1/2\"/>

REVISIONS	BY

**FERRARI SHIELDS & ASSOCIATES**  
 ARCHITECTURAL  
 & CIVIL ENGINEERS  
 1850 Cadillac, Reno, NV 89509  
 775-785-8359 (fax)  
 775-785-8359 (cell)  
 admin@ferrarisshields.com

**PIPER'S OPERA HOUSE**  
 FACADE  
 RENO, NEVADA  
 SHEET TITLE: STRUCTURAL SHORING DETAILS

DRAWN	SAS
CHECKED	DMF
DATE	5/18/02
SCALE	AS SHOWN
JOB NO.	00403
SHEET	

**SD-1**  
 OF SHEETS

REVISIONS	BY


**FERRARI SHIELDS & ASSOCIATES**  
 CIVIL ENGINEERS  
 1835 Cadillac Place  
 Reno, Nevada 89509  
 775-784-5159 (fax)  
 admin@ferrarisai.com

**PIPER'S OPERA HOUSE  
 FACADE REINFORCED  
 RENO, NEVADA**


SHEET TITLE: STRUCTURAL DETAILS REINFORCED FACADE FRAME

DRAWN: SS  
 CHECKED: PMF  
 DATE: 5/14/02  
 SCALE: AS SHOWN  
 JOB NO.: CD403  
 SHEET


**SD-2**  
 OF SHEETS




**DETAIL M-M**  
 SCALE: 3/4" = 1'-0"




**DETAIL H-H**  
 SCALE: 3/4" = 1'-0"




**DETAIL D-D**  
 SCALE: 3/4" = 1'-0"




**DETAIL L-L**  
 SCALE: 3/4" = 1'-0"




**DETAIL G-G**  
 SCALE: 3/4" = 1'-0"




**DETAIL C-C**  
 SCALE: 3/4" = 1'-0"




**DETAIL P-P**  
 SCALE: 1" = 1'-0"




**DETAIL K-K**  
 SCALE: 1" = 1'-0"



**DETAIL F-F**  
 SCALE: 3/4" = 1'-0"




**DETAIL B-B**  
 SCALE: 1" = 1'-0"




**DETAIL N-N**  
 SCALE: 1" = 1'-0"



**DETAIL C-C**  
 SCALE: 1" = 1'-0"



**DETAIL E-E**  
 SCALE: 1/2" = 1'-0"



**DETAIL A-A**  
 SCALE: 1-1/2" = 1'-0"

2025 RELEASE UNDER E.O. 14176

# a historic restoration for piper's opera house

b street  
virginia city, nv

plan review 3.6.06



© 2006 anthony smith architect

a historic restoration for  
piper's opera house  
b street  
virginia city, nv

### design team

#### architect

Anthony Smith Architecture  
860 Sandhill Road, Suite 201  
Reno, NV 89521  
(775) 333-6773  
Fax: (775) 333-6775

#### structural

Ferran Shields & Associates  
185 Cadillac Place  
Reno, NV 89509  
(775) 829-9227  
Fax: (775) 829-9359

### sheet index

A0.1 Cover Sheet

#### structural

- SN-1 Structural Notes
- SN-2 Structural Notes
- S-1 Foundation Plan / Floor Framing Plan
- SD-1 Structural Details
- SD-2 Structural Details

#### architectural

- A1.0 Partial First Floor Plan / Stair Cross-Section / Stair Elevation
- A2.0 Partial Second Floor Plan

### project information

**building code:** 2003 International Building Code  
**address:** B Street, Virginia City, Nevada  
**fire sprinklered:** Yes  
**construction type:** V - B  
**occupancy group:** A-1 (Assembly)

revisions

drawn:	sm / sjp
checked:	sjp
date:	march 6, 2006
scale:	as noted
project no:	0543

cover sheet

# A0.1





11/20/2006 10:54 AM From: Chiew (300) Subject: PIPERS OPERA HOUSE, RENO, NV - R000201.DWG

- 4.3. The slumps indicated above are for unplastized concrete. Larger slumps may be attained through the use of a superplasticizer.
- 4.4. Admixtures for concrete shall comply with ISO 1906.5 and ACI 318, Sec. 3.6.
- 4.5. Evaluation and acceptance of concrete shall conform with ACI 318, Sec. 3.6. In addition to the two cylinders required, make two additional cylinders (total of four for each test). One cylinder shall be tested at 7 days.  
If the 7-day break is less than 80% of the specified 28-day strength, the Contractor shall investigate and make any corrections or changes as necessary to ensure future concrete will reach the specified strength.  
If the average of the two 28-day strengths is below the acceptable limits, test the fourth cylinder at 56 days.

- 4.6. Prior to placing concrete, approval shall be obtained from the Engineer or local building agency for sleeves, openings, or other attachments not shown on the drawings.
- 4.7. Use the following cover on reinforcement in cast-in-place concrete, unless noted otherwise on the drawings:
 

3"	Concrete cast against and permanently exposed to earth.
2"	Concrete exposed to earth or weather, #5 bars or larger.
1-1/2"	Concrete exposed to earth or weather, #5 bars and smaller.
3/4"	Concrete not exposed to weather or in contact with ground, #1 bar and smaller.
1-1/2"	Concrete not exposed to weather or in contact with ground, #2 & #3 bars.
1-1/2"	Beams, columns and piers, cover over ties.
3/4"	Slabs and walls, formed above grade not exposed to weather.
1-1/2"	Clear to top for reinforcement in slabs-on-grade.

- 4.8. Concrete walls shall be reinforced as follows unless detailed otherwise (this reinforcement does not apply to basement walls or retaining walls; advise the Engineer if reinforcement is not specified):
 

Wall Thickness	Reinforcement Location	Horizontal Bars	Vertical Bars
6"	Center of Wall	#4 @ 18"	#4 @ 18"
8"	Center of Wall	#5 @ 18"	#5 @ 18"
10"	Each Face	#4 @ 18"	#4 @ 18"
12"	Each Face	#4 @ 18"	#4 @ 18"

- 4.9. Provide matching foundation dowels for all vertical bars, unless detailed otherwise.
- 4.10. Provide standard hooks per ISO 1907.1 and ACI 318, Sec. 7.1, unless detailed otherwise.
- 4.11. Use 1" or (1) bar diameter, whichever is greater, minimum clear distance between parallel reinforcing bars, including spliced bars. For bonded bars, use an effective diameter, based on the total area of the bond, to establish the required clearance.
- 4.12. Provide lap splices, welded splices, mechanical connections, and developments of standard hooks as specified in ACI 318, Ch. 12. Make lap splices only at the locations shown on the drawings, as indicated in these notes, or as approved in advance by the Engineer.  
For normal weight concrete, use the minimum lap splice lengths listed below, but not less than 24", unless detailed otherwise:
 

Bar Size	Top Bars	Other Bars
#3 - #6	(7) Bar Dia.	(7) Bar Dia.
#7 - #11	(9) Bar Dia.	(9) Bar Dia.

- \*Top bars\* are horizontal bars with more than 12" of fresh concrete cast below the bars.  
Lap splice lengths listed above apply only when the clear distance between bars, including lapped reinforcement, is (2) bar diameters or greater and clear cover is not less than (1) bar diameter. When the clear distance between bars is less than (2) bar diameters or the clear cover is less than (1) bar diameter, increase the splice length by 50%.

- 4.13. Provide 3/4" chamfer on all exposed corners of concrete, unless shown otherwise on Architectural details.
- 4.14. Roughen the existing concrete surface at the interface of construction joints to an amplitude of approximately 1/4", except where a key is specifically indicated or where the use of a bond breaker is indicated. Immediately before new concrete is placed, thorough wet the interface surface and remove any standing water.
- 4.15. Where new concrete is deposited against concrete that is greater than 28 days old, thoroughly clean existing surfaces of laitance and foreign material and saturate with water. Remove all standing water prior to placement of new concrete. Roughen the existing surface to an amplitude of 1/4".
- 4.16. Securely tie all reinforcement before placing concrete.

- 5. REINFORCEMENT (ISO Ch 19)
  - 5.1. Reinforcement shall conform to ISO 1903.5, ACI 318, Sec. 3.5, and ASTM A615 and A705. Welded Wire Fabric shall conform to ISO 1903.5, ACI 318, Sec. 3.5, and ASTM A185.
  - 5.2. Use A615, Grade 60 reinforcement for concrete, ISO.
  - 5.3. Bend reinforcing steel cold, unless directed otherwise by the Engineer.
  - 5.4. Promptly notify the Engineer if conditions arise where there are insufficient minimum clear distances or where construction problems related to congestion are encountered.

- 6. CONNECTIONS TO CONCRETE AND CONCRETE INSERTS (ISO Ch 19)
  - 6.1. Epoxy grout reinforcing dowels and threaded rod (ASTM A36, unless noted otherwise) using Simpson SBT adhesive system per ISO Report BR-5279. Covers DCA-01 TB06 adhesive system per ISO Report BR-5286. Hilti HIT-150 adhesive system per ISO Report BR-5173, or Hilti/Resbond EPOC adhesive system per ISO Report BR-4289. Alternate anchorage systems require written pre-approval of the Engineer. Install according to the Manufacturer's printed instructions.
  - 6.2. Install Simpson SBT adhesive anchors in concrete per ISO Report BR-5279 and the Manufacturer's printed instructions.
  - 6.3. Install Hilti HIT adhesive anchors in concrete with HIT HV-150 adhesive per ISO Report BR-5173 and the Manufacturer's printed instructions.
  - 6.4. Use wedge and expansion anchors as manufactured by Simpson or Hilti, or an approved equal. Install according to the Manufacturer's printed instructions.

- 7. STRUCTURAL STEEL (ISO Ch 22)
  - 7.1. Structural steel detailing, fabrication, and erection shall conform to ISO Ch. 22 and AISI "Code of Standard Practices For Steel Buildings and Bridges."
  - 7.2. Wide flange shapes ("W", "WT") shall be ASTM A992 (Fy = 50 ksi); where ASTM A992 is not available, ASTM A36/F432 Dual Certification (Fy = 50 ksi) may be substituted. Channel and Angle shapes ("C", "MC", "L", "M") shall be ASTM A36/F212 Dual Certification (Fy = 50 ksi). Plates, bars, and other miscellaneous shapes shall be ASTM A36 (Fy = 35 ksi).  
Structural tubing (ST) shall be ASTM A500, Grade B (Fy = 46 ksi).  
Pipe columns shall be ASTM A53, Grade B, Type E or C (Fy = 35 ksi).
  - 7.3. Bolts indicated as machine bolts (MB) or anchor bolts (AB) shall be ASTM A307. Threaded rod shall be ASTM A36.

- 7.4. Welding shall conform to AWS Structural Welding Code-Steel (AWS D1.1). Certified welders shall perform all welding.  
Use E7018 electrodes (E6018 at high-gauge steel studs) with a minimum Charpy V-Notch toughness (CVN) of 27 J (-10° F).  
At complete penetration welds, backing bars shall be removed and welds repaired on both sides with E7018 welds.

- 7.5. Heated stud anchors (MS) shall be Type 30L, by TRW-Nelson, or approved equal. Where not noted, use 3/4" diameter studs. Structural steel to receive MS's shall be free from paint or patches with primers that allows welding of studs. Install according to the Manufacturer's printed instructions.
- 7.6. Base plate holes for anchor bolts may be oversized as follows:
 

Anchor Bolt Dia.	Hole Size
3/4" - 1 1/8"	1/16" Oversized
1" - 2"	1/8" Oversized
Over 2"	1" Oversized

- 7.7. Use non-weldable, non-brick grout under base plates. Install according to the Manufacturer's printed instructions.
- 8. SAWN LUMBER, TIMBER, AND MANUFACTURED WOOD PRODUCTS (ISO Ch 23)
  - 8.1. All rough framing shall conform to the requirements of ISO Ch. 23 and the 2001 "National Design Standards for Wood Construction."
  - 8.2. For sawn lumber, use Douglas Fir-Larch per 2001 "National Design Standards for Wood Construction," Tables 4A and 4D, of the following minimum grades, unless noted otherwise on the plans:
 

Description	Grade	Allowable Stress	Mod. of Elasticity
2x and 4x Beams and Stringers	No. 2	70 - 900 psi	E = 1,600 ksi
Post and Timbers	No. 1	70 - 1,350 psi	E = 1,600 ksi
	No. 3	70 - 1,000 psi	E = 1,600 ksi

- Use pressure-treated Douglas Fir-Larch No. 2 for all plates and wood within 6" of earth. (Note: Special framing hardware requirements apply when using pressure-treated lumber. See framing hardware note below.)
- 8.3. Use prefabricated plywood wet joists as manufactured by True Joist, and of the type and size indicated on the plans. Substitute products from other manufacturers require prior written approval from the Engineer.  
Design for the loads given in Section 2.3 of these Notes, unless noted otherwise on the plans.
- 8.4. Use Microlam (LVL) and Parallel (PSL) beams and TimberStrand (LSL) beams, studs and rim boards as manufactured by True Joist, of the type and size indicated on the plans, and with the following minimum properties:
 

Description	Allowable Stress	Mod. of Elasticity
Microlam (LVL)	Fb = 2,600 psi	E = 1,900 ksi
Parallel (PSL)	Fb = 2,900 psi	E = 2,000 ksi
TimberStrand (LSL)	Fb = 1,700 psi	E = 1,900 ksi

- Blocking, stiffeners and hangers are the responsibility of the Manufacturer, unless specifically indicated on the plans.  
Substitute products from other manufacturers require prior written approval from the Engineer.

- 8.5. Structural Glued Laminated Timbers (glulam) shall comply with ANSI/AITC A190.1 and ASTM D 3737. Use Douglas Fir-Larch connections as follows, unless noted otherwise:
 

Single Spans	DF-24FV1
Continuous Spans <th>DF-24FV8</th>	DF-24FV8

- 8.6. Plywood sheathing nailing for shear walls and diaphragms is indicated on the drawings or in these Notes. The following abbreviations are used to designate nailing in details and schedules:
 

Abb.	Typical to all blocking over walls and elements indicated to act as shears.
BN	Boundary nailing
CK	Continuous edge nailing
EN	Edge nailing
FN	Field nailing

- 8.7. Wall sheathing shall be APA rated sheathing, Exposure I, as follows:
 

Thickness	Plywood
Minimum Nailing: 8d, 8N-6", 8N-6", 8N-12"	15/32"

 Oriented strand board (OSB) SHALL NOT BE USED in place of plywood for wall sheathing.  
Provide 2" blocking along all edges not supported by studs.
- 8.8. Roof sheathing shall be APA C-D Span Rated panels, Exposure I, as follows:
 

Min. Thickness	Plywood	Span Index
Minimum Nailing: 8d, 8N-6", 8N-6", 8N-12"	19/32" or 5/8"	32/16

 Oriented strand board (OSB) meeting the requirements for "wood structural panels" as defined in ISO 2303 may be substituted for plywood roof sheathing, provided such product also meets the required APA Rating.  
Note that particleboard is not included in the definition of wood structural panels, and may not be used as such.

- 8.9. Floor sheathing shall be STUDBOARD-FLOOR, as follows:
 

Thickness	Plywood
Minimum Nailing: 10d, 8N-6", 8N-6", 8N-10"	3/4"

 Nail with 10d ring or screw-shank nails and glue to supports. Apply glue as recommended by APA and the Glue Manufacturer.
- 8.10. Lay plywood for floors and roofs with face grain perpendicular to joists and with end joints staggered. Where panels are less than 24" wide, block all edges.
- 8.11. Attach nail plates using 5/8" dia. anchor bolts at 32" maximum, unless noted otherwise. Use 12" bolt length for 3x or 4x plates, 18" bolt length for 2x plates. Each anchor bolt shall be equipped with a minimum 2" x 2" x 3/16" plate washer (Simpson B578-2, or equivalent).

- Each separate length of nail plates shall be attached with a minimum of (2) of the specified anchor bolts. Each bolt is in addition to any bolts used for hidden anchorage.
- 8.12. For wood to wood nailed connections, use spacing and edge distances of (1) diameters and (6) diameters, respectively, or as required to avoid splitting the wood.
- 8.13. Where required to avoid splitting, pre-drill holes with a drill bit diameter equal to the next smaller nail diameter.
- 8.14. Where nails will be exposed to weather, use zinc coated, aluminum alloy wire, or stainless steel nails conforming to ISO 2309.9.

- 8.15. For members resisting wind or seismic loads, use common nails only; box nails and sinkers (OS) nails are not acceptable unless approved in writing by the Engineer. Members resisting wind or seismic loads include, but are not limited to: roof and floor diaphragm sheathing nailing; shearwall sheathing nailing; diaphragm and shearwall blocking and bracing; overlying plate nailing; gable bracing and blocking; and splices to double top plates.
- 8.16. Use the following minimum Nailing Schedules (Notes: This schedule is more restrictive than that contained in ISO Table 2303.2.1):
 

	Notes
Joists to wall or girder, toenail	(3) 10d
Brackets to joist, toenail each end	(2) 10d
Double top plates, face nail	(4) 10d
Top plate to stud, end nail	(2) 10d
Stud to sole plate, toenail	(3) 16d
or end nail	(2) 8d
Doubled studs, face nail	16d @ 16"
Double top plates, face nail	16d @ 12"
Continuous header, two pieces, along each edge	16d @ 12"
Colling joist to plate, toenail	(1) 8d
Continuous header to stud, toenail	(1) 8d
Joists, laps over partitions, face nail	(2) 16d
Colling joists to parallel rafters, face nails	(3) 16d
Rafters, joists to plate, toenail	(3) 10d
Blocking between joists or rafters to top plate	(1) 8d
Rim joist to top plate or sill plate, toenail	(3) 16d @ ea block
Build-up corner studs	16d @ 16"
Build-up beams, each side, staggered	16d @ 16"

- The quantities and spacings listed are for common nails; except for members resisting wind or seismic loads, 16d Sinkers (16d OS) may be substituted at the same quantities and spacings as specified above.

- 8.17. Provide W1, W2.5 or W3.5A ties for all rafters, roof trusses or roof joists, unless noted otherwise.
- 8.18. Use framing hardware as manufactured by Simpson Strong-Tie or United Steel Products (USP), and of the type and size indicated on the plans. Install as recommended by the Manufacturer. Where hardware can be specified with different size fasteners, use the largest fastener, unless noted otherwise.  
Alternate hardware requires Engineer's approval prior to installation. Submit proposed equivalent and ISO-93 Report for each alternate item. Contractor/Installer assumes full liability resulting from the use of non-approved framing hardware including, but not limited to, product and framing performance.  
Framing hardware shall be hot-dip galvanized (60 minimum coating) or painted. Hardware in contact with pressure-treated lumber shall be hot-dip galvanized (99 minimum coating). Hardware in contact with lumber pressure-treated with Alkaline Copper Quaternary (ACQ) or ACQ-B (Barbanelite), Copper Azole (CA-A or CA-B), or BSA (ECOT) shall be hot-dip galvanized (915 minimum coating) or stainless steel. Hardware in contact with lumber pressure-treated with Ammoniacal Copper Zinc Arsenate (ACZA) or other products containing an amoniac carrier shall be stainless steel.

- 8.19. Where holdowns are indicated at ends of shear walls, nail the sheathing to the member to which the holddown is connected. Use the same nailing specified for plywood panel edges.
- 8.20. All detailing, fabrication, and erection of gullies and gutters shall be according to ATCO Specifications. Give special care to the protection of gullies members that are to be exposed to weather.
- 8.21. Give special attention to the bearing surfaces of columns to ensure that members fit tightly and that interfacing surfaces are true.
- 8.22. Use ASTM A307 Machine Bolts and use washers where bolts are not or not bears on wood. Drill holes 1/32" to 1/16" larger in diameter than the bolt.

- 8.23. Use ASTM A307 or ASTM A36 Lag Screws and use washers where head bears on wood. Drill lead holes as follows:
 

Lag Dia.	Lead Hole Dia.
3/8"	11/16"
1/2"	15/16"
5/8"	7/8"
3/4"	1 1/16"

- 8.24. For non-bearing interior walls on concrete slabs-on-grade, shoot sole plates to the floor using 2-1/2" long by 0.185" diameter powder-actuated pins, spaced 6" from ends and at 12" maximum elsewhere. Install according to the Manufacturer's printed instructions.
- 8.25. Where multiple joists, rafters or trusses in diaphragms and multiple studs in shear walls are required and plywood edges fall at the interface of the members, connect the multiple members together as required to transfer diaphragm shear.

- 9. MISCELLANEOUS
  - 9.1. Install and anchor mechanical, plumbing and electrical equipment, including ducts, pipes and conduits, to the structure in accordance with ISO 1601. Submit shop drawings for review to the Mechanical or Electrical Engineer, respectively. The Contractor shall provide any additional structural supports required within the floor or roof structure. Enclosures, fasteners or any other element providing stability for equipment require an ISO-93 report or an equivalent testing report, showing the product to be capable of transmitting side required forces.

- 10. SPECIAL INSPECTION (ISO Ch 17)
  - 10.1. Provide for special inspection in compliance with ISO 1704 as follows:
    - 10.1.1. Concrete: Special inspection is not required for foundations; design is based on a concrete compressive strength of 3,500 psi.
    - 10.1.2. Bolts Installed in Concrete: Special inspection is not required for anchor bolts, except where specifically noted on the plans.
    - 10.1.3. Adhesive Anchor Bolts: Special inspection is required for adhesive anchor bolts. For Simpson SBT anchors, conduct special inspection per ISO Report BR-5279, Sec. 2.6. For other products, refer to the appropriate ISO-93 Report.
    - 10.1.4. Welding: Continuous special inspection is required for all structural welding, including reinforcing steel, except inspection may be periodic for:
      - 10.1.4.1. Single-pass fillet welds not exceeding 5/16" in size.
      - 10.1.4.2. Headed stud anchor (MSA) welding.
  - 10.2. Special inspection is not required for welding done in an approved fabricator's shop per ISO 1704.2.2, subject to approval of the building department having jurisdiction.

REVISIONS	BY

**FERRARI SHIELDS & ASSOCIATES**  
 CONSULTING STRUCTURAL ENGINEERS  
 775-828-9377 (fax)  
 775-828-9377 (cell)  
 www.ferrari-shields.com


**PIPER'S OPERA HOUSE**  
**2005 BUDGET PROJECTS & NEW ENTRY STAIR**  
**RENO, NEVADA**  
 STRUCTURAL NOTES




DATE	6/2006	DATE	JUN 30 2007
DRAWN	SN	DATE	5/24/06
CHECKED	SN	SCALE	NONE
DATE	5/24/06	JOB NO.	058405059

**SN-2**






115 STD - ISOL JT @ INT COL  
SCALE: 3/4" = 1'-0"



111 STD - BM TO GIRDER CONN  
SCALE: NO SCALE



107 STD - DBL ANGLE SHEAR CONN (TYPE II CONN)  
SCALE: NO SCALE

NOMINAL DEPTH, "D"	A325N BOLTS	LENGTH OF ANGLES	ANGLE THK, "t"	ALLOY LOAD
8, 10	(2) 1/2"	5/8"	1/4"	29.4K
12, 14	(3) 3/8"	5/8"	1/4"	46.2K
16, 18, 21	(4) 1/2"	1 1/8"	1/4"	63.1K
24, 27	(5) 3/4"	1 1/8"	3/8"	99.2K
30, 33, 36	(6) 1"	1 7/8"	3/8"	128K


CONTINUOUS WALL FOOTING SCHEDULE

SCALE: NONE


MARK	WIDTH	THICKNESS	CONT REINF "A"	TRANSV REINF "B"
CF1	1'-0"	16"	(2) #4	---
CF2	1'-2"	16"	(2) #4	---
CF3	1'-4"	16"	(2) #4	---
CF4	3'-0"	1'-0"	(3) #4	---
CF5	3'-0"	1'-2"	(3) #5	---
CF6	3'-0"	1'-4"	(4) #5	---
CF7	3'-0"	1'-6"	(4) #6	---
CF8	4'-0"	1'-8"	(5) #6	---
CF9	3'-0"	1'-8"	(5) #6	#4 @ 12"
CF10	6'-0"	1'-8"	(6) #6	#5 @ 14"

FOOTINGS DESIGNED FOR A MAXIMUM OF 3000 PSF SOIL PRESSURE.


114 STD - GROUT UNDER BASE PLATE  
SCALE: NO SCALE




113 STD - ISOL COL FTG  
SCALE: 3/4" = 1'-0"




109 STD - BEAM TO COLUMN CONN  
SCALE: NO SCALE




105 STD - FULL HEIGHT WEB STIFFENER  
SCALE: NO SCALE



112 STD - BEAM TO SPANDEL CONNECTION  
SCALE: NO SCALE



108 STD - BEAM TO TS COLUMN CONN  
SCALE: NO SCALE



104 STD - PC & TS COL BASE PLATE  
SCALE: NO SCALE

REVISIONS	BY

**FERRARI SHIELDS & ASSOCIATES**  
CONSULTING STRUCTURAL ENGINEERS  
885 Colville Street  
Reno, Nevada 89509  
775-829-8219 (Fax)  
www.ferrari-shields.com

**PIPER'S OPERA HOUSE**  
2005 BUDGET PROJECTS & NEW ENTRY STAIR  
RENO, NEVADA

PROJECT TITLE: STRUCTURAL DETAILS

DATE: 6/2006 JUN 30 2007


SCALE: AS SHOWN

JOB NO: CSM00022


SHEET: SD-1

DRAWN: SAS  
CHECKED: DAF  
DATE: 5-20-02-27-08  
SCALE: AS SHOWN  
JOB NO: CSM00022  
SHEET: SD-1


H:\WORKING\Opera House 2005 Budget Projects\Structural\SD-1.dwg, 11/20/06, 1:02:38 PM




**127** DETAIL  
SCALE: 1" = 1'-0"




**123** DETAIL  
SCALE: 3/4" = 1'-0"




**119** DETAIL  
SCALE: 1-1/2" = 1'-0"




**128** DETAIL  
SCALE: 1" = 1'-0"




**126** DETAIL  
SCALE: 1" = 1'-0"




**123** DETAIL  
SCALE: 1" = 1'-0"




**118** DETAIL  
SCALE: 1-1/2" = 1'-0"




**125** DETAIL  
SCALE: 1" = 1'-0"




**126** DETAIL  
SCALE: 1" = 1'-0"




**123** DETAIL  
SCALE: 1" = 1'-0"




**121** DETAIL  
SCALE: 3/4" = 1'-0"



**124** DETAIL  
SCALE: 1-1/2" = 1'-0"



**123** DETAIL  
SCALE: 1" = 1'-0"



**116** DIAG BRACE DETAIL  
SCALE: 1" = 1'-0"

REVISIONS	BY

**FERRARI SHIELDS & ASSOCIATES**  
CONSULTING STRUCTURAL ENGINEERS  
1185 Caliente, Reno, Nevada 89509  
775-325-5353 (Fax)  
www.ferrari-shields.com


**PIPER'S OPERA HOUSE**  
2005 BUDGET PROJECTS & NEW ENTRY STAIR  
RENO, NEVADA

PROFESSIONAL ENGINEER  
PAUL J. SHIELDS  
No. 4214  
DATE: JUN 30 2009  
EXP: JUN 30 2009


DRAWN: SAK  
CHECKED: PAF  
DATE: 6-20-09  
SCALE: AS SHOWN  
JOB NO.: 09040009  
SHEET: 11

**SD-2**


H:\2009\0904 - Piper's Opera House\2009 Budget Projects\09040009.DWG, 6/23/09, 1:58:31 PM




**1** section  
wood cap & 1 1/2\"/>



**B** elevation @ stair  
1/4\"/>



**A** cross section @ stair  
coordinate all dimensions & components of structure prior to construction  
1/4\"/>



ground level floor plan  
1/4\"/>

plan review 3.6.06



© 2006 Anthony Smith Architecture

a historic restoration for  
**piper's opera house**  
125 North 3rd Street  
Virginia City, NV

revisions


drawn:	ms / sjp
checked:	sjp
date:	march 6, 2006
scale:	as noted
project no:	0543



**A1.0**

Anthony Smith Architecture, Inc. is not responsible for the accuracy or completeness of reproductions of this document generated by other than electronic means.

Anthony Smith Architecture is not responsible for the accuracy or completeness of reproduction of this document generated by other than electronic means.



second level floor plan



second level floor plan

revision	date	by

drawn:	acj / sp
checked:	sp
date:	march 6, 2006
scale:	as noted
project no:	0543

A2.0

plan review 3-6-06



© 2006 anthony smith and associates

a historic restoration for  
**pipe's opera house**  
 120 1/2 street  
 virginia city, nv

anthony smith architecture  
 400 north main street, 301  
 virginiacity, nevada 89401  
 P 775.332.8773 www.anthony-smith.com

# PIPER'S OPERA HOUSE VIRGINIA CITY, NEVADA THEATRE MODERNIZATION

## ALLOWABLE BATTEN LOADS

Span between lift lines	8'	9'	10'	11'	12'
<b>1-1/4" Schedule 40 Pipe 2.27 Lb/Ft</b>					
Uniform load at 1/3 of yield <sup>1</sup> (lbs/ft)	35	28	22	18	15
Uniform load at 1/360 deflection <sup>2</sup> (lbs/ft)	31	22	16	12	9
Point load at 1/3 of yield <sup>3</sup> (lbs)	119	107	96	88	82
Point load at 1/360 deflection <sup>4</sup> (lbs)	82	65	52	43	36
<b>1-1/2" Schedule 40 Pipe 2.72 Lb/Ft</b>					
Uniform load at 1/3 of yield <sup>1</sup> (lbs/ft)	49	39	31	25	24
Uniform load at 1/360 deflection <sup>2</sup> (lbs/ft)	49	34	25	19	15
Point load at 1/3 of yield <sup>3</sup> (lbs)	165	147	133	121	112
Point load at 1/360 deflection <sup>4</sup> (lbs)	130	103	83	69	58
<b>1-1/2" Schedule 80 Pipe 3.63 Lb/Ft</b>					
Uniform load at 1/3 of yield <sup>1</sup> (lbs/ft)	62	48	39	32	26
Uniform load at 1/360 deflection <sup>2</sup> (lbs/ft)	62	43	32	24	18
Point load at 1/3 of yield <sup>3</sup> (lbs)	209	186	169	154	142
Point load at 1/360 deflection <sup>4</sup> (lbs)	164	130	105	87	73
<b>2" Schedule 40 Pipe 3.65 Lb/Ft</b>					
Uniform load at 1/3 of yield <sup>1</sup> (lbs/ft)	86	67	54	44	37
Uniform load at 1/360 deflection <sup>2</sup> (lbs/ft)	105	74	54	41	31
Point load at 1/3 of yield <sup>3</sup> (lbs)	283	253	228	208	192
Point load at 1/360 deflection <sup>4</sup> (lbs)	279	221	179	148	124

- (1) Allowable load in pounds per foot of batten at 1/3 of yield.
- (2) Allowable uniform load with a maximum deflection of 1/360 between pickup lines.
- (3) Maximum concentrated load in pounds at midpoint between pickup lines at 1/3 yield.
- (4) Concentrated load at midpoint between pickup lines with deflection of 1/360.


© 2004 by J.R. CLANCY, INC.

Permission is granted make copies of this document if the J R Clancy information and this copyright notice are retained. Modification or editing of this document is not permitted.

PIPER'S OPERA HOUSE - Weights			
Item	Qty.	Unit Wt. lbs.	Total Wt.-lbs.
ETC Source Four Ellipsoidals—lighting instrument	60	14.0	840
ETC Panels—lighting instrument	20	7.5	150
ETC Panel EA—lighting instrument	20	8.0	160
Selecon 4' Cyc Lights	8	31.0	248
ETC 6' Connector Strips—lighting circuit distribution	12	60.0	720
ETC 14' Connector Strips—lighting circuit distribution	2	140.0	280
ETC Pigtail Boxes for light ladders	10	20.0	200
Misc. Cables			20
2" Upper Pipe Supports—sch. 40	112'	3.7	408
1 1/2" Sch. 40 black pipe for raceways 5 X 42"	210'	1.7	570
1 1/2" Pipe Grid—sch. 40	476'	2.7	1,290
1 1/2" Pipe Clamps	50		30
Misc. nuts, bolts, shackles,			50
H & H Specialties—3 curtain tracks, 400 series			300
1/4" System 3 Proof Coil Chain	800'	1.4	1,104
Old Time Advertising Canvas Drop	1		60
All/ Curtains (except valance & tormento legs)			1,050
<b>GRAND TOTAL WEIGHT:</b>			<b>7,480</b>

Based on Grand Total Weight of 7,480 lbs.  
 1,260 sq. ft. grid = 5.94 lbs./sq. ft. Grand Total  
 Distributed weight below Upper Pipe & Beams 7,072 lbs.  
 Based on 48 drop points below upper pipe & beams =147 lbs. ea. drop point

\*\*\*Does not include electrical conduit, wiring, & other electrical needs by Electrical Contractor



**FLEX-A-LITE WEST**


10250 Aldbaran Drive  
 Reno, Nevada 89506  
 775-477-7711  
 775-677-7671 fax  
 775-742-7600 cell  
 mike@flexlite.com  
 CSL #9311

**Project:** Piper's Opera House Theatre Renovation  
**Location:** Virginia City, Nevada  
**Drawing Title:** FRONT ELEVATION  
**Scale:** 1/4" Page: 25 Date: JUNE 1 2008  
**Drawn By:** Mike Ross

**FRONT ELEVATION** 1/4" SCALE





SIDE ELEVATION	
1	Valance
2	Tormentor Leg
3	#1 Electric
4	Grand Drape
5	#2 Electric
6	#1 Border
7	#1 Leg
8	#3 Electric
9	#2 Border
10	#2 Leg
11	Mid Stage Traveller
12	#4 Electric
13	#3 Border
14	#3 Leg
15	#5 Electric
16	Up Stage Traveller
17	Old Time Advertising Canvas Drop



**FLEX-A-LITE WEST**

10001 F. COLEMAN, DUBLIN, CA 94568  
 708-977-7877 fax  
 708-977-7877 tel  
 115-142-7000 corp  
 info@flexalite.com  
 920-983-1111

Project: Piper's Opera House Theatre Renovation  
 Location: Virginia City, Nevada  
 Drawing Title: SIDE ELEVATION  
 Scale: 1/4" Page: 2 of 5 Date: JUNE 5, 2008  
 Drawn By: Mike Ross





LIGHTING CIRCUITS & DRAPERY LAYOUT	
1	Electric Projection Screen 16h X 16w
2	Valance
3	Tormentor Legs
4	#1 Electrics
5	#1 Light Ladder/Pipe
6	Grand Drap
7	#2 Electrics
8	#2 Light Ladder
9	#1 Leg
10	#1 Border
11	#3 Electrics
12	#3 Light Ladder
13	#2 Leg
14	#2 Border
15	Mid Stage Traveller
16	#4 Electrics
17	#4 Light Ladder
18	#3 Leg
19	#3 Border
20	#5 Light Ladder
21	#5 Electrics
22	Floor Pockets
23	Upstage Black Traveller
24	Old Time Advertising Canvas Drop
FP	Floor Pockets
ND	Non Dim Circuits

LIGHTING CIRCUITS + DRAPERY LAYOUT 1/4"


**FLEX-A-LITE WEST**

10250 Akabaran Drive  
Reno Nevada 89506  
775-877-7771  
775-877-7577 fax  
775-742-7800 cell  
mikesagan@aol.com  
CSI: #0311

Project: Piper's Opera House Theatre Renovation  
Location: Virginia City, Nevada  
Drawing Title: LIGHTING CIRCUITS + DRAPERIES  
Scale: 1/4" Page: 3 of 5 Date: JUNE 16, 2008  
Drawn By: Mike Ross




PIPE GRID REFLECTED  
1/4" SCALE CEILING






**FLEX-A-LITE WEST**  
 10250 Alcebran Drive  
 Reno, Nevada 89506  
 775-877-7711  
 775-877-7577 fax  
 775-743-7600 cell  
 mike@flexalite.com  
 CSL #8311

Project: Piper's Opera House Theatre Renovation  
 Location: Virginia City, Nevada  
 Drawing Title: PIPE GRID  
 Scale: 1/4" Page: 4 of 5 Date: 11/15/10  
 Drawn By: Mike Ross



PIPE GRID ATTACHMENT  
1/4" SCALE

Project: Piper's Opera House Theatre Renovation  
 Location: Virginia City, Nevada  
 Drawing Title: UPPER PIPE SUPPORTS  
 Scale: 1/4" = 1'-0" Date: June 5, 2008  
 Drawn By: Mike Ross  
 Flex-A-Lite West  
 12520 Ardmore Drive  
 Reno, Nevada 89504  
 775-811-1111  
 775-742-7500 cell  
 775-742-7527 fax  
 mkrass@flexalite.com  
 CST #8311



PIPE JOINTS T.B. ALTERNATED



LOCATION: STAGE LEFT										NEMA RATING ↓	
TYPE	DIRECTORY	LOAD	BKR	CR	CR	BKR	LOAD	DIRECTORY	TYPE		
EMERGENCY LIGHTS		3P	11	→	2	3P		STAGE LEFT UPPER BAY			
ATTIC LIGHT		3P	13	→	4	3P					
FRONT STAGE RIGHT		3P	15	→	5	3P		DINNER BUFFET			
FRONT STAGE LEFT		3P	17	→	6	3P					
BACK STAGE SPOT		3P	19	→	10	3P		RECEPT			
PREPETER WORK LIGHT		3P	21	→	12	3P		RESTROOM RECEPT			
SPARE NOT USED		3P	23	→	14	3P		RECEPT			
CENTER WORK LIGHTS		3P	25	→	16	3P		RECEPT			
RECEPTS		3P	27	→	18	3P		RECEPT			
RECEPTS		3P	29	→	20	3P		HEATER RECEPT			
RECEPTS		3P	31	→	22	3P					
RECEPTS		3P	33	→	24	3P					
RECEPTS		3P	35	→	26	3P		RECEPT			
RECEPTS		3P	37	→	28	3P		RECEPT			
RECEPTS		3P	39	→	30	3P		NORTH EMERGENCY			
SPARE NOT USED		3P	41	→	32	3P		SPACE			
SPARE NOT USED		3P	43	→	34	3P		SPACE			
SPARE NOT USED		3P	45	→	36	3P		SPACE			
SPARE NOT USED		3P	47	→	38	3P		SPACE			
SPARE NOT USED		3P	49	→	40	3P		SPACE			
SPARE NOT USED		3P	51	→	42	3P		NORTH EXIT			

VOLTS:  208/120V, 3Ø, 4W  480/277V, 3Ø, 4W  
 AMPS:  125A  225A  400A   
 MAIN:  MLO  MCB  3Ø WBS   
 BUS:  ALUMINUM  COPPER  
 WTD:  FLUSH  SURFACE  
 DOOR:  STANDARD  DOOR IN DOOR

PHASE A LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 PHASE B LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 PHASE C LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 TOTAL CONNECTED LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 NEUTRAL BUS 50% GROUND BUS 5%  
 AIC RATING:  10K  14K  22K

LOCATION: BAR										NEMA RATING ↓	
TYPE	DIRECTORY	LOAD	BKR	CR	CR	BKR	LOAD	DIRECTORY	TYPE		
LOBBY LIGHTS		3P	11	→	2	3P					
LOBBY RECEPTS		3P	13	→	4	3P		ALARM			
LOBBY PUMP		3P	15	→	5	3P					
LOBBY EXIT SIGNS		3P	17	→	6	3P					
BOILER		3P	19	→	10	3P		WORKSHOP LIGHTS			
		3P	21	→	12	3P					
		3P	23	→	14	3P					
		3P	25	→	16	3P					
		3P	27	→	18	3P		ELEVATOR SUPP PUMP			
		3P	29	→	20	3P		ELEVATOR LIGHTS			
		3P	31	→	22	3P		ELEVATOR + WBS ROOM WALL HEATER			
ELEVATOR		3P	33	→	24	3P					
ELEVATOR CAB		3P	35	→	26	3P		TSTP BAR + BATH			
BAR INV COOLER		3P	37	→	28	3P					
BOILER PUMP NOT LOOP		3P	39	→	30	3P		RECEPT			
BAR SUPP PUMP		3P	41	→	32	3P		SPACE			
BAR BATH BOILER EXIT SIGNS		3P	43	→	34	3P		SPACE			
SPARE NOT USED		3P	45	→	36	3P		SPACE			
SPARE NOT USED		3P	47	→	38	3P		SPACE			
SPARE NOT USED		3P	49	→	40	3P		WELDER			
SPARE NOT USED		3P	51	→	42	3P					

VOLTS:  208/120V, 3Ø, 4W  480/277V, 3Ø, 4W  
 AMPS:  125A  225A  400A   
 MAIN:  MLO  MCB  3Ø WBS   
 BUS:  ALUMINUM  COPPER  
 WTD:  FLUSH  SURFACE  
 DOOR:  STANDARD  DOOR IN DOOR

PHASE A LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 PHASE B LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 PHASE C LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 TOTAL CONNECTED LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 NEUTRAL BUS 50% GROUND BUS 5%  
 AIC RATING:  10K  14K  22K

SHOP

• FUTURE BAR HALLWAY LIGHTS + RECEPTS

LOCATION: BALCONY AREA										NEMA RATING ↓	
TYPE	DIRECTORY	LOAD	BKR	CR	CR	BKR	LOAD	DIRECTORY	TYPE		
OFFICE LIGHTS		3P	11	→	2	3P		NORTH WEST RECEPTS			
SOUTH WALL RECEPTS		3P	13	→	4	3P		STAR LIGHTS			
EAST WALL RECEPTS		3P	15	→	5	3P		SPACE			
NORTH WEST RECEPTS		3P	17	→	6	3P		ATTC PELDSON LIGHT IN CONTRACTOR			
ATTIC BLOWER		3P	19	→	10	3P		STAR RECEPT BELOW THIS PANEL			
		3P	21	→	12	3P		SPACE			
		3P	23	→	14	3P					
		3P	25	→	16	3P					
		3P	27	→	18	3P					
		3P	29	→	20	3P					
		3P	31	→	22	3P					
		3P	33	→	24	3P					
		3P	35	→	26	3P					
		3P	37	→	28	3P					
		3P	39	→	30	3P					
		3P	41	→	32	3P					

VOLTS:  208/120V, 3Ø, 4W  480/277V, 3Ø, 4W  
 AMPS:  125A  225A  400A   
 MAIN:  MLO  MCB  3Ø WBS   
 BUS:  ALUMINUM  COPPER  
 WTD:  FLUSH  SURFACE  
 DOOR:  STANDARD  DOOR IN DOOR


PHASE A LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 PHASE B LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 PHASE C LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 TOTAL CONNECTED LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 NEUTRAL BUS 50% GROUND BUS 5%  
 AIC RATING:  10K  14K  22K

OFFICE HALLWAY


LOCATION: BAR										NEMA RATING ↓	
TYPE	DIRECTORY	LOAD	BKR	CR	CR	BKR	LOAD	DIRECTORY	TYPE		
INV COOLER		3P	1	→	2	3P		SPACE			
INV COOLER ICE MACHINE		3P	3	→	4	3P		RESTROOM HALL LIGHTS			
		3P	5	→	6	3P		FAN ABOVE DOOR			
		3P	7	→	8	3P		INV COOLER			
BAR STORE ROOM LIGHTS		3P	9	→	10	3P		RESTROOM LIGHTS - ALL			
SPARE		3P	11	→	12	3P		BAR RECEPTS			
		3P	13	→	14	3P		BAR RECEPTS			
SPARE		3P	15	→	16	3P		FAN HEAT FRONT BAR			

VOLTS:  208/120V, 3Ø, 4W  480/277V, 3Ø, 4W  
 AMPS:  125A  200A  400A   
 MAIN:  MLO  MCB  3Ø WBS   
 BUS:  ALUMINUM  COPPER  
 WTD:  FLUSH  SURFACE  
 DOOR:  STANDARD  DOOR IN DOOR

PHASE A LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 PHASE B LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 PHASE C LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 TOTAL CONNECTED LOAD: \_\_\_\_\_ KVA ( \_\_\_\_\_ A)  
 NEUTRAL BUS 50% GROUND BUS 5%  
 AIC RATING:  10K  14K  22K




"PANEL A" - IN KITCHEN ALTERNATE 1



"PANEL A" - IN KITCHEN ALTERNATE 2

NOTE - BOTH PANEL DIRECTORIES WERE IN PANEL DOOR



A FIRST FLOOR AS-BUILT PLAN  
 EI 1/4" = 1'-0"



Construction  
 Design  
 CIVICS, INC.  
 1515 WEST 14TH STREET, SUITE 100  
 LAS VEGAS, NEVADA 89102

PIPER'S OPERA HOUSE  
 STOREY COUNTY - NEVADA

DATE	REVISIONS

SHEET TITLE: FIRST FLOOR AS-BUILT PLAN
JOB No.: 10-143
DRAWN BY: DS
CHECKED BY: MVL/AG
DATE: 4/7/2010
SHEET No. EI







sheet notes

- ① PROVIDE EXTERIOR SNOWMELT SYSTEM (FOR NEW CONCRETE LANDING) THAT AUTOMATICALLY ACTIVATES WHEN PRECIPITATION IS DETECTED AND TEMPERATURES ARE BELOW 39 DEGREES FAHRENHEIT. SYSTEM COMPONENTS INCLUDE THERMOSTAT (MOUNTED IN APPROVED METAL BOX SUPPLIED BY MANUFACTURER) AND EMBEDDED SENSOR THAT DETECTS MOISTURE AND TEMPERATURE. ELEKTRA MODEL ET02 AS MANUFACTURED BY OJ ELECTRONICS OR APPROVED EQUIVALENT
- ② POINT OF CONNECTION FOR EXTERIOR SNOWMELT SYSTEM AT NEW CONCRETE LANDING. TIE TUBING INTO EXISTING HYDROIC HEATING SYSTEM AT EXISTING BOILER ROOM
- ③ 8 INCH THICK FIBERGLASS-REINFORCED CONCRETE SLAB (MIN. 4000 PSI @28 DAYS) OVER FOUR INCH TYPE 2 CLASS B COMPACTED AGGREGATE BASE PER STOREY COUNTY REQUIREMENTS (APPROX. 115 SF)
- ④ THREE INCH THICK AC OVER 6 INCH COMPACTED AGGREGATE BASE PER STOREY COUNTY REQUIREMENTS (APPROX. 875 SF)
- ⑤ REMOVE AND REPLACE EXISTING WATER BOX WITH NEW TRAFFIC RATED VAULT AS APPROVED BY STOREY COUNTY WATER SYSTEM (PH 775-647-0998)
- ⑥ EXISTING VAULT TO REMAIN
- ⑦ NEW CONCRETE-FILLED PIPE BOLLARD PAINTED TO MATCH EXISTING

© 2019 BY THE DUBE GROUP, INC.  
THESE PLANS ARE COPYRIGHTED AND ARE SUBJECT TO COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK" UNDER SECTION 1710 OF THE COPYRIGHT ACT (17 U.S.C. 107). ANY USE OR REPRODUCTION OF THIS DRAWING IN WHOLE OR IN PART BY ANY INDIVIDUAL OR ENTITY IS STRICTLY PROHIBITED UNLESS WITH THE EXPRESS WRITTEN CONSENT OF THE ARCHITECT.


IN ACCORDANCE WITH NEVADA ADMINISTRATIVE CODE, ALL TIES, DETAILS AND SPECIFICATIONS SHALL BE IN THE POSSESSION OF THE ARCHITECT. COPIES OF THE DRAWINGS AND SPECIFICATIONS OBTAINED BY THE CLIENT MAY BE USED ONLY FOR THE USE AND FOR OCCUPANCY OF THE PROJECT FOR WHICH THEY WERE PREPARED, AND NOT FOR CONSTRUCTION OF ANY OTHER PROJECT. POSSESSION OF THESE DRAWINGS AND SPECIFICATIONS OR COMPUTER AIDED DESIGN ELECTRONIC FILES IS STRICTLY PROHIBITED.

general notes

NEW CONCRETE LANDING SHALL FINISH FLUSH WITH GROUND FLOOR FINISH FLOOR LEVEL. SLOPE LANDING AND NEW AC DRIVEWAY AWAY FROM BUILDING AND TOWARD B STREET



SCALE: 1/8" = 1'-0"



loading dock & driveway improvements to  
**Piper's Opera House**  
12 B Street  
Virginia City, Nevada 89401

DATE:	06/20/19
BY:	ARCHITECT
CHECKED BY:	SEALED
DESIGNED BY:	SEALED
PROJECT NO.:	19-001

sheet number  
**site plan**

standard abbreviations

A.C.	Asphalt Concrete	INT	Interior
ADJUS	Adjustable	INT	Interior
ADDTN	Addition		
ADJ.	Adjustable or Adjust	JT	Joint
A.F.F.	Aggregate Finish Floor	JCM	Joint
AGGR	Aggregate	JCM	Joint
AJT	Aluminum	LAV	Lavatory
AJUM	Aluminum	LB	Label
AIB	Asbestos	LB	Label
AUTO	Automatic	LIG	Lighting
AT	At		
BD	Board	MATL	Material
BLDG	Building	VAC	Vacuum
BLKG	Blocking	MECH	Mechanical
SW	Bottom	MECH	Mechanical
BT	Brace	MANU	Manufacturing
BTM	Bottom	VIN	Vinyl
BR	Brace	VISC	Viscous
BSG	Building	V.P.H.	Voids Per Hour
BTWN	Between	WTD	Wood
CAB	Cabinet	N	North
CB	Concrete Block	NEW	New
CEM	Concrete	N/C	Not in Contract
CEP	Concrete	NUM	Number
CFM	Cubic Feet per Minute	NOM	Nominal
CF	Casting	NT	Not
CJ	Conjoint Joint	N.T.S	Not to Scale
CLD	Cladding		
CLP	Clear	OV	Over
CMU	Concrete Masonry Unit	OC	On Center
COL	Column	OD	Outside Diameter
COMP	Composite	OH	Opposite Hand
CONC	Concrete	OL	Outlet
CONN	Connection	OSB	OSB
CONSTR	Construction	OSB	OSB
COIT	Controlled	OSB	OSB
COOLING	Cooling	OSB	OSB
C.P.	Concrete Pipe	PL	Plate or Ply Line
CTN	Container	PLT	Partition or Panel
CTEX	Construction	PL	Plate
C.W.	Cold Water	PLA	Plate
C	Contactor	PLA	Plate
D	Depth	PLM	Plumbing
DBL	Double	PLM	Plumbing
DET	Detail	P.C.	Point of Connection
DESC	Description	P.F.	Per Foot
D.F.	Dressing Room	P.F.	Per Foot
DM	Diameter	P.F.	Per Foot
DIP	Dip	P.F.	Per Foot
DR	Door	P.F.	Per Foot
DRWG	Drawing	P.F.	Per Foot
D	Diameter	P.F.	Per Foot
E	East	P.F.	Per Foot
E	East	P.F.	Per Foot
EA	Each	P.F.	Per Foot
ELEC	Electrical	P.F.	Per Foot
ELEV	Elevator	P.F.	Per Foot
EQ	Equal	P.F.	Per Foot
EQPT	Equipment	P.F.	Per Foot
E.W.	Electric Water Heater	P.F.	Per Foot
E.W.	Electric Water Heater	P.F.	Per Foot
EXH	Exhaust	P.F.	Per Foot
EXT	Exterior	P.F.	Per Foot
EXT	Exterior	P.F.	Per Foot
FD	Fire Door	P.F.	Per Foot
FEC	Fire Extinguisher Cabinet	P.F.	Per Foot
F.F.	Fire Floor	P.F.	Per Foot
F.F.E	Fire Floor Elevation	P.F.	Per Foot
F.F.H	Fire Floor Hazard	P.F.	Per Foot
FG	Form	P.F.	Per Foot
FHT	Floor	P.F.	Per Foot
FLP	Floor	P.F.	Per Foot
F.O.	Floor Opening	P.F.	Per Foot
F.O.S	Face of Slab	P.F.	Per Foot
FTG	Footing	P.F.	Per Foot
GA	Gage/Gauge	P.F.	Per Foot
GAL	Gallon	P.F.	Per Foot
GA.V	Gypsum	P.F.	Per Foot
GI	Gypsum	P.F.	Per Foot
GL	Glass	P.F.	Per Foot
GLB	Glass Block	P.F.	Per Foot
GR	Gross	P.F.	Per Foot
GSP	Gross Square Foot	P.F.	Per Foot
GYP	Gypsum Board	P.F.	Per Foot
H	High	P.F.	Per Foot
HARD	Hard	P.F.	Per Foot
H.S	Hard	P.F.	Per Foot
H.C.	Hard	P.F.	Per Foot
H.D.W.	Hard	P.F.	Per Foot
H.L.T.	Hard	P.F.	Per Foot
H.C.N.Z	Hard	P.F.	Per Foot
H.R.	Hard	P.F.	Per Foot
H.T.	Hard	P.F.	Per Foot
H.T.P.	Hard	P.F.	Per Foot
H.V.A.C.	Hard	P.F.	Per Foot
I.B.C.	International	P.F.	Per Foot
I.D.	Inside	P.F.	Per Foot
I.E.	Inside	P.F.	Per Foot
INSUL.	Insulation	P.F.	Per Foot

project notes

The Scope of Work is to complete the restroom improvements at Piper's Opera House, 12 B Street, Virginia City, Nevada 89440. Currently, the men's restroom is accessed through the leased tenant space (a tavern) and does not meet federal accessibility requirements. The women's restroom is a shell space with some perimeter framing (walls only) and rough-in electrical and plumbing. As a result, the single operable men's restroom functions as a unisex facility for patrons of the tavern and visitors to Piper's Opera House.

Construction will occur in two phases. During the first phase, the men's restroom will remain fully operational and continue to function as the unisex facility for guests during build-out of the women's restroom shell. Once the women's restroom and adjacent corridor areas are complete, the second phase of construction will consist of improvements to the men's restroom.

Both the tavern and Piper's Opera House will be occupied and open for business during construction. Construction activities shall not interfere nor impede business, traffic or general operations of the facility. Piper's Opera House is listed on the National Register of Historic Places and the Contractor(s) shall endeavor to conduct all Work with the greatest care possible to preserve and protect this national treasure.

Piper's Opera House maintains a list of materials supplied by the Owner that are to be used in the project. Wherever possible, existing elements, fixtures, or features are to remain or be re-used in the remodel. All work shall be in conformance with applicable federal, state and local codes and ordinances.

project directory

owner: piper's opera house  
12 b street | virginia city, nevada 89440  
p | 775.847.0433

architect: dubé group architecture  
458 court street | reno, nevada 89501  
p | 775.323.1001 f | 775.323.2220

contractor:

index to drawings

general

t1.0 title sheet

architectural

- a1.0 restroom floor plan
- a2.0 partial reflected ceiling plan / schematic power & lighting plan
- a3.0 interior elevations / accessible mounting heights

PLUMBING FIXTURE SCHEDULE

SYMBOL	MANUFACTURER & MFR NUMBER	TRIM	REMARKS
WC1	WATER CLOSET, FLOOR MOUNTED, TANK TYPE "KOHLER"	SEAT: "STRONGHOLD" ELONGATED OPEN FRONT LESS COVER w/ SUPPLY FITTINGS	ADA COMPLIANT WITH LEVER HANDLE ON APPROACH SIDE
WC2	WATER CLOSET, EXISTING, TO BE RELOCATED		
WC3	WATER CLOSET, EXISTING, TO REMAIN		
LV1	LAVATORY, COUNTER MOUNTED SELF RIMMING, VITREOUS CHINA, "TOTO" L7909.4	FAUCET: "KOHLER" K-15182-P, POP UP DRAIN, P-TRAP AND SUPPLIES	ADA-COMPLIANT WITH PIPE WRAPS
SK1	SINK, UTILITY, EXISTING TO BE RELOCATED		

project title

# restroom improvements to the Piper's Opera House

12 B Street, Virginia City, Nevada 89440



458 COURT STREET  
RENO, NEVADA 89501  
PH: 775.323.1001 FAX: 775.323.2220

WWW.DUBEGROUP.COM

© 2016 BY THE DUBÉ GROUP, INC.  
"THESE PLANS AND SPECIFICATIONS ARE SUBJECT TO CORRECTION PROVIDED AS AN 'ARCHITECTURAL AGREEMENT' UNDER SECTION 12.02 OF THE CONTRACT SET BY U.S.C. AS AMENDED (OCTOBER 1988) AND KNOWN AS THE 'CONSULTING ARCHITECTURAL RECORDS PROFESSIONAL ACT OF 1992'. ANY USE OR MODIFICATION OF THIS DRAWING IN FULL OR IN PART WITHOUT WRITTEN PERMISSION OF DUBÉ GROUP IS PROHIBITED. ANY SUCH VIOLATION SHALL BE CONSIDERED A BREACH OF THE AGREEMENT."

IN ACCORDANCE WITH NEVADA ADMINISTRATIVE CODE 630.020, DRAWINGS AND SPECIFICATIONS SHALL REMAIN THE PROPERTY OF THE ARCHITECT. NO PART OF THESE DRAWINGS AND SPECIFICATIONS MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

PROJECT:

restroom improvements to

Piper's Opera House  
12 B Street  
Virginia City, Nevada 89440

DATE:	01/23/16
SCALE:	AS SHOWN
PROJECT:	AS SHOWN
DATE:	01/23/16
SCALE:	AS SHOWN
PROJECT:	AS SHOWN

DATE: 01/23/16


title sheet

PROJECT:

t1.0

sheet notes

- 1) RE-WOOD RAMP (SEE FROM SHEET 101) TO EXISTING FLOOR
- 2) AREA OF NEW WOOD FLOORING TO MATCH EXISTING
- 3) LINE OF EXISTING STRUCTURAL SUPPORT BEAM (ABOVE)
- 4) EXISTING EDGE OF EXCAVATION
- 5) PROVIDE 1/2" CLASSIC LAMINATE TO LET PARTITION DOORS - REMOVE EXISTING DOOR AND FRAME WHERE OCCURS
- 6) REMOVE EXISTING WALL-CLOSET AND SALVAGE FOR RE-USE (SEE SHEET NOTE 2-3, ALSO). SAWCUT FLOOR TO EXTEND AND RELOCATE CLOSET FLANGE AS INDICATED. PATCH CONCRETE 5'x8' AND SET 1" TO MATCH EXISTING WOOD-FLOOR SURFACES
- 7) REMOVE EXISTING DOOR AND BUILD DOORWAY IN NEW STUDS AND SET THE 1" x 2" PROFILE BOTH SIDES AND WOOD WANSLOTS ON BOTH SIDES TO MATCH FINISH
- 8) SAWCUT WALL AT NEW OPENING FOR NEW 3'-0" WIDE BY 6'-8" HIGH FOUR PANEL WOOD DOOR w/ GLASS. FINISH THREE-SIDED TO MATCH EXISTING WALL-WAY FLOORING
- 9) REMOVE EXISTING DOOR AND FRAME, INCLUDING NON-FUNCTIONAL HILL
- 10) REMOVE EXISTING WALL
- 11) CONNECT QUANTER SUPPLIED 3/4" x 3/4" SINK IN NEW CLOSET. PROVIDE PER PANELS 1/2" GUT TO CEILING (ON THREE SIDES) OVER 5/8" SOUNDBOARD OVER 2x4 WOOD STUDS
- 12) NEW 2'-8" WIDE BY 6'-8" HIGH FOUR PANEL WOOD DOOR w/ MORTISED BRACKET. UNDERCUT 7/8" TO ALLOW WATER RUNOFF FROM VOP HOLDUP TO EXISTING FLOOR DRAIN
- 13) VOP HOLES
- 14) CUSTOM WROUGHT IRON SECURITY GRATE, PAINTED TYPICAL OF 2)
- 15) REMOVE EXISTING SIGN CABINET
- 16) ADA-COMPLIANT SELF-RAMPING SANITARY SET IN NEW 24" DEEP 17" WIDE SANITARY CABINET w/ 34" WIDE BY 46" DEEP CLEAR FLOOR SPACE CENTERED ON FIXTURE. PROVIDE 4" BATH AND SILE SPLASHES AND UNDERCUPPER FRONT PROTECTIVE WALL. MOUNT ACCESSIBLE LAVATORY AT 34" TO TOP OF R.O. WALKWAY
- 17) PROVIDE 3'-0" WIDE BY 6'-8" HIGH FOUR PANEL WOOD DOOR w/ GLASS IN EXISTING DRAWING
- 18) FINISH EXISTING WOOD FRAME WALLS TO ENCLOSE NEW RESTROOM AND CORNER WITH NEW STUDS AND SUPPORT 1" OVERBOARD BOTH SIDES AND WOOD WANSLOT ON CORNER SIDE TO MATCH EXISTING
- 19) 3'-0" WIDE BY 6'-8" HIGH FOUR PANEL WOOD DOOR
- 20) INSTALL OWNER-SUPPLIED CERAMIC TILE FLOORING, 18" x 18" TILE, TO MATCH ADJACENT RESTROOM
- 21) FULL HEIGHT WALL PARTITIONS - 5/8" TYPE 1" x 2" W/ 1/2" HOLLOW GUT-DOES OVER 2x WOOD STUDS - FINISH TO MATCH ADJACENT RESTROOM WALLS
- 22) NEW PARTITION WALL - 5/8" TYPE 1" x 2" PROFILE BOTH SIDES OF 2x WOOD STUDS. PROVIDE WOOD WANSLOT OVERCUT JOG TO MATCH EXISTING - TERMINATE AT INTERSECTION WITH BOILER ROOM WALL
- 23) 6-1/2" REGISTER - CONNECT TO EXISTING FLEXIBLE HVAC DUCTING TO MATCH EXISTING ADJACENT RESTROOM
- 24) RELOCATED WATER CLOSET (SEE SHEET NOTE 8/4/1)



a restroom floor plan  
SCALE: 1/4" = 1'-0"



© 2010 BY THE DUBE GROUP, INC.

THESE PLANS ARE COPYRIGHTED AND ARE SUBJECT TO COPYRIGHT PROTECTION AS AN ARCHITECTURAL WORK UNDER SECTION 102 OF THE COPYRIGHT ACT OF 1976. NO UNAUTHORIZED REPRODUCTION OR TRANSMISSION IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, IS PERMITTED WITHOUT THE WRITTEN PERMISSION OF THE DUBE GROUP, INC. ANY USE OR REPRODUCTION OF THIS DRAWING OR PORTION OF IT IN ANY FORM OR BY ANY MEANS WITHOUT THE WRITTEN PERMISSION OF THE DUBE GROUP, INC. IS STRICTLY PROHIBITED.

RESTROOM IMPROVEMENTS TO:  
Piper's Opera House  
12 B Street  
Virginia City, Nevada 89740

DATE	DESCRIPTION

PROJECT TITLE  
**restroom floor plan**

PROJECT NO.  
**a1.0**

sheet notes

- ① EXISTING 1/2" SPRINKLER HEAD
- ② EXISTING EXHAUST FAN (TYP. OF 2)
- ③ EXISTING EXHAUST FAN (WALL VENT)
- ④ USE OF EXISTING STRUCTURAL STEEL SUPPORT BEAM
- ⑤ EXISTING EDGE OF EXCAVATION (ELEV. 7500)
- ⑥ EXISTING EDGE OF CEILING
- ⑦ 5/8" TYPE "Y" CEILING BOARD OVER 2x WOOD FRAMING BRACED TO MATCH EXISTING RESTROOM CEILING
- ⑧ NEW RESTROOM EXHAUST FAN (TYP. OF 2) 1/2" W/ 1/2" FLEXIBLE DUCTING TO MATCH EXISTING
- ⑨ NEW FIRE SPRINKLER DROP (TYP. OF 2)
- ⑩ NEW EXHAUST FAN SIGNAL LENT TO MATCH EXISTING
- ⑪ PATCH EXISTING CEILING AS REQUIRED. FINISH TO MATCH ADJACENT SURFACES
- ⑫ LIGHT SWITCH - MOUNT @ 48" MAXIMUM A.F.F.
- ⑬ 1/2"X2" DUPLEX RECEPTACLE - MOUNT ABOVE COUNTER @ 48" MAXIMUM A.F.F.
- ⑭ EXISTING EMERGENCY LIGHT FEATURE TO REMAIN
- ⑮ EXISTING SURFACE MOUNTED LIGHT SOURCE (TYPICAL OF 3) - ADJUST LOCATION AS REQUIRED
- ⑯ INSTALL 2000H-SUPPLY 1" SURFACE MOUNTED LIGHT SOURCE (TYPICAL OF 2)
- ⑰ EMERGENCY LIGHT FEATURE (TYPICAL OF 2) - VERIFY LOCATION AND QUANTITIES WITH STORE COUNTY BUILDING INSPECTOR
- ⑱ DUPLEX RECEPTACLE MOUNT @ 12" A.F.F.

© 2019 BY THE DUBÉ GROUP, INC.  
THESE PLANS ARE COPYRIGHTED AND ARE SUBJECT TO COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK" UNDER SECTION 107 OF THE COPYRIGHT ACT OF 1976, AS AMENDED (DECEMBER 1990) AND KNOWINGLY REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

IN ACCORDANCE WITH NEVADA ADMINISTRATIVE CODE 833.030, DRAWINGS AND SPECIFICATIONS SHALL REMAIN THE PROPERTY OF THE ARCHITECT. COPIES OF THE DRAWINGS AND SPECIFICATIONS RETAINED BY THE CLIENT MAY BE USED ONLY FOR THE USE AND FOR OCCUPANCY OF THE PROJECT FOR WHICH THEY WERE PREPARED, AND NOT FOR CONSTRUCTION OF ANY OTHER PROJECT. PERMISSION OF THESE DRAWINGS AND SPECIFICATIONS ON COMPUTER DISK OR OTHER ELECTRONIC MEDIA IS STRICTLY PROHIBITED.

11/15/2019

restroom  
improvements to

Piper's Opera House  
128 B Street  
Virginia City, Nevada 89401


DATE	DESCRIPTION
11/15/19	ISSUE
11/15/19	ISSUE
11/15/19	ISSUE
11/15/19	ISSUE
11/15/19	ISSUE
11/15/19	ISSUE

Revision 1/19

partial reflected  
ceiling plan /  
schematic power  
& lighting plan


Sheet 1 of 04

a2.0



**b** schematic power & lighting plan


SCALE: 1/4" = 1'-0"



**a** partial reflected ceiling plan


SCALE: 1/4" = 1'-0"






**4** accessible mounting heights  
a3.0

SCALE: N.T.S.




**3** corridor interior elevations  
a3.0

SCALE: 1/4" = 1'-0"



**2** men's restroom interior elevations  
a3.0

SCALE: 1/4" = 1'-0"



**1** women's restroom interior elevations  
a3.0

SCALE: 1/4" = 1'-0"

sheet notes

- ① 5/8" TYPE "C" ZIPBOARD OVER NEW OR EXISTING 2x4 WOOD STUDS. PROVIDE MOISTURE RESISTANT BOARD IN LOCATIONS WHERE REDDARD BY CODE
- ② 4 PANEL WOOD DOOR AND CASING FINISHED TO MATCH EXISTING
- ③ EXTEND WOOD BASE, HANDSCOT, AND CHAIR RAIL HOLDING IN LOCATIONS INDICATED - FINISH TO MATCH EXISTING
- ④ REMOVE EXISTING DOOR AND IMPUL DOORWAY WITH NEW STUDS AND 5/8" TYPE "C" ZIPBOARD BOTH SIDES AND WOOD HANDSCOT BOTH SIDES TO MATCH EXISTING
- ⑤ CUSTOM WROUGHT IRON SECURITY GATE, PAINTED (TYPICAL OF 2)
- ⑥ ADA-COMPLIANT SELF FINISHING LAVATORY SET IN NEW 24" DEEP PLASTIC LAMINATE COUNTERTOP 4" 3/8" WIDE BY 45" DEEP CLEAR FLOOR SPACE CONTROLLED ON FIXTURE. PROVIDE 4" BACK AND SIDE SPLASHES AND UNDERCOUNTER FIXTURE PROTECTIVE WRAP. MOUNT ACCESSIBLE LAVATORY AT 3'-4" TO TOP OF RAIL, MAXIMUM
- ⑦ LINE OF CEILING IN RESTROOM
- ⑧ CONNECT EXISTING FLEXIBLE HVAC DUCTING TO NEW 6x12 REGISTER TO MATCH EXISTING ADJACENT RESTROOM
- ⑨ SURFACE MOUNTED LIGHT SCENIC
- ⑩ SEE FLOOR PLAN AND FILING FIXTURE SCHEDULE FOR NEW, EXISTING, AND RELOCATED FIXTURES
- ⑪ 6x12 REGISTER
- ⑫ SOAP DISPENSER - MOUNT @ 44" A.F.F.
- ⑬ OVAL MIRROR (TYP. OF 3)
- ⑭ PLASTIC LAMINATE TOILET PARTITION DOOR
- ⑮ SANITARY WIPER DISPOSAL
- ⑯ STAINLESS STEEL GRAB BARS - SEE DETAIL 4/A3.0
- ⑰ SEAT COVER DISPENSER
- ⑱ TOILET PAPER DISPENSER
- ⑲ PATCH AND OR REPAIR EXISTING WALLS AS REQUIRED - RE-PAINT TO MATCH EXISTING AND BLEND WITH NEW CONSTRUCTION
- ⑳ ACCESSIBLE RESTROOM SIGN - SEE DETAIL 4/A3.0

© 2016 BY THE DUBE GROUP, INC.  
THESE PLANS ARE COPYRIGHTED AND ARE SUBJECT TO THE PROVISIONS OF THE ARCHITECTURE CONTRACT. NO PART OF THESE PLANS MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT. IN ACCORDANCE WITH FEDERAL ADMINISTRATIVE CODE 28 CFR 119.101, THE ARCHITECT'S OFFICE SHALL MAKE THE RECORDS OF THE ARCHITECTURAL WORK OF THE ARCHITECT AND THE RECORDS OF THE ARCHITECTURAL WORK OF THE ARCHITECT AVAILABLE TO THE PUBLIC FOR REVIEW AND FOR REPRODUCTION FOR RESEARCH AND EDUCATIONAL PURPOSES. FOR MORE INFORMATION, CONTACT THE ARCHITECT AT THE ADDRESS LISTED ON THESE PLANS. ALL INFORMATION ON COPYRIGHTS AND ON OTHER ELECTRONIC SIGNATURE INFORMATION IS SUBJECT TO CHANGE.

restroom  
improvements to  
Piper's Opera House  
12 B Street  
Virginia City, Nevada 89410

DATE:	10/10/2016
BY:	AD
CHECKED BY:	AD
SCALE:	AS SHOWN
PROJECT NO.:	16-001

interior  
elevations /  
accessible  
mounting heights

a3.0



dubé group  
ARCHITECTURE

415 South Third Street, Reno, Nevada 89501  
775.783.8000  
http://www.dubegroup.com  
http://www.dubegroup.com

P: 775.783.8000  
F: 775.333.2222

© 2009 by the DUBÉ GROUP, INC.  
THESE PLANS ARE COPYRIGHTED AND ARE SUBJECT TO  
COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK"  
UNDER SECTION 102 OF THE COPYRIGHT ACT OF U.S.C. AS  
AMENDED December 1990 AND SIMILAR AS THE  
ARCHITECTURAL WORKS COPYRIGHT PROTECTION ACT OF  
1990. ANY USE OR REPRODUCTION OF THIS DRAWING IN  
WHOLE OR IN PART BY ANY MEANS WHATSOEVER IS  
STRICTLY PROHIBITED EXCEPT WITH THE EXPRESS WRITTEN  
CONSENT OF THE ARCHITECT.

IN ACCORDANCE WITH NEVADA ADMINISTRATIVE CODE  
REGULATIONS, DRAWINGS AND SPECIFICATIONS SHALL REMAIN THE  
PROPERTY OF THE ARCHITECT. COPIES OF THE DRAWINGS  
AND SPECIFICATIONS RETAINED BY THE CLIENT MAY BE  
USED ONLY FOR THE USE AND FOR OCCUPANCY OF THE  
PROJECT FOR WHICH THEY WERE PREPARED, AND NOT FOR  
CONSTRUCTION OF ANY OTHER PROJECT. POSSESSION OF  
THESE DRAWINGS AND SPECIFICATIONS ON COMPUTER DISK  
OR OTHER ELECTRONIC MEDIUM IS STRICTLY PROHIBITED.

project code

Piper's Opera House  
12 B Street  
Virginia City, Nevada 89440


Job Number: 09-001  
Date: 10/20/09  
Drawn By: [blank]  
Checked By: [blank]  
Title: [blank]

Sheet Description

site plan

Sheet Number

AS1.0





4250 West Sahara | Las Vegas, Nevada 89102  
www.dubegroup.com  
info@dubegroup.com

31 11/23/2010  
1 11/23/2010



© 2010 BY THE DUBÉ GROUP, INC.  
THESE PLANS ARE CONSIDERED AND ARE SUBJECT TO COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK" UNDER SECTION 102 OF THE COPYRIGHT ACT OF 1976, U.S.C. AS AMENDED. REPRODUCED THIS AND OTHER AS THE ARCHITECTURAL WORKS COPYRIGHT PROTECTION ACT OF 1976, MAY BE THE SUBJECT OF THIS DRAWING IN WHOLE OR PART IN ANY MANNER UNLESS THE DUBÉ GROUP HAS BEEN ADVISED WITH THE EXPRESS WRITTEN CONSENT OF THE ARCHITECT.

IN ACCORDANCE WITH NEVADA ADMINISTRATIVE CODE, ALL CHANGES AND SPECIFICATIONS SHALL REMAIN THE PROPERTY OF THE ARCHITECT. COPIES OF THE DRAWINGS AND SPECIFICATIONS ISSUED BY THE CLIENT MAY BE UTILIZED ONLY FOR THE USE AND FOR OBTAINING THE PROJECT FOR WHICH THEY WERE PREPARED, AND NOT FOR CONSTRUCTION OF ANY OTHER PROJECT. POSSESSION OF THESE DRAWINGS AND SPECIFICATIONS OR COPIES THEREOF OR OTHER ELECTRONIC MEDIA IS STRICTLY PROHIBITED.

PROJECT NO.

Piper's Opera House  
12 B Street  
Virginia City, Nevada 89440

Job Number: 10000  
Date: 11/23/2010  
Drawing No: 10000  
Title: 10000  
Author: 10000  
Reviewer: 10000

FILE DESCRIPTION

B Street level  
floor plan

FILE NUMBER

a1.0






dubé group  
ARCHITECTURE

450 S. 1st Street | Reno, Nevada 89501  
775.784.2222  
www.dubegroup.com

1115 32nd Street  
Reno, NV 89502



© 2009 BY THE DUBÉ GROUP, INC.  
THESE PLANS ARE COPYRIGHTED AND ARE SUBJECT TO  
COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK"  
UNDER SECTION 102 OF THE COPYRIGHT ACT OF 1976, AS  
AMENDED DECEMBER 1990 AND KNOWN AS THE  
ARCHITECTURAL WORKS COPYRIGHT PROTECTION ACT OF  
1990, AND THE ARCHITECTURE ACT OF 1968, AND THE  
BRIEF OF A CONTRACTOR OF THIS DRAWING OR  
WHOLE OR IN PART BY ANY MEANS WHATSOEVER IS  
STRICTLY PROHIBITED EXCEPT WITH THE EXPRESS WRITTEN  
CONSENT OF THE ARCHITECT.

IN ACCORDANCE WITH NEVADA ADMINISTRATIVE CODE  
REGULATING DRAWING AND SPECIFICATION WORK, THESE  
PLANS AND SPECIFICATIONS HEREBY BECOME THE  
PROPERTY OF THE ARCHITECT. COPIES OF THE DRAWINGS  
AND SPECIFICATIONS HEREBY BY THE CLIENT MAY BE  
MADE ONLY FOR HIS USE AND FOR RECEIVING THE  
PROJECT FOR WHICH THEY WERE PREPARED, AND NOT FOR  
CONSTRUCTION OF ANY OTHER PROJECT. PERMISSION OF  
THESE DRAWINGS AND SPECIFICATIONS ON COMPUTER AID  
OR OTHER ELECTRONIC MEDIA IS STRICTLY PROHIBITED.

PROJECT 088

Piper's Opera House  
12 B Street  
Virginia City, Nevada 89440

JOB NUMBER: 088-001  
DATE: September 28, 2009  
DRAWN BY: JLD  
CHECKED BY: JLD  
ISSUERS: JLD

THIS DESCRIPTION:  
auditorium level  
floor plan


sheet number:  
a2.0



dubé group  
ARCHITECTURE

450 South Street | Reno, Nevada 89501  
tel: (775) 784-0000  
http://www.dubegroup.com

01 10/15/2011  
11 10/15/2011



© 2011 BY THE DUBE GROUP, INC.

THESE PLANS ARE COPYRIGHTED AND ARE SUBJECT TO COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK" UNDER FEDERAL LAW OF THE COPYRIGHT ACT OF 1976, AS AMENDED DECEMBER 1990 AND KNOWN AS THE ARCHITECTURAL WORKS COPYRIGHT PROTECTION ACT OF 1990. ANY USE OR REPRODUCTION OF THE DRAWING IN WHOLE OR IN PART BY ANY MEANS OR THROUGH ANY DIRECTLY INDIRECT MEANS, WITH THE SPECIFIC WRITTEN CONSENT OF THE ARCHITECT.

IN ACCORDANCE WITH NEVADA ADMINISTRATIVE CODE REGULATIONS AND SPECIFICATIONS THAT REGARD THE PROPERTY OF THE ARCHITECT, PORTION OF THE DRAWINGS AND SPECIFICATIONS DELIVERED BY THE CLIENT MAY BE UTILIZED ONLY FOR THE USE AND FOR OCCUPANCY OF THE PROJECT FOR WHICH THEY WERE PREPARED, AND NOT FOR CONSTRUCTION OF ANY OTHER PROJECT. PORTIONS OF THESE DRAWINGS AND SPECIFICATIONS ON COMPACT DISK OR OTHER ELECTRONIC MEDIA IS STRICTLY PROHIBITED.

project name

Piper's Opera House  
12 B Street  
Virginia City, Nevada 89440

user	gms
date	10/15/2011
drawn by	gms
checked by	gms
revision	

sheet description

balcony level  
floor plan

sheet number

a3.0

Attachment C

Storey County Capital Improvement Plan DRAFT

02/07/23 BOCC APPROVED

NOTES:

Items shown for 2025-2028 are subject to anticipated revenues from commerce and economic development activity at TRI-Center. The following is a plan for anticipated future capital improvements. This is not a budget, and the items listed have not necessarily been obligated. This CIP may be adjusted each year to align with actual revenues, obligations, community needs, available grants, and other conditions.

DRAFT TALKING PAPER SUBJECT TO CHANGE AND PUBLIC DISCUSSION.

CAPITAL IMPROVEMENT PROJECTS										
2023 Projects										
	Dept. Managing Project	Fund	Fiscal Year Target	Fiscal Year Target if Grants Secured	Total Estimate County Expense	Estimated Grant Funding	Project Location	Short Name	Description	Notes
	CR	Grant	23	Grant 23	\$ 2,500,000	\$ 2,500,000	LW	LW Sr and Comm. Center	Lockwood senior and community center with new - PROJECT WILL SPAN INTO FY 24/25	Designing now. 2023 Appropriations
	JC	Capital	23		\$ 225,000		VC	Justice Ct Parking Phase I	Improve parking (gravel), bollards, and lighting at Justice Court, add driveway to West South Street	
	Planning	Planning	23		\$ 5,000		County	PC with GIS Capability	Add PC with Geographic Information Systems (Esri GIS Arc-Info) capability to move some GIS in-house	
	PW	Capital	23		\$ 120,000		TRI	Com. Dev. Office	Convert Switch Conference Room to Community Development office; including HVAC, lighting, and ceiling	
	PW	Capital	23		\$ 1,000		TRI	Door Lettering	Community Development and Business Development office door lettering	
	PW	Capital	23		\$ 30,000		VC	CH Window Safety Film	Film on Courthouse glass for safety and seismic	
	PW	Capital	23		\$ 20,000		TRI	TRI Monument Signs	"Storey County" monument signs at entrances to TRI-Center	
	PW	Capital	23		\$ 5,000		TRI	McCarran Complex Letters	Change lettering on McCarran Complex to be more visible and appropriate	
	PW	Capital	23		\$ 3,000		TRI	McCarran Complex Sign	Add free-standing sign at McCarran Complex	
	PW	Capital	23	Grant 23	\$ -	\$ 100,000	VC	Courthouse Electrical	Replace Courthouse electrical	SHPO Grant - no match
	PW	Capital	23		\$ 30,000		VC	Courthouse Fence Repair	Repair and replace portions of Courthouse wrought iron fence. Mold then foundry. Most cost is mold.	Mold can be reused in future
	PW	Facilities	23		\$ 500,000		VC	NSP Park Conversion CCI	Park Services requires park to replace park taken by Community Chest building in VC	
	PW	Infrastructure	23	ARPA 23	\$ 600,000	\$ 800,900	VC	Water B Str Project w ARPA	B Street water line project with ARPA funds	ARPA Funds
	PW	Infrastructure	23		\$ 82,213		VC	Water Tank Upgrades	Repair and seal water tanks See 2022/23 infrastructure Ordinance	
	PW	Capital	23		\$ 600,000		VCH	VCH Fire Bays	VCH fire bays allow existing building to be converted to community center Re-bid from FY2022	Will span over multiple FYs
	PW	Maintenance	23		\$ 400,000		TRI	Re-Roof TRI 75	Reroof and roof improvements on Fire Station 75 McCarran complex	Maintenance or infrastructure?
					<b>\$ 5,961,213</b>	<b>\$ 3,400,900</b>				
2023 Equipment & Vehicles										
	Building	Equip. Acq.	23		\$ 50,000	\$ -	Building	GMC Inspector Pickup	Per draft GSA with Redwood Materials	Pending
	Building	Equip. Acq.	23		\$ 50,000	\$ -	Building	GMC Inspector Pickup	Per draft GSA with Redwood Materials	Pending
	SCSC	Equip. Acq.	23		\$ 35,000	\$ -	LW	SUV / Minivan	Passenger vehicle to transport DV Advocates, Counselors, and Staff for Senior Services	SCSC restructure
	PW	Equip. Acq.	23		\$ 50,000	\$ -	PW	Sander	Sander gantry granes for summer sander hanging and storage	
	PW	Equip. Acq.	23		\$ 120,000	\$ -	PW	Small Town Plow	Small Town Plow for steep and narrow streets of Virginia City	Not purchased in '22 per budget.
	PW	Equip. Acq.	23		\$ 70,000	\$ -	PW	GMC Buildings/Gnds.	GMC 4-door diesel w. utility bed for buildings/grounds. Needs to pull weight	
	PW	Equip. Acq.	23		\$ 60,000	\$ -	PW	GMC Buildings/Gnds.	GMC 3/4 ton long-bed gas pickup with shell for water and sewer	
	PW	Equip. Acq.	23		\$ 650,000	\$ -	PW	Vactor Truck (south)	Replace worn Vactor Truck to serve south end of Storey County (VC, GH, VCH, MT)	
	SO	Equip. Acq.	23		\$ 50,000	\$ -	SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle	
	SO	Equip. Acq.	23		\$ 50,000	\$ -	SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle	
	SO	Equip. Acq.	23		\$ 50,000	\$ -	SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle	
	VCTC	Equip. Acq.	23		\$ 20,000	\$ -	VCTC	UTV VCTC	UTV with pickup bed for Fairgrounds and event work for tourism	
	VCTC	Equip. Acq.	23		\$ 50,000	\$ -	VCTC	GMC SUV or PU	7-passenger SUV (GMC Yukon) or crew-cab half-ton pickup for staff trips and field work and towing	
	VCTC	Equip. Acq.	23		\$ 200,000	\$ -	VCTC	Shuttle w. ADA Expansion	Shuttle for VC and TRI-Center uses	

## Storey County Capital Improvement Plan *DRAFT*

Dept. Managing Project	Fund	Fiscal Year Target	Fiscal Year Target if Grants Secured	Total Estimate County Expense	Estimated Grant Funding	Project Location	Short Name	Description	Notes
<b>2023 Equipment &amp; Vehicles TOTALS:</b>				\$ 1,505,000	\$ -				
<b>2023 Plans &amp; Studies</b>									
<b>2023 Plans &amp; Studies TOTALS:</b>				\$ -	\$ -				
<b>2024 Projects</b>									
PW	Capital	24		\$ 75,000	\$ -	County	Courthouse Security	Add security elements to county courthouse	
FD	Capital	24	Grant 24	\$ -	\$ 650,000	VCH	VCH Dorms for Fuels Crew	Add dorm rooms for Fire fuels reduction and other fire crews at VC Highlands	Paid for by NV Energy grant possible
FD	Capital	24	Grant 24	\$ 3,750,000	\$ 3,750,000	VC	Fire Station 71 Rebuild	Replace Fire Station 71 with new bays, offices, dorms, and training facilities	2023 Appropriations CDS Grant
FD	Capital	24		\$ 78,000	\$ -	VCH	Connect Fire Station 72 Bay	Connection between Fire Station 72 VCH and new fire apparatus bays built on or about FY2023	
CR	Grant	24	Grant 24	\$ 747,000	\$ 615,000	VC	Fairgrounds Upgrade	Add ADA restrooms, Water hookups, electrical hookups, remodel existing ticket booth, grade/pave Fairgrounds	2023 Appropriations CDS Grant
FD	Capital	24		\$ 50,000	\$ -	VCH	Fire Station 72 Siding	Replace bad exterior siding on Fire Station 72 VCH	
FD	Capital	24		\$ 5,000	\$ -	TRI	Fire Station 75 Bedrooms	Finish bedrooms/dorms buildout inside Fire Station 75	
FD	Capital	24		\$ 32,000	\$ -	VC	Fire Station 71 Exhaust	Exhaust system Fire Station 71 VC	
IT	IT	24		\$ 1,000	\$ -	LW	LW Fiber to Rainbow B	Microwave connection from county tower to Rainbow Bend HOA Clubhouse	Pending eligibility and desire
IT	IT	24		\$ 1,000	\$ -	LW	LW Fiber to LCC	Microwave connection from county tower to Lockwood Community Corporation Office	Pending eligibility and desire
IT	IT	24		\$ 1,000	\$ -	LW	LW Fiber to CGID	Microwave connection from county tower to Canyon General Improvement District	Pending eligibility and desire
IT	IT	24		\$ 500,000	\$ -	County	Region Fiber Link IT	10-year revamp of the Quad-County, Dispatch, Radio network system.	
IT	IT	24		\$ 10,000	\$ -	LW	LW Microwave Tower	Tower behind SO substation to facilitate microwave internet connections throughout Lockwood	Easement w. LCC near done
IT	IT/Capital	24		\$ 65,000	\$ -	LW	LW Fiber/Wireless Link	Tower and microwave link between SO Substation, Station 74, LWSC, and to Rainbow and LCC Buildings	
PW	Capital	24		\$ 50,000	\$ -	MT	MTCC Outdoor Reader Board	Replace Mark Twain Comm Center message board with size needed to display events at Mark Twain Center.	
PW	Capital	24		\$ 25,000	\$ -	MT	MTCC Outdoor Lighting	Install commercial exterior light fixtures around all 4 sides of Mark Twain Community Center	
PW	Facilities	24		\$ 100,000	\$ -	County	NPS Park Conversion	NPS park conversion from Community Chest land improvements. Park location currently undetermined.	
PW	Rail	24		\$ 50,000	\$ -	GH	GH Depot ADA Ramp	GH add ramp to GH Freight Depot to connect to train for passengers	.25 cent sales V&T Rail Fund used
PW/VCTC	Rail	24		\$ 150,000	\$ -	VC	VC Depot ADA	ADA improvements to VC Freight Depot (ADA lift, rails, restrooms, etc.)	.25 cent sales V&T Rail Fund used
PW	Roads	24		\$ 50,000	\$ -	LW	Lockwood Tower Rd Pt 2	LW LLC Tower Road Upper Part - Tar seal upper pavement, grade and base turnaround, stabilize slope at top	
PW	Water	24		\$ 90,000	\$ -	VC	Five Mile Res. Security	Add cameras to Five Mile Reservoir	No available funding in Water
SO	Infra/Capital	24		\$ 500,000	\$ -	LW	LW SO Substation Phase 1	Replace SO Lockwood substation with new modular building. Add county staff office for community access	Preparing now
PW	Roads	24		\$ 100,000	\$ -	VC	Cemetery east access	Culvert and dirt road over drainage at southeast corner of cemetery for access per MOU with CCF	
PW	Build/Grounds	24		\$ 100,000	\$ -	VC	Comm. Dev. Generator	Connect Community Development to Public Works facility generator system	
PW	Infrastructure	24		\$ 210,000	\$ -	VC	Sewer Payments	See 2023/24 Infrastructure Ordinance	
PW	Infrastructure	24		\$ 100,000	\$ -	VC	Hillside Tank Piping	Main line piping to go directly into 2 Hillside Tanks eliminating possibility of bypassing	NDEP/Farr West recommended
PW	Infrastructure	24		\$ 200,000	\$ -	VC	Water SCADA 2 Pumps	2 VFD drives and controls into the SCADA for the 2 finished water pumps	
PW	Infrastructure	24		\$ 75,000	\$ -	VC	Influent Effluent Valves	Replace DeZurik effluent and influent valves. Multiple sizes.	
PW	Infrastructure	24		\$ 85,000	\$ -	VC	Water Tank Upgrades	Repair and seal VC water tanks. See 2023/24 Infrastructure Ordinance	
PW	Infra/Roads	24		\$ 350,000	\$ -	County	Road Projects Countywide	Countywide road rehabilitation projects per Farr West CIP report. See 2023/24 Infrastructure Ordinance	
PW	Infrastructure	24		\$ 150,000	\$ -	LW	LW SO Substation Phase 2	Sheriff's substation at Lockwood, phase 2. See 2023/24 Infrastructure Ordinance	Project to cross years 23/24
PW	Capital	24		\$ 75,000	\$ -	MT	MT Mailbox Plaza	Consolidated mailbox plaza on Mark Twain Community Center grounds	
PW	Infrastructure	24		\$ 200,000	\$ -	VC	Widen F Street at RR Station	Widen F Street including filling side to accommodate RR passenger area. Possible RR Fund ??	Partial VTRR Fund???
PW	Capital	24		\$ 500,000	\$ -	TRI	SO Substation 75	SO substation at Station 75	
PW	Roads	24		\$ 450,000	\$ -	VC	Realign Toll Rd at CCI	Realign the west end of Toll Road so it matches county property. Work with Community Chest.	Survey needed
VCTC/Rail	Rail	24		\$ 300,000	\$ -	VC	VC Depot Roof	VC new roof on VC Freight Depot	.25 cent sales V&T Rail Fund used

## Storey County Capital Improvement Plan *DRAFT*

Dept. Managing Project	Fund	Fiscal Year Target	Fiscal Year Target if Grants Secured	Total Estimate County Expense	Estimated Grant Funding	Project Location	Short Name	Description	Notes
VCTC/PW	Rail	24		\$ 250,000		VC	VC Depot Paving	Pave parking area around VC Freight Depot	25 cent sales V&T Rail Fund used
VCTC	Roads	24		\$ 50,000		VC	Fairgrounds Traffic	Install traffic calming devices on I and L Streets to slow Fairgrounds vehicles in residential areas	
VCTC	VCTC	24		\$ 130,000		VC	VCTC Center Design	Design new VCTC Visitors' Center at the Black and Howell site	Unless moving to DA/SO office
<b>2024 Project TOTALS:</b>				<b>\$ 9,655,000</b>	<b>\$ 5,015,000</b>				
<b>2024 Equipment &amp; Vehicles</b>									
CM	Equip. Acq.	24		\$ 60,000		CM	GMC 7-Passenger SUV	SUV per 2022 vehicle rotation with Community Development and Economic Development Officer	
PW	Equip. Acq.	24		\$ 20,000		PW	Light Plant w. Solar	Portable construction light plant w. solar array	
SO	Equip. Acq.	24		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle	
SO	Equip. Acq.	24		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle	
SO	Equip. Acq.	24		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle	
<b>2024 Equipment &amp; Vehicles TOTALS:</b>				<b>\$ 230,000</b>	<b>\$ -</b>				
<b>2024 Plans &amp; Studies</b>									
PW	Roads	24		\$ 100,000		County	Update Roads Rehab CIP	Farr West update to countywide road rehabilitation plan	
CM	County Mgr.	24		\$ 100,000		County	Regional Impact Study 2.0	Follow up to 1.0 fiscal impact study, and respond to legislative inquiries related to regional fiscal impacts	
Plan	Planning	24		\$ 100,000		County	Master Plan Update	5-Year Storey County Master Plan Update consultation and technical assistance	
CM	County Mgr.	24		\$ 5,000	\$ -	County	Strategic Plan	Continue working on strategic plan. To be completed Spring 2023 (FY23)	75% done. Winter '21 complete.
CM	County Mgr.	24		\$ 50,000	\$ -	County	Water Master Plan	South/Central county water master plan with Farr West Engineering	
Plan	Planning	24		\$ 50,000	\$ -	County	Road Abandon Study	Study and report to determine what roads may be considered for possible future abandonment.	
Plan	Planning	24	Grant 22	\$ 63,000	\$ 190,000	LW	N. Long Valley Creek Study	Drainage study for lower Long Valley Creek at and around Lockwood	Grant match to TRFMA.
Plan/VCTC	Planning/VCTC	24		\$ 50,000	\$ -	VC	VC Parking Study	Update to 1992 Parking Study for Virginia City ((What is the status on this happening FY23?))	
Plan	Planning	24		\$ 5,000		VC	VC Drainage Study	Study to evaluate drainage needs for Six Mile Canyon including NDEP/FEMA/EPA CERCLA mercury	EPA very difficult to overcome
<b>2024 Plans &amp; Studies TOTALS:</b>				<b>\$ 523,000</b>	<b>\$ 190,000</b>				
<b>2025 Projects</b>									
CD	Capital	25		\$ 50,000		VC	Comm. Dev. ADA	Improve ADA compliance at Community Development (doors, hallway, restroom, stoop)	
CD	Capital	25		\$ 50,000		VC	Comm. Dev. Bumps	Add bollards and bumpers to Community Development parking area	
CD	Capital	25		\$ 75,000		VC	Comm. Dev. Mud	Add mudroom/cold air entry to main entrance to Community Development office	
DC	Capital	25		\$ 250,000		VC	CH ADA Restrooms	Retrofit Storey County Courthouse with ADA restrooms, jury ADA accessibility, and related retrofits	
Dispatch	Capital	25		\$ 200,000		VC	Dispatch Security	Safety, security, and efficiency improvements to Dispatch Center building and grounds	
EM	Capital	25		\$ 1,500,000		VC	EOC	Emergency Operation Center located at or near 911 State Route 341	Alternative to school buildings
FD	Capital	25		\$ 5,500,000		MT	Fire Station 73 Replace	New fire station at Mark Twain	
FD	Capital	25		\$ 7,500,000		TRJ	Fire Station 75	New fire station 75 - move out of current station	
FD	Capital	25		\$ 1,000,000		LW	Land for Fire Station 74	Purchase land for relocation of Fire Station 74 Lockwood. Land out of FEMA floodplain but in Lockwood	
IT	Capital	25		\$ 120,000		County	LAN	Network devices, LANs, storage, and communications	
JC	Capital	25		\$ 150,000		VC	Justice Ct Parking Phase II	Pave and improve parking lot at Justice Court	
MTCC	Capital	25		\$ 150,000		MT	MT Comm. Electrical	Upgrade electrical and breakers at Mark Twain Community Center	
MTCC	Capital	25		\$ 50,000		MT	MT Comm. Roof	Check metal roof and make necessary repairs	Maintenance or infrastructure?
MTCC	Capital	25		\$ 250,000		MT	MT Comm. Fire Bay	Add separate building for fire apparatus so MTCC can expand into existing occupied bay area	
MTCC	Capital	25		\$ 25,000		MT	MT. Comm Lights	Install exterior lighting and parking lot lighting around Mark Twain Community Center	
MTCC	Capital	25		\$ 100,000		MT	MT. Comm Trees	Add landscaping, trees, and irrigation around the Mark Twain Community Center	

### Storey County Capital Improvement Plan *DRAFT*

Dept. Managing Project	Fund	Fiscal Year Target	Fiscal Year Target if Grants Secured	Total Estimate County Expense	Estimated Grant Funding	Project Location	Short Name	Description	Notes
MTCC	Capital	25		\$ 200,000		MT	MT Comm Repave	Repave parking lot at Mark Twain Community Center	
Plan	Capital/Roads	25	Grant 28	\$ 200,000	\$ 10,000,000	VC	VC/6 Mile Flood Implemen	Implement Six Mile Drainage Project - From Master Drainage Plan Started in 2022	200k county match per CWSD
PW	Infrastructure	24		\$ 5,000,000		VC	School Building Buy Ph. 1	Purchase VCMS and HG Elementary school buildings for county admin offices and comm. chambers	Pending SCSD land and K12.
PW	Capital	25		\$ 100,000		VC	Generator VCSC	Generator for VC Senior Center facility	
PW	Capital	25		\$ 100,000		VC	Generator SMAC	Generator for Saint Mary's Art Center	
PW	Capital	25		\$ 100,000		VC	Generator Fourth Ward	Generator for Fourth Ward School	
PW	Capital	25		\$ 15,000		VC	Generator GH Train Depot	Generator for Gold Hill Train Depot	
PW	Capital	25		\$ 15,000		VC	Generator VC Train Depot	Generator for VC Train Depot for fire sprinkler heating	
PW	Capital	25		\$ 100,000		VC	Generator SC Justice Court	Generator for Storey County Justice Court and IT offices	
PW	Capital	25		\$ 100,000		GH	Generator GH Sewer	Generator for Gold Hill wastewater treatment plant	
PW	Capital	25		\$ 100,000		VC	Generator Comptroller	Generator connect comptroller's office to Courthouse	
PW	Capital	25		\$ 200,000		MT	MT Comm. Center	Retrofit Mark Twain Community Center to better facilitate events, food closet, and senior services	
PW	Capital	25		\$ 75,000		VC	Water Filters	Replace water filter media. Anthracite coal, green sand, aggregate, and poly beads	
PW	Capital	25		\$ 150,000		LW	LW Dog Park	Construct dog park near Louise Peri Park in Lockwood	
PW	Capital	25		\$ 200,000		VC	CH Generator Replace	Replace Courthouse backup generator and related equipment	
PW	Capital	25		\$ 300,000		VC	Fuel Tanks at PW	Replace double-lined fuel tank at Public Works shop	
PW	Capital	25		\$ 150,000		VC	VC Dog Park	Construct dog park near Miner's Park or other location as appropriate	
PW	Facilities	25		\$ 150,000		MT	MT Dog Park	Construct dog park near Mark Twain Community Park	
PW	Infrastructure	25		\$ 700,000		VC	Water Treat Pre-Tank	VC water plan replace open bodies with tank	
PW	Infrastructure	25		\$ 150,000		VC	Water Plant Valves	Replace Limitorque Control Packs for the influent and effluent valves at sewer treatment plant	
PW	Capital	25		\$ 120,000		VC-GH	Phase I Bike/Ped Lane GH	Phase I-Grade and gravel bike/ped path between Gold Hill and VC (Fourth Ward to Greiner's historic way)	Seek recreation grants
PW	Infrastructure	25		\$ 150,000		VCH	VCH Comm. Center	(Phase 2) VCH community center building retrofit restrooms, etc (Construction after Fire Station 72 Bays)	Pending Station 72 bays
PW	Infrastructure	25		\$ 230,000		VC	Washington St. Stairs	Replace wood stairs at Washington Street between C and D Streets	
PW	Infra/Capital	25		\$ 4,000,000		VC	County Swimming Pool	Rehabilitate 1964 Storey County Swimming Pool with updated and compliant facility	
PW	Infra/Capital	25		\$ 500,000		VC	VC Transfer Station Move	Relocate waste transfer station to accommodate school expansions	Alternative A
PW	Infra/Capital	25		\$ 150,000		VC	VC Transfer Station Screen	Screen, wall off, and reposition transfer station to accommodate and accompany school expansion	Alternative B
PW	Infrastructure	25		\$ 300,000		VCH	VCH Community Center	Highlands community center building upgrades - completed after fire bays are constructed	
PW	Infrastructure	25		\$ 85,000		VC	Water Tank Upgrades	Repair and seal of VC water tanks. See 2023/24 Infrastructure Ordinance.	
PW	Infra/Roads	25		\$ 705,000		County	Road Projects Countywide	Countywide road rehabilitation projects per Farr West CIP report. See 23/24 Infrastructure Ordinance	50/50 Infrastructure/Roads
PW	Infrastructure	25		\$ 1,500,000		TRI	Pittsburgh to Ireland	Finish Pittsburgh west segment connecting it to Ireland. Note drainage improvements	
PW	Infrastructure	25		\$ 1,000,000		TRI	Pittsburgh Drainage	Correct culverts and drainage way beneath Pittsburgh Drive west segment	
PW	Roads	25		\$ 1,000,000		TRI	Sydney Cul-De-Sac	Correct cul-de-sac at Sydney Drive to remove GID building and drainages. Add south-to-north drainage	Reconveyance needed
PW	Roads	25		\$ 2,000,000		VCH	Cartwright	Cartwright Road widening, shoulder improvements, and drainage reconstruction	
PW	Roads	25		\$ 500,000		MT	Culverts Sam Clemens N	Bridge on Sam Clemens over existing north high-water crossing	
PW	Roads	25		\$ 500,000		MT	Culverts Sam Clemens S	Bridge on Sam Clemens over existing south high-water crossing	
PW	Roads	25		\$ 2,000,000		VCH	Lousetown	Lousetown Road widening, shoulder improvements, and drainage reconstruction	
PW	Water	25		\$ 3,000,000		VC	B and Union St. Water Line	B and Union Street Water Mains (10-inch PVC Main, 8-inch PVC main, Meters and Service, Traffic Control.	Engineering report done Jan '22
PW	Water	25		\$ 3,000,000		VC	Flowery, D to Silver Water	Flowery between C and D, running south on D to Silver, east on Silver to E Street, and Noyes St to Silver	
PW	Water	25		\$ 900,000		SC	Silver City Tank	Replace Silver City Water Tank	Engineering report done Jan '22
PW	Water	25		\$ 900,000		VC	Taylor Tank	Replace Taylor Water Tank	Engineering report done Jan '22
PW	Water	25		\$ 6,000,000		VC	VC Water Distribution Line	Replace water distribution lines in Virginia City	
PW	Water	25		\$ 4,000,000		GH	GH Water Distribution Line	Replace water distribution lines in Gold Hill	See draft water plan
Recorder	Capital	25		\$ 1,000,000		County	Archive Building	Document archive building that is secure, temperature controlled	
VCTC	Roads/Rail	25		\$ 400,000		VC	Fairgrounds Rd. RR.	Realign, correct, and properly signal RR crossing at Fairgrounds Road and F Street	25 cent sales V&T Rail Fund?
VCTC	Roads/Rail	25		\$ 500,000		VC	Restrooms C Street	Add public restrooms at vacant lot between Zephas and Liberty Engine 1	One of four alternatives

### Storey County Capital Improvement Plan *DRAFT*

	Dept. Managing Project	Fund	Fiscal Year Target	Fiscal Year Target if Grants Secured	Total Estimate County Expense	Estimated Grant Funding	Project Location	Short Name	Description	Notes
Pending	VCTC	VCTC	25		\$ 3,000,000		VC	VCTC Center Build	Build new VCTC Visitors' Center at the Black and Howell site (corner of C and Taylor) owned by county	Explore other alternatives too
<b>2025 Project TOTALS:</b>					<b>\$ 62,515,000</b>	<b>\$ 10,000,000</b>				
<b>2025 Equipment &amp; Vehicles</b>										
PW	Equip. Acq.		25		\$ 250,000		PW	Water Truck	Water truck. Currently must switch out water tank with plow hardware each season.	
PW	Equip. Acq.		25		\$ 330,000		PW	Road Sweeper	Street sweeper truck	
PW	Equip. Acq.		25		\$ 200,000		PW	Short-Frame Plow	Peterbuilt heavy truck plow and sander to replace International plow	
PW	Equip. Acq.		25		\$ 300,000		PW	Peterbuilt Dump Truck	Dump Truck. Replace current Kenworth.	
PW	Equip. Acq.		25		\$ 200,000		PW	1 Ton Contractor Truck	F-550/5500 Diesel contractor body one-ton truck	
PW	Equip. Acq.		25		\$ 50,000		PW	Forklift	10,000 lbs. forklift	
PW	Equip. Acq.		25		\$ 150,000		PW	Skippy Tractor	John Deere Skippy loader box grader tractor	
PW	Equip. Acq.		25		\$ 100,000		PW	Road Kick Broom	Road Kick Off Broom	
PW	Equip. Acq.		25		\$ 20,000		PW	Light Plant w. Solar	Portable light plant w. solar array for construction project lighting	
PW	Equip. Acq.		25		\$ 60,000		PW	GMC Buildings/Gnds	GMC 3/4 ton long-bed gas pickup with shell for water and sewer	
PW	Equip. Acq.		25		\$ 70,000		PW	GMC Buildings/Gnds	GMC 4-door diesel w. utility bed for buildings/grounds. Needs to pull weight.	
PW	Equip. Acq.		25		\$ 350,000		PW	Motor Grader	John Deere Motor Grader	
Sheriff	Equip. Acq.		25		\$ 250,000		SO	Mobile EOC	Mobile emergency operations center.	
Sheriff	Equip. Acq.		25		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
Sheriff	Equip. Acq.		25		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
Sheriff	Equip. Acq.		25		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
<b>2024 Equipment &amp; Vehicles TOTALS:</b>					<b>\$ 2,480,000</b>	<b>\$ -</b>				
<b>2026 Projects</b>										
FD	Capital		26		\$ 1,250,000		VCH	Station 72 Fuel Mgt Quarte	Living quarters for fire crew and fire fuels and seasonal crews at VCH	
FD	Capital		26		\$ 2,500,000		County	Fire Training Tower North	FD Training Tower North District (LW, PR, TRI)	
FD	Capital		26		\$ 7,500,000		Fire	LW Fire Station 74 Move	Move Fire Station 74 Lockwood out of FEMA Floodplain	When Patrick is developed
Plan	Planning		26		\$ 20,000	\$ 100,000	TRI	TRI Drainage Study	Study to evaluate drainage needs for Tahoe-Reno Industrial Center on county-owned roads and parcels	For county-owned ROW only
PW	Capital		26		\$ 100,000		LW	Fuel Tanks at PW LW	Replace double-lined fuel tank at Lockwood Fire Station 74	
PW	Capital		26		\$ 100,000		TRI	Fuel Tanks at PW TRI	Replace double-lined fuel tank at TRI-Center Station 75	
PW	Capital		26		\$ 100,000		VCH	VCH Mailbox Plaza	Reconstruct and expand snow shelter mailbox plaza at Highlands	
PW	Capital		26		\$ 1,500,000		VC	PW Fire Truck Shop	Expand service shop to accommodate fire apparatus and large commercial vehicles	Need meeting to discuss possible locati
PW	Capital		26		\$ 1,000,000		MT	MT Park Space	Develop space between MT Park and MTCC with seating, shade, barbecues, and usable space	
PW	Capital		26		\$ 240,000		VC/GH	Phase II Bike/Ped Lane GH	Phase II-Pave bike/pedestrian route between Gold Hill and VC historic route	Seek recreation grants
PW	Roads		26		\$ 150,000		TRI	TRI Waltham Bus Stop	Covered transit bus shelter and bus stop staging at Waltham Way location	
PW	Roads		26		\$ 150,000		TRI	TRI Electric Bus Stop	Covered transit bus shelter and bus stop staging on Electric Avenue	
PW	Roads		26		\$ 150,000		TRI	TRI USA Bus Stop	Covered transit bus shelter and bus stop staging on USA, Peru, or Sydney	
PW	Roads		26		\$ 150,000		TRI	TRI Venice Bus Stop	Covered transit bus shelter and bus stop staging on Venice, Denmark, or Pittsburgh	
PW	Infrastructure		26		\$ 85,000		VC	Water Tank Upgrades	Repair and seal VC water tanks. See 23/24 Infrastructure Ordinance	
PW	Infra/Roads		26		\$ 476,000		County	Road Projects Countywide	Countywide road rehabilitation projects per Farr West CIP report. See 23/24 Infrastructure Ordinance	50/50 Infrastructure/Roads
PW	Infra/Capital		26		\$ 4,000,000		VC/MT	Bridge at Six Mile Cyn	New and wider bridge over Six Mile Canyon Creek in Six Mile Canyon Road	
PW	Rail		26		\$ 200,000		GH	Gold Hill Depot Paint	Paint exterior of Gold Hill V&T Depot	.25 cent sales V&T Rail Fund
PW	Rail		26		\$ 200,000		VC	VC Depot Paint	Paint exterior of VC V&T Depot	.25 cent sales V&T Rail Fund
PW	Infrastructure		24		\$ 5,000,000		VC	School Building Buy Ph. 2	Purchase VCMS and HG Elementary school buildings for county admin offices and comm. chambers.	Pending SCSD land and K12. Phase 2

### Storey County Capital Improvement Plan DRAFT

Dept. Managing Project	Fund	Fiscal Year Target	Fiscal Year Target if Grants Secured	Total Estimate County Expense	Estimated Grant Funding	Project Location	Short Name	Description	Notes
PW	Rail	26		\$ 20,000		GH	Survey GH Depot Land	Survey and reconsolidate land in and around Gold Hill Freight Depot for parking and staging	
PW	Roads	26		\$ 50,000		VC	SR 341 Retain Wall	Reconstruct retaining wall adjacent to residence on north end of SR 341 in Virginia City	NDOT conversation to continue
PW	Roads	26		\$ 3,000,000		VC	Pave all VC dirt roads	Road expansion and paving in Virginia City to facilitate building on existing platted lots	Affordable housing
PW	Water	26		\$ 1,440,000		VC/GH	Divide Tank	Replace Divide Water Tank - Why if each year we repair and seal the tanks/ Where will this go?	Engineering report done Jan '22
PW	Water	26		\$ 1,253,000		VC	Hillside to Divide Main	12-inch PVC Water Main Hillside Tanks to Divide Tank. (12-inch PVC Main, Engineering, etc.)	
PW	Water	26		\$ 2,640,000		SC/GH	Silver City Water Main	8-inch PVC PRV water main between Gold Hill and Silver City to the Silver City Water Tank	
PW	Water	26		\$ 720,000		VC	Five Mile Res. Wall	Wall surrounding Five Mile Reservoir	
PW	Water	26		\$ 360,000		VC	Water Treat Plant Wall	Wall abutting south of water treatment center ponds	
VCTC	Capital	26		\$ 10,000,000		VC	Convention Center	Convention center for VCTC, county, companies, etc., conferences and conventions	
Piper's	Capital	26		\$ 405,000		VC	Piper's Wall Structure	West building wall/water infiltration	See Historic Structures Report
PW	Roads	26		\$ 850,000		VC	Piper's Road Improve	A Street Roadway improvements	See Historic Structures Report
Piper's	Capital	26		\$ 50,000		VC	Piper's Repairs	Complete stairs to balcony, Balcony repairs "as-exists", Restroom exhaust fans, Replace missing finials	See Historic Structures Report
Piper's	Capital	26		\$ 162,500		VC	Piper's Exterior	Repaint/repair brick & mortar at Old Corner Bar, Refurbish 7 front doors, Replace exterior egress stairs North	See Historic Structures Report
<b>2026 Project TOTALS:</b>				<b>\$ 45,821,500</b>	<b>\$ 100,000</b>				
<b>2026 Plans &amp; Studies</b>									
Plan	Cty Mgr	26		\$ 20,000		VCH/VC	VCH/Comstock Nat Gas	Farr West study of natural gas transmission and distribution for Highlands and Comstock - Move later???	Start with 15% study feasibility
Plan	Planning	24		\$ 5,000	\$ -	GH	GH Drainage Study	Study to evaluate drainage needs for Gold Canyon, Gold Hill, American Flat including NDEP/FEMA/EPA	
Plan	Water	26		\$ 20,000		County	VCH Water Plan	Update 2022 Water Master Plan for VCH water distribution system	
<b>2026 Plans &amp; Studies TOTALS:</b>				<b>\$ 45,000</b>	<b>\$ -</b>				
<b>2026 Equipment &amp; Vehicles</b>									
CD	Equip. Acq	26		\$ 40,000		CD	Pickup CD	Replace current vehicle per rotation schedule	
PW	Equip. Acq	26		\$ 300,000		PW	Peterbilt Dump Truck	Dump Truck	
PW	Equip. Acq	26		\$ 150,000		PW	Service Truck	Service F550/5500 chassis with service body	
PW	Equip. Acq	26		\$ 230,000		PW	John Deere Loader	John Deere Loader to replace TRI Center loader	Some recovery at auction
PW	Equip. Acq	26		\$ 200,000		PW	Service Truck w. Crane	Service Truck Diesel with Crane Body	
PW	Equip. Acq	26		\$ 200,000		PW	1 Ton Contractor Truck	F550/5500 Diesel contractor body one-ton truck	
PW	Equip. Acq	26		\$ 250,000		PW	Dump Truck	Replace Ford L9000 Dump Truck with new 10-wheel dump truck	
SO	Equip. Acq	26		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
SO	Equip. Acq	26		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
SO	Equip. Acq	26		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
<b>2026 Equipment &amp; Vehicles TOTALS:</b>				<b>\$ 1,520,000</b>	<b>\$ -</b>				
<b>2027 Projects</b>									
FD	Infrastructure	27		\$ 650,000		County	Reserve Fire Apparatus Storage	Add fire apparatus storage building for reserve firefighters - <i>Where?</i>	
FD	Infrastructure	27		\$ 7,500,000		TRI	Add Fire Station 77 TRI N.	Add Fire Station 77 at TRI per ISO rating to access south TRI area near Lyon-Storey Line	Possible shared Storey-Lyon Facility
IT	Capital	27		\$ 100,000		County	Security Key Fobs	Countywide key fob entrance security system	
PW	Capital	27		\$ 1,800,000		VC	CH Earthquake Retro.	Earthquake retrofit of County Courthouse	See Historic Structures Report
PW	Capital	27		\$ 100,000		VC	Seismic VC Sr Center	Earthquake retrofit VC Senior Center	
PW	Capital	27		\$ 5,000,000		VC	VC Senior Center	Replace or expand VC Senior Center serving Highlands and Comstock.	
PW	Capital	27		\$ 12,000		MT	MT BMX Comp Track	BMX freestyle bicycle competition track	Requested by resident



### Storey County Capital Improvement Plan *DRAFT*

Dept. Managing Project	Fund	Fiscal Year Target	Fiscal Year Target if Grants Secured	Total Estimate County Expense	Estimated Grant Funding	Project Location	Short Name	Description	Notes
PW	Capital	27		\$ 180,000		MT	MT Skateboard Park	Skateboard Park Mark Twain	Location TBD
PW	Capital	27		\$ 180,000		VC/GH	VC Skateboard Park	Skateboard Park Virginia City or Gold Hill	Location TBD
PW	Capital	27		\$ 180,000		LW	LW Skateboard Park	Skateboard Park Lockwood	Location TBD
PW	Infrastructure	27		\$ 85,000		VC	Water Tank Upgrades	Repair and seal VC water tanks. See 23/24 Infrastructure Ordinance.	
PW	Infra/Roads	27		\$ 5,100,000		County	Road Projects Countywide	Countywide road rehabilitation projects per Farr West CIP report. See 23/24 Infrastructure Ordinance.	25/75 Infrastructure/Roads
PW	Infrastructure	27		\$ 1,200,000		GH	GH Sewer Lines	Replace sewer lines in Gold Hill	Plan needed
PW	Infra/Capital	27		\$ 1,800,000		VC	Seismic retro St. Mary's	Earthquake retrofit of Saint Mary's Art Center (old hospital)	Estimate needed
PW	Infra/Capital	27		\$ 1,800,000		VC	Seismic retro Fourth Wd.	Earthquake retrofit of Fourth Ward School	Estimate needed
PW	Infra/Capital	27		\$ 1,800,000		VC	Seismic retro Piper's	Earthquake retrofit of Piper's Opera House	Estimate needed
PW	Infra/Capital	27		\$ 75,000		LW	LW School Bus Stop Cover	Covered snow shelter for school students at SCSD designated bus stop	School district location
PW	Infra/Capital	27		\$ 75,000		VC	VC School Bus Stop Cover	Covered snow shelter for school students at SCSD designated bus stop	School district location
PW	Infra/Capital	27		\$ 75,000		MT	MT School Bus Stop Cover	Covered snow shelter for school students at SCSD designated bus stop	School district location
PW	Infra/Capital	27		\$ 75,000		VCH	VCH School Bus Stop Cover	Covered snow shelter for school students at SCSD designated bus stop	School district location
PW	Pipers	27		\$ 600,000		VC	Piper's Structural Retro	Retrofit Piper's Opera House structural integrity, ADA access, interior improvements, retaining wall, etc.	
PW	Roads	27		\$ 100,000		VC	Boardwalk Ext./Ped Trail	Pedestrian trail paved between Fourth Ward School and Virginia City Motel and Justice Court.	
PW	Rail	27		\$ 150,000		GH	GH Depot Parking	Improve Gold Hill Freight Depot area for parking and vehicle staging	
VCTC/PW	Rail	27		\$ 200,000		GH	GH Depot Parking Pave	Pave parking area around Gold Hill Freight Depot	Mapping needed
VCTC	Capital	27		\$ 250,000		VC	Taylor St. Stairs	Replace historic Taylor Street stairs from C to B Street	Engineering complete. Ready
VCTC	Pipers	27		\$ 250,000		County	Piper's Electrical	Upgrade service to 600A, Add emergency generator	See Historic Structures Report
VCTC	Pipers	27		\$ 60,000		County	Piper's Kitchen		See Historic Structures Report
<b>2027 Project TOTALS:</b>				<b>\$ 29,397,000</b>	<b>\$ -</b>				
<b>2027 Equipment &amp; Vehicles</b>									
PW	Equip. Acq.	27		\$ 130,000		PW	Service Truck	Service F550/5500 chassis with service body	
PW	Equip. Acq.	27		\$ 250,000		PW	5 Yard AWD Dump Truck	Five yard all-wheel-drive dump truck with plow prep.	
PW	Equip. Acq.	27		\$ 300,000		PW	Tractor Trailer	Peterbuilt Truck and RGN Transport Trailer.	
PW	Equip. Acq.	27		\$ 650,000		PW	Vactor Truck (north)	New Vactor Truck to serve north end of Storey County (LW, TRI, PR)	
SO	Equip. Acq.	27		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
SO	Equip. Acq.	27		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
SO	Equip. Acq.	27		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
<b>2027 Equipment &amp; Vehicles TOTALS:</b>				<b>\$ 1,480,000</b>	<b>\$ -</b>				
<b>2027 Plans &amp; Studies</b>									
PW	Roads	27		\$ 100,000		County	Roads CIP VC	Update Roads CIP to widen, straighten, shoulder, and upgrade county roads countywide	Roads CIP done by Farr West.
<b>2027 Plans &amp; Studies TOTALS:</b>				<b>\$ 100,000</b>	<b>\$ -</b>				
<b>2028 Projects</b>									
DC	District Court	28	Grant 28	\$ 20,000,000	\$ 4,000,000	County	First District Courthouse	New First District Court per upcoming First District Court orders for modern and secure court facilities	
FD	Capital	28		\$ 7,500,000		VCH	Fire Station 72 VCH	Replace dated fire station at VCH	
FD	Capital	28		\$ 7,500,000		PR	Fire Station 76 PR	Dependent on planned unit development status at PR	
FD	Capital	28		\$ 2,500,000		County	Fire Training Tower	South District Training Tower (VC, VCH, MT)	
PW	Facilities	28		\$ 500,000		VCH	County Horse Shelter	Wild horse rescue center in at VCH run by VRWPA or other qualified non-profit	Location TBD

## Storey County Capital Improvement Plan DRAFT

	Dept. Managing Project	Fund	Fiscal Year Target	Fiscal Year Target if Grants Secured	Total Estimate County Expense	Estimated Grant Funding	Project Location	Short Name	Description	Notes
	Fire	Infrastructure	28	Grant 28	\$ 700,000	\$ 3,500,000	VCH	Replace Fire Station 72 VC	Replace Fire Station 72 VCH with larger building and sleeping quarters to meet area needs	
	Plan	Infrastructure	28		\$ 500,000		LW	LCC Gas Lines	Replace gas distribution lines throughout LCC. Allow NV Energy to connect LCC to new LW natural gas utility	Discovery Phase Assess now
	Plan	Infrastructure/G	28	Grant 25	\$ 200,000	\$ 10,000,000	MT	Mark Twain Drainage	Implement DVAMP master plan including drainage, detention basins, easements, culverts, etc.	Lyon match, CWSD too, plan done
	Plan/PW	Capital	28		\$ 360,000		VC	East C St. Boardwalk	Replace wooden sidewalk along west edge of C Street between SO office and Fourth Ward School	"Main Streets" funding?
	Plan/PW	Capital	28		\$ 600,000		VC	West C St. Boardwalk	Sidewalk along east shoulder of C Street between SO office and Fourth Ward School	"Main Streets" funding?
	PW	Capital	28		\$ 500,000		TRI	TRI Admin Offices	Develop TRI Government Center to accommodate all remote county offices for north access	Painted Rock PUD service too
	PW	Capital	28		\$ 2,000,000		MT	Regional Fire Train Center	Add fire and emergency training site near Mark Twain Community Center	
	PW	Capital	28		\$ 700,000		LW	LW Riverwalk	Riverwalk, shade, etc., between Menizes and Rainbow Bend to access by all Lockwood residents	
	PW	Capital	28		\$ 2,000,000		VC	VC South Entrance Rest St	Develop south entrance to VC with restrooms, parking, and visitor information kiosks	
	PW	Capital	28		\$ 4,000,000		VC	Swimming Pool Cover	Cover new swimming pool to become indoor facility and year-round service	
	PW	General	28		\$ 1,000,000		LW	LW Land Acquire Washoe	Acquire vacant land north of Rainbow Bend	Request land swap from Washoe
	PW	Infrastructure	28		\$ 10,000,000		PR	Bridge at Painted Rock	Replace existing Painted Rock Bridge over Truckee River.	
	PW	Infrastructure	28		\$ 2,000,000		LW	Bridge at Rainbow Bend	New and wider bridge over Long Valley Creek in Rainbow Bend at Avenue of the Colors	Tie in with LW Flood Project
	PW	Infrastructure	28		\$ 2,000,000		LW	Bridge at Peri Ranch Rd	New and wider bridge over Long Valley Creek into Peri Ranch Road at the Lockwood Community Corp.	
	PW	Infrastructure	28		\$ 2,000,000		LW	Bridge at southern LCC Rd	New and wider bridge over Long Valley Creek into (( )) at the Lockwood Community Corp.	
	PW	Infrastructure	28		\$ 2,500,000		GH	Gold Hill Sewer Expansion	Expand Gold Hill wastewater facility (x2) to facilitate new residential/commercial construction	Affordable housing
	PW	Roads	28		\$ 500,000		VCH	Long Valley Rd Improve	Long Valley Road improvements, drainage reconstruction, and paving. First 2 miles from Lousetown.	
	PW	Roads	28		\$ 1,000,000		LW	Peri Ranch Rd. west	Widen, improve, and separate from residential units Peri Ranch Road from comm center to Canyon Way	Pending alignment by Leporie
	PW	Roads	28		\$ 2,000,000		VC	C Street Fix from NDOT	Drainage, shoulder, curb, retaining walls, and structural repairs on C Street	Per NDOT relinquishment
	PW	Roads	28		\$ 240,000		VC	Boardwalk North (west)	Boardwalk/sidewalk west side of C Street from Sutton to Carson Street	Main Streets funding?
	PW	Roads	28		\$ 240,000		VC	Boardwalk North (east)	Boardwalk/sidewalk east side of C Street from Sutton to Carson Street (bridge over Marsh park lot)	Main Streets funding?
	PW	Roads	28		\$ 360,000		VC	Boardwalk North Bridge	Boardwalk/sidewalk east side of C Street bridge/overhang over lower parking lot segment	Main Streets funding?
	SO	Jail-Justice	28	Grant 28	\$ 15,000,000	\$ 3,000,000	VC	Jail-Justice Complex	Replace VC jail facility due to safety and security	
	VCTC	Pipers	28		\$ 363,000		VC	Piper's HVAC/Plumbing	Add 60 gallon h2o heater, auditorium hydronic heating and evaporative cooling, direct ventilation, roof ventilat	See Historic Structures Report
	VCTC	Pipers	28		\$ 70,000		VC	Piper's Carriage House	Prep 2 opening for Carriage house doors, refurbish/rebuild 2 carriage house doors	See Historic Structures Report
	VCTC	Pipers	28		\$ 250,000		VC	Piper's Balcony	Balcony repairs "full use" option	
	VCTC	VCTC	28	Grant 28	\$ 1,000,000	\$ 200,000	VC	Inclinator F to C Street	Inclinator from VC Freight Depot (multi-modal transit hub) to C Street	Estimate needed
					<b>2027 Project TOTALS:</b>	<b>\$ 90,083,000</b>	<b>\$ 20,700,000</b>			
<b>2028 Equipment &amp; Vehicles</b>										
	CD	Equip. Acq.	28		\$ 50,000		CD	Pickup CD	Replace current vehicle per rotation schedule	
	CD	Equip. Acq.	28		\$ 50,000		CD	Pickup CD	Replace current vehicle per rotation schedule	
	CM	Equip. Acq.	28		\$ 50,000		CM	Staff Vehicle	Replace current vehicle per rotation schedule and anticipated mileage	
	Dispatch	Equip. Acq.	28		\$ 50,000		Dispatch	Staff Vehicle	Replace current vehicle per rotation schedule and anticipated mileage	
	IT	Equip. Acq.	28		\$ 50,000		IT	Staff Vehicle	Replace current vehicle per rotation schedule and anticipated mileage	
	PW	Equip. Acq.	28		\$ 50,000		PW	Staff Vehicle	Replace current vehicle per rotation schedule and anticipated mileage	
	SCSC	Equip. Acq.	28		\$ 50,000		SCSC	Staff Vehicle	Replace current vehicle per rotation schedule and anticipated mileage	
	SO	Equip. Acq.	28		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
	SO	Equip. Acq.	28		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
	SO	Equip. Acq.	28		\$ 50,000		SO	Patrol Vehicle Rotation	Patrol vehicle per three-year rotation. Some funds recovered with auctioning out replaced vehicle.	
	VCTC	Equip. Acq.	28		\$ 50,000		VCTC	Staff Vehicle	Replace current vehicle per rotation schedule and anticipated mileage	
					<b>2028 Equipment &amp; Vehicles TOTALS:</b>	<b>\$ 550,000</b>	<b>\$ -</b>			

### Storey County Capital Improvement Plan *DRAFT*

Dept. Managing Project	Fund	Fiscal Year Target	Fiscal Year Target if Grants Secured	Total Estimate County Expense	Estimated Grant Funding	Project Location	Short Name	Description	Notes
<b>2028 Plans &amp; Studies</b>									
Plan	Planning	28		\$ 100,000		County	Master Plan Update	10-Year Storey County Master Plan Update consultation and technical assistance.	
<b>2028 Plans &amp; Studies TOTALS:</b>				<b>\$ 100,000</b>	<b>\$ -</b>				
<b>2029 Projects</b>									
PW	Capital	29		\$ 12,000,000		County	Regional Animal Shelter	Regional animal center for small and large animals (Coordinate with Lyon and other counties)	
PW	Capital	29		\$ 2,000,000		VCH	Petroglyphs Ranger Stn.	Develop ranger station, tourism center, parking, restrooms, etc. to open and protect Petroglyphs site	
PW	Capital	29		\$ 500,000		VC	VC TC Visitors' Center	Occupy and rehabilitate existing DA/Sheriff Office into VC TC Visitors' Center. Per moving to school build.	
PW	Capital	29		\$ 100,000		LW	LW Amphitheater	Construct outdoor amphitheater in Lockwood near Louise Peri Park	
PW	Capital	29		\$ 100,000		VC	VC Amphitheater	Construct outdoor amphitheater in VC near Miner's Park and Community Chest	
PW	Capital	29		\$ 100,000		MT	MT Amphitheater	Construct outdoor amphitheater in Mark Twain in gap between park and Community Center	
PW	Capital	29		\$ 100,000		VCH	VCH Amphitheater	Construct outdoor amphitheater in Highlands on land between Community Center and Lousetown Rd	
PW	Capital	29		\$ 1,000,000		VC	School Admin Building TI	Retrofits to move administrative offices to E Street schools when school moves to K12 facility	Courthouse remain court
PW	Capital	29		\$ 200,000		VC	School Admin Building TI	Retrofits to create board/commission chambers at existing school gym when move occurs	Community chambers
PW	Capital	29		\$ 4,000,000		VC	Divide Reservoir Park	Add recreation facilities (benches, barbecues, fishing dock, etc.) to Divide Reservoir for public use	2016 Master Plan supported
PW	Capital	29		\$ 1,000,000		MT	Entrance Kiosk and Impv.	Community information bulletin kiosk, parking, benches, lighting, and improvements	
PW	Capital	29		\$ 1,000,000		LW	Entrance Kiosk and Impv.	Community information bulletin kiosk, parking, benches, lighting, and improvements	
PW	Capital	29		\$ 1,000,000		VCH	Entrance Kiosk and Impv.	Community information bulletin kiosk, parking, benches, lighting, and improvements	
PW	Capital	29		\$ 1,000,000		VC	Entrance Kiosk and Impv.	Community information bulletin kiosk, parking, benches, lighting, and improvements	
PW	Capital	29		\$ 1,000,000		TRI	Entrance Kiosk and Impv.	Community information bulletin kiosk, parking, benches, lighting, and improvements	
PW	Capital	29		\$ 4,000,000		TRI	TRI Justice Center	Add justice complex to TRI (Court, jail, administration, SO substation, other offices and facilities)	
PW	Capital	29		\$ 10,000,000		Unknown	Ice Skating Rink	Ice Skating Rink per request at community town hall. Location TBD	Requested at Town Hall 2021
PW	Infrastructure	29		\$ 80,000,000		VCH	Water Transmission to VCH	Water transmission line from VC to Highlands	See Water Master Plan 2022
PW	Infrastructure	29		\$ 12,000,000		VC	Parallel Siphon Comstock	Parallel siphon 1580 to Five Mile Res. For Comstock Buildout 1,086 gpm 12 inch main, 6" air release valves	See Water Master Plan 2022
PW	Infrastructure	29		\$ 2,400,000		VC	Upgrade Water Capacity	WTP Capacity Upgrade, Comstock Buildout 1.5 MGD capacity	See Water Master Plan 2022
PW	Infrastructure	29		\$ 127,000,000	\$ 25,400,000	VC	Water to Highlands	Water transmission, capacity storage, treatment, and distribution to Highlands	2022 Water Master Plan. Explore funds
PW	Infrastructure	29		\$ 5,000,000		VC	VC Power Lines Undergrnd	Underground power lines in downtown Virginia City area	Subject to community desire.
PW	Infrastructure	29		\$ 80,000,000		VCH	VCH Natural Gas Trans.	Natural Gas transmission lines from north county to Highlands and Comstock	NV Energy projet pending. Explore fun
PW	Infrastructure	29		\$ 26,000,000	\$ 5,200,000	MT	Water to Mark Twain	Water transmission, capacity storage, treatment, and distribution to Mark Twain Estates	See Water Master Plan 2022
PW	Infrastructure	29		\$ 50,000,000		VCH	VCH Natural Gas Distrib.	Natural Gas distribution lines from new main to residences and businesses in VCH and Comstock	NV Energy projet pending. Explore fun
PW	Infrastructure	29		\$ 80,000,000		VC	VC Natural Gas Trans.	Natural Gas transmission line from south county to Virginia Cith and Gold Hill	NV Energy projet pending. Explore fun
PW	Infrastructure	29		\$ 50,000,000		VC	VC Natural Gas Distrib.	Natural gas distribution line from new main to residences and businesses in VC and Gold Hill	NV Energy projet pending. Explore fun
PW	Roads	29		\$ 5,000,000		VCH	Lousetown-341 Intersection	Improve access and egress at Lousetown and SR 341 intersection	
PW	Roads	29		\$ 5,000,000		VC	B Street Widen/Parking	Widen B Street between Taylor and Sutton. Provide angled parking for visitors and residents	Design subject to community
PW	Roads	29		\$ 5,000,000		VC	D Street Widen/Parking	Widen and straighten D and/or E Streets for angled parking, loop circulation, and C Street avoidance	Design subject to community
PW	Roads	29		\$ 2,000,000		VC	C Street Parking/Amend	Amend traffic patterns on C Street around improvements to B, D, and E Streets	Design subject to community
PW	Roads	29		\$ 10,000,000		LW	LW Ramp Improvement	Widen and improve safety on Canyon Way ramp approaching I-80 interchange	Subject to Washoe land swap
<b>2029 Project TOTALS:</b>				<b>\$ 578,500,000</b>	<b>\$ 30,600,000</b>				
<b>Notes and Abbreviations</b>									
<b>CIP TOTALS:</b>				<b>\$ 830,065,713</b>	<b>\$ 66,415,000</b>			CM = County Manager	
								CR = Community Relations	
								DC = District Court	



**3.2 – Audit**


**Audit Report  
STOREY COUNTY, NEVADA  
June 30, 2022**

**STOREY COUNTY, NEVADA**  
**TABLE OF CONTENTS**  
**JUNE 30, 2022**

<b>FINANCIAL SECTION</b>	<b>Page</b>
Independent Auditor's Report.....	1
Management's Discussion and Analysis.....	4
Basic Financial Statements	
Government-wide Financial Statements	
Statement of Net Position.....	12
Statement of Activities.....	13
Fund Financial Statements:	
Governmental Funds	
Balance Sheet.....	15
Reconciliation of the Governmental Funds Balance Sheet to the Statement of Net Position.....	17
Statement of Revenues, Expenditures and Changes in Fund Balances.....	18
Reconciliation of the Statement of Revenues, Expenditures and Changes in Fund Balances of the Governmental Funds to the Statement of Activities.....	20
Statement of Revenues, Expenditures, and Changes in Fund Balances - Budget and Actual	
General Fund.....	21
Roads Fund.....	26
474 Fire Protection District Fund.....	27
Tri Payback Fund.....	28
USDA Bond Fund.....	29
Virginia City Tourism Commission Fund.....	30
Proprietary Funds	
Statement of Net Position.....	31
Statement of Revenues, Expenditures and Changes in Fund Balances.....	32
Statement of Cash Flows.....	33
Fiduciary Funds	
Statement of Net Position and change in net position.....	34
Notes to Financial Statements.....	35
Supplementary Information:	
Combining Balance Sheet - Nonmajor Governmental Funds.....	61
Combining Statement of Revenues, Expenditures and Changes in Fund Balances - Nonmajor Governmental Funds.....	64
Statement of Revenues, Expenditures and Changes in Fund Balance Budget and Actual	
Special Revenue Funds:	
Equipment Acquisition.....	67
Justice Court.....	68
Drug Court.....	69
Indigent Medical.....	70
Park Tax.....	71
Mutual Aid.....	72
Emergency Mitigation.....	73
Indigent Accident.....	74
Technology.....	75
Federal/State Grant.....	76
Fire Emergency.....	77
Stabilization.....	78
Genetic Marker Testing.....	79
Piper's Opera House.....	80
Fire Grant.....	81

**STOREY COUNTY, NEVADA**  
**TABLE OF CONTENTS**  
**JUNE 30, 2022**

<b>FINANCIAL SECTION (cont'd.)</b>	Page
Capital Projects Funds	
Capital Projects.....	82
Infrastructure.....	83
Virginia City Rail.....	84
Fire .....	85
Enterprise Funds:	
Water System	
Statement of Revenue and Expense.....	86
Statement of Cash Flows.....	87
Virginia Divide Sewer Improvement District	
Statement of Revenue and Expense.....	88
Statement of Cash Flows.....	89
Schedule of Changes in the Total OPEB Liability and Related Ratios .....	90
Schedule of County's Share of Net Pension Liability-Public Retirement System of Nevada.....	91
Schedule of County's Contributions-Public Employees' Retirement System of Nevada.....	92
 <b>COMPLIANCE SECTION</b>	
Report on Compliance and on Internal Control over Financial Reporting and on Compliance and Other Matters Based on an Audit of Financial Statements Performed in Accordance with Governmental Auditing Standards.....	93
Schedule of Findings and Responses.....	99



## **INDEPENDENT AUDITOR'S REPORT**

To the Honorable Board of County Commissioners  
Storey County, Nevada

### **Report on the Financial Statements**

We have audited the accompanying financial statements of the governmental activities, the business-type activities, each major fund, and the aggregate remaining fund information of Storey County, Nevada as of and for the year ended June 30, 2022, and the related notes to the financial statements, which collectively comprise the Storey County, Nevada's basic financial statements as listed in the table of contents.

In our opinion, the financial statements referred to above present fairly, in all material respects, the respective financial position of the governmental activities, business-type activities, each major fund, and the aggregate remaining fund information of Storey County, Nevada, as of June 30, 2022, and the respective changes in financial position, and where applicable, cash flows, thereof and the respective budgetary comparisons for the General Fund and the Regional Streets and Highway Fund for the year then ended in conformity with accounting principles generally accepted in the United States of America.

### ***Basis for Opinions on Each Major Federal Program***

We conducted our audit in accordance with auditing standards generally accepted in the United States of America and the standards applicable to financial audits contained in Government Auditing Standards, issued by the Comptroller General of the United States. Our responsibilities under those standards are further described in the Auditor's Responsibilities for the Audit of the Financial Statements section of our report. We are required to be independent of Storey County, Nevada and to meet our other ethical responsibilities, in accordance with the relevant ethical requirements relating to our audit. We believe that the audit evidence we have obtained is sufficient and appropriate to provide a basis for our audit opinions.

### **Responsibilities of Management for the Financial Statements**

Management is responsible for the preparation and fair presentation of these financial statements in accordance with accounting principles generally accepted in the United States of America; and for the design, implementation, and maintenance of internal control relevant to the preparation and fair presentation of financial statements that are free from material misstatement, whether due to fraud or error.

In preparing the financial statements, management is required to evaluate whether there are conditions or events, considered in the aggregate, that raise substantial doubt about the Storey County, Nevada ability to continue as a going concern for twelve months beyond the financial statement date, including any currently known information that may raise substantial doubt shortly thereafter.

### ***Auditor's Responsibilities for the Audit of the Financial Statements***

Our objectives are to obtain reasonable assurance about whether the financial statements as a whole are free from material misstatement, whether due to fraud or error, and to issue an auditor's report that includes our opinions. Reasonable assurance is a high level of assurance but is not absolute assurance and therefore is not a guarantee that an audit conducted in accordance with generally accepted auditing standards and *Government Auditing Standards* will always detect a material misstatement when it exists. The risk of not detecting a material misstatement resulting from fraud is higher than for one resulting from error, as fraud may involve collusion, forgery, intentional omissions, misrepresentations, or the override of internal control. Misstatements are considered material if there is a substantial likelihood that, individually or in the aggregate, they would influence the judgment made by a reasonable user based on the financial statements.



In performing an audit in accordance with generally accepted auditing standards and *Government Auditing Standards*, we:

- Exercise professional judgment and maintain professional skepticism throughout the audit.
- Identify and assess the risks of material misstatement of the financial statements, whether due to fraud or error, and design and perform audit procedures responsive to those risks. Such procedures include examining, on a test basis, evidence regarding the amounts and disclosures in the financial statements.
- Obtain an understanding of internal control relevant to the audit in order to design audit procedures that are appropriate in the circumstances, but not for the purpose of expressing an opinion on the effectiveness of the Storey County, Nevada's internal control. Accordingly, no such opinion is expressed.
- Evaluate the appropriateness of accounting policies used and the reasonableness of significant accounting estimates made by management, as well as evaluate the overall presentation of the financial statements.
- Conclude whether, in our judgment, there are conditions or events, considered in the aggregate, that raise substantial doubt about the Storey County, Nevada's ability to continue as a going concern for a reasonable period of time.

Exercise professional judgment and maintain professional skepticism throughout the audit.

- Identify and assess the risks of material misstatement of the financial statements, whether due to fraud or error, and design and perform audit procedures responsive to those risks. Such procedures include examining, on a test basis, evidence regarding the amounts and disclosures in the financial statements.
- Obtain an understanding of internal control relevant to the audit in order to design audit procedures that are appropriate in the circumstances, but not for the purpose of expressing an opinion on the effectiveness of the Storey County, Nevada's internal control. Accordingly, no such opinion is expressed.
- Evaluate the appropriateness of accounting policies used and the reasonableness of significant accounting estimates made by management, as well as evaluate the overall presentation of the financial statements.
- Conclude whether, in our judgment, there are conditions or events, considered in the aggregate, that raise substantial doubt about the Storey County, Nevada's ability to continue as a going concern for a reasonable period of time.

We are required to communicate with those charged with governance regarding, among other matters, the planned scope and timing of the audit, significant audit findings, and certain internal control-related matters that we identified during the audit.

#### ***Required Supplemental Information***

Accounting principles generally accepted in the United States of America require that the management's discussion and analysis, on pages 4 through 10 and the schedules of other post-employment benefits and the County's proportionate share of the net pension liability and defined benefit plan contributions on pages 90-92 be presented to supplement the basic financial statements. Such information is the responsibility of management, and although not a part of the basic financial statements, is required by Governmental Accounting Standards Board, who considers it to be an essential part of financial reporting for placing the basic financial statements in an appropriated operational, economic, or historical context. We have applied certain limited procedures to the required supplementary information in accordance with auditing standards generally accepted in the United States of America, which consisted of inquiries of management about the methods of preparing the information and comparing the information for consistency with management's responses to our inquiries, the basic financial statements, and other knowledge we obtained during our audit of the basic financial statements. We do not express an opinion or provide any assurance on the information because the limited procedures do not provide us with sufficient evidence to express an opinion or provide any assurance.

***Supplementary Information***

Our audit was conducted for the purpose of forming opinions on the financial statements that collectively comprise the Storey County, Nevada's basic financial statements. The budgetary comparison financial statements for the major capital projects fund, combining and individual nonmajor fund financial statements, and schedule of expenditures of federal awards, as required by Title 2 U.S. Code of Federal Regulations Part 200, Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards, are presented for purposes of additional analysis and are not a required part of the basic financial statements. Such information is the responsibility of management and was derived from and relates directly to the underlying accounting and other records used to prepare the basic financial statements. The information has been subjected to the auditing procedures applied in the audit of the basic financial statements and certain additional procedures, including comparing and reconciling such information directly to the underlying accounting and other records used to prepare the basic financial statements or to the basic financial statements themselves, and other additional procedures in accordance with auditing standards generally accepted in the United States of America. In our opinion, the combining and individual nonmajor fund financial statements and the schedule of expenditures of federal awards are fairly stated, in all material respects, in relation to the basic financial statements as a whole.

**Other Reporting Required by Government Auditing Standards**

In accordance with Government Auditing Standards, we have also issued a report dated November 30, 2022, on our consideration of Storey County, Nevada's internal control over financial reporting and on our tests of its compliance with certain provisions of laws, regulations, contracts, and grant agreements and other matters. The purpose of that report is to describe the scope of our testing of internal control over financial reporting and compliance and the results of that testing, and not to provide an opinion on the effectiveness of Storey County, Nevada's internal control over financial reporting or on compliance. That report is an integral part of an audit performed in accordance with Government Auditing Standards in considering Storey County, Nevada's internal control over financial reporting and compliance.



Reno, NV  
December 20, 2022

**COUNTY OF STOREY, STATE OF NEVADA  
MANAGEMENT'S DISCUSSION AND ANALYSIS**

---

As management of Storey County, State of Nevada, we offer readers of Storey County's financial statements this overview and analysis of Storey County for the fiscal year ended June 30, 2022.

**FINANCIAL HIGHLIGHTS**

- The government wide net position at the close of the 2022 fiscal year was \$45,157,984 which was a increase from 2021 in the amount of \$14,202,289. This represents \$26,882,029 governmental activities and \$18,275,955 in Business type activities
- The assets of Storey County exceeded its liabilities by \$47,630,037
- The primary revenue sources for the County for governmental activities were \$20,347,868 of property taxes, \$8,925,398 of consolidated taxes, and \$1,168,182 of capital contributions and grants.
- The government wide expenses were \$30,479,628. The greatest expenses were in the General government function \$11,321,937 and the Public Safety function in the amount of \$14,663,332.
- At the close of the fiscal year the general fund balance was \$28,468,540 an increase from the previous year in the amount of \$5,564,494. Combined governmental funds closed fiscal year 2022 with combined balance of \$53,208,353.
- Storey County's bonded debt at June 30, 2022 was \$10,992,118 which was \$9,595,293 in revenue bonds of the County's Enterprise Funds, and \$1,396,825 bond of the Storey County Fire Protection District.

**OVERVIEW OF THE FINANCIAL STATEMENTS**

This discussion and analysis are intended to serve as an introduction to Storey County's basic financial statements. These basic financial statements include (1) government-wide financial statements (2) fund financial statements, and (3) notes to the financial statements. This report also contains supplementary information in addition to the basic financial statements themselves.

**Government-Wide Financial Statements.** The government-wide statements are designed to provide readers with a broad overview of Storey County's finances in a manner similar to private-sector business.

The Statement of Net Position is information on all of Storey County's assets and liabilities, with the difference between the two reported as net assets. Over time, increases and decreases in net assets may serve as an indicator to show if the financial position of Storey County is improving or declining.

The Statement of Activities notes information as to how the government's net assets changed during the last fiscal year. All changes in net assets are reported as soon as the event causing the change occurs, regardless of the timing of related cash flows. Revenues and expenses are reported for some items that result in cash flows in future periods, (e.g., uncollected taxes, earned and unused vacation and sick leave).

The government-wide financial statements distinguish functions of Storey County that are mainly supported by taxes and intergovernmental revenues (government activities) from other functions that recover their costs through user fees and charges (business type activities). The governmental activities of Storey County included general government, public safety, roads and streets, judicial and, culture and recreation, and community support. The business activities (enterprise funds) are the water and sewer.

The government-wide financial statements can be found in this report on pages 12 and 13.

**Fund Financial Statements.** Funds are groupings of related accounts and is used to maintain control over resources segregated for specific activities or purpose. Storey County uses fund accounting to ensure compliance with state and federal finance related requirements. The fund types of Storey County are as follows: governmental; enterprise; and fiduciary.

**COUNTY OF STOREY, STATE OF NEVADA**  
**MANAGEMENT'S DISCUSSION AND ANALYSIS**

---

**Governmental Funds.** Governmental funds are used to account for the functions reported as governmental activities, in the government-wide financial statements. Unlike the Government-Wide Financial Statements, governmental fund statements focus on near term inflows of expendable resources and on balances of expendable resources at the end of the fiscal year. This information helps with decisions as to near term financing needs.

The focus of governmental funds is narrower than the government-wide financial statements. It is useful to compare the information for governmental funds with similar information for governmental activities in government-wide financial statements. By doing so, readers will better understand the long-term impact of governments near-term financing decisions. The governmental fund Balance Sheet and governmental fund Statement of Revenues, Expenditures, and Changes in Fund Balances allow this comparison between governmental funds and activities.

Storey County has twenty-three governmental funds. Financial information is stated separately in the governmental fund Balance Sheet and in the governmental Statement of Revenues, Expenditures, and Changes in Fund Balances, for the general fund and five other funds considered major funds. Data from the other seventeen governmental funds are combined. Individual fund data for non-major governmental funds are reported in combining statements in this report.

Storey County adopts an annual budget for each of its governmental and propriety funds. A budgetary comparison statement has been provided for all funds to show compliance with the budget.

The governmental funds financial statements can be found in this report on pages 15 through 30.

**Proprietary funds.** Storey County operates two enterprise (proprietary) funds; the Water Fund and the Sewer Fund which supply services in Virginia City and Gold Hill. These funds are reported as business type activities, reported in the government-wide financial statements..

Enterprise funds are presented on pages 32 through 33.

**Fiduciary funds.** Fiduciary funds are used to account for resources held for other entities. Fiduciary funds are not reflected in the government-wide financial statements as the resources of these funds are not available to support Storey County. The cash basis of accounting is used for fiduciary funds

Fiduciary fund financial statements can be found in this report on page 34.

**Notes to the financial statements.** The notes in this report provide additional information necessary for a full understanding of the information provided in the government-wide financial statements. The notes can be found on pages 35 through 59.

**Other information.** In addition to the basic financial statements and accompanying notes, this report also presents certain supplementary information, including budget to actual comparison data. These schedules test compliance with budgetary constraints and management directive to enhance accountability at the fund and function level. This information may be found on pages

**COUNTY OF STOREY, STATE OF NEVADA  
MANAGEMENT'S DISCUSSION AND ANALYSIS**

**GOVERNMENT-WIDE FINANCIAL ANALYSIS**

A significant portion of the County's net position, \$38,299,000, reflects the amount invested in capital assets (e.g. land and easements, structures and improvements, infrastructure, and equipment), less any related debt used to acquire those assets. The County uses these capital assets to provide services to citizens; consequently, these assets are not available for future spending. Although the County's investment in capital assets is reported net of related debt, it should be noted that the resources needed to repay this debt must be provided from other sources, since the capital assets themselves cannot be used to liquidate these liabilities.

The restricted portion of the County's net position, \$402,000, represents resources that are subject to external restrictions (statutory, bond covenants or granting agency) on how they may be used.

The unrestricted portion of the County's net position due to governmental activities is 6,457,000 primarily due to the classification of long-term pension liabilities to the unrestricted category. These liabilities are required by new accounting standards in order to communicate to potential lenders and the public the potential liability the County bears for future pension expense. These liabilities accumulate over decades as part of the County's employment agreements and the timing for their translation into current year expense is not subject to precise projection.

\*For more detailed information, see the government-wide Statements of Net Position and Notes to the Financial Statements.

**STOREY COUNTY, NEVADA  
NET POSITION**

	Governmental Activities June 30, 2022	Business Type Activities June 30, 2022	Total June 30, 2022	Total June 30, 2021
Current and Other Assets	\$ 58,809,000	\$ 1,838,000	\$ 60,647,000	\$ 51,138,000
Capital Assets	54,768,000	26,570,000	81,338,000	83,315,000
Total Assets	<u>\$ 113,577,000</u>	<u>\$ 28,408,000</u>	<u>\$ 141,985,000</u>	<u>\$ 134,453,000</u>
Deferred Outflows	<u>\$ 18,368,000</u>	<u>\$ 263,000</u>	<u>\$ 18,631,000</u>	<u>\$ 13,732,000</u>
Long Term Liabilities				
Outstanding	\$ 80,308,000	\$ 9,966,000	\$ 90,274,000	\$ 100,299,000
Current Liabilities	3,980,000	111,000	4,091,000	6,359,000
Total Liabilities	<u>\$ 84,288,000</u>	<u>\$ 10,077,000</u>	<u>\$ 94,365,000</u>	<u>\$ 106,658,000</u>
Deferred Inflows	<u>\$ 20,775,000</u>	<u>\$ 318,000</u>	<u>\$ 21,093,000</u>	<u>\$ 10,571,000</u>
Net Position				
Invested in Capital				
Assets, Net of Related Debt	\$ 21,324,000	\$ 16,975,000	\$ 38,299,000	\$ 32,799,000
Restricted	143,000	259,000	402,000	402,000
Unrestricted	5,415,000	1,042,000	6,457,000	(2,245,000)
Total Net Position	<u>\$ 26,882,000</u>	<u>\$ 18,276,000</u>	<u>\$ 45,158,000</u>	<u>\$ 30,956,000</u>

**COUNTY OF STOREY, STATE OF NEVADA  
MANAGEMENT'S DISCUSSION AND ANALYSIS**

STOREY COUNTY, NEVADA  
CHANGES IN NET POSITION

At the end of 2022 fiscal year Storey County reports a positive balance in net position for both the government activities and business-type activities. This is true for the prior fiscal year.

Storey County's overall net position increased \$14,202,000 compared to a \$2,682,000 increase in the prior year. The governmental activities net position increased by \$14,295,000 and the Business-type activities decreased \$93,000. The details of the changes are noted in the following table:

	Governmental Activities <u>June 30, 2022</u>	Business Type Activities <u>June 30, 2022</u>	Total <u>June 30, 2022</u>	Total <u>June 30, 2021</u>
<b>REVENUES:</b>				
<b>Program Revenues:</b>				
Charges for Services	\$ 11,122,000	\$ 1,105,000	\$ 12,227,000	\$ 6,927,000
Operating Grants and Contributions	388,000	-	388,000	961,000
Capital Grants and Contributions	-	1,168,000	1,168,000	954,000
<b>General Revenues:</b>				
Taxes	20,348,000	-	20,348,000	19,142,000
Intergovernmental	8,925,000	-	8,925,000	6,127,000
Interest Earnings	(1,135,000)	-	(1,135,000)	(13,000)
Bond Proceeds	-	-	-	-
Other	<u>2,411,000</u>	<u>121,000</u>	<u>2,532,000</u>	<u>1,704,000</u>
<b>Total Revenues</b>	<b>42,059,000</b>	<b>2,394,000</b>	<b>44,453,000</b>	<b>35,802,000</b>
<b>EXPENSES:</b>				
General Government	14,846,000	-	14,846,000	15,547,000
Public Safety	8,823,000	-	8,823,000	11,861,000
Judicial	1,476,000	-	1,476,000	399,000
Health and Welfare	290,000	-	290,000	259,000
Culture and Recreation	411,000	-	411,000	402,000
Community Support	1,316,000	-	1,316,000	1,325,000
Highways and Streets	602,000	-	602,000	1,870,000
Intergovernmental	-	-	-	-
Water and Sewer	<u>-</u>	<u>2,487,000</u>	<u>2,487,000</u>	<u>1,457,000</u>
<b>Total Expenses</b>	<b>27,764,000</b>	<b>2,487,000</b>	<b>30,251,000</b>	<b>33,120,000</b>
<b>Changes in Net Position</b>	<b>14,295,000</b>	<b>(93,000)</b>	<b>14,202,000</b>	<b>2,682,000</b>
<b>Net Position - July 1</b>	<b><u>12,587,000</u></b>	<b><u>18,369,000</u></b>	<b><u>30,956,000</u></b>	<b><u>28,274,000</u></b>
<b>Net Position - June 30</b>	<b><u>\$ 26,882,000</u></b>	<b><u>\$ 18,276,000</u></b>	<b><u>\$ 45,158,000</u></b>	<b><u>\$ 30,956,000</u></b>

COUNTY OF STOREY, STATE OF NEVADA  
MANAGEMENT'S DISCUSSION AND ANALYSIS

---

**FINANCIAL ANALYSIS OF THE GOVERNMENT FUNDS.** As noted earlier, Storey County uses fund accounting to ensure and demonstrate compliance with finance related legal requirements.

At the end of the fiscal year, Storey County's governmental funds reported a combined ending fund balance of \$53,208,353, an increase of \$10,497,652 from the prior year.

**General Fund.** The General Fund is the chief operating fund of the County. At the end of the current fiscal year, the fund balance was \$28,468,540 and increase of \$5,5564,494 from the prior year.

Expenditures increase was \$655,869 : General government expenditures increased by \$474,863 Judicial expenditures increased by \$188,827 , and Public Safety decreased by \$22,658. All increases are primarily due to increases in salary and benefit increases in various departments and union organizations.

**Road fund.** The Road Fund has an ending fund balance at the close of the current year of \$1,721,993 a decrease of \$930,110. Revenues increased 42% during the year due to the gas and SCCRT tax. Expense decreased 53% primarily due to a decrease in capital road projects.

**474 Fire Protection District Fund.** The Fire Protection District Fund has a fund balance at the end of the fiscal year of \$4,673,622. This is an increase of \$2,548,950. Revenues increased 47% primarily due to Tesla payments, Ad Valorem and Intergovernmental Funding, and Expenses increased 10% primarily due to increases in salaries and benefits

**Budgetary Highlights Fiscal Year ending June 30, 2022.**

The budget statements reflect a comparison budgeted revenues and expenditures to the actual for the year ending June 30, 2022. The budget statements were prepared from the final budget as filed with the Nevada Department of Taxation. Augmentations and line item transfers were made during the year as approved by the Storey County Commissioners.

The General Fund revenues were more than expectations by \$5,685,568 leaving a fund balance of \$28,468,540 General Fund information can be found on pages 21 through 25.

**Capital Assets.** Storey County's investment in capital assets for its governmental and business type activities as of June 30, 2022 amount to \$81,338,000 (net accumulated depreciation). This investment in capital assets includes land, buildings, and Water/Sewer systems, improvements, machinery and equipment, park facilities, roads, and bridges.

STOREY COUNTY NEVADA  
CAPITAL ASSETS  
JUNE 30, 2022

	Governmental Activities <u>June 30, 2022</u>	Business Type Activities <u>June 30, 2022</u>	Total <u>June 30, 2022</u>
Land	\$ 811,000	\$ -	\$ 811,000
Antique Furniture	75,000	-	75,000
Construction in Process	2,931,000	14,793,000	17,724,000
Leased assets	56,000	-	56,000
Buildings and Improvements	8,888,000	-	8,888,000
Improvements other than Buildings	34,905,000	-	34,905,000
Machinery and Equipment	7,102,000	-	7,102,000
Sewer and Water systems	-	11,777,000	11,777,000
<b>Total</b>	<b>\$ 54,768,000</b>	<b>\$ 26,570,000</b>	<b>\$ 81,338,000</b>

**COUNTY OF STOREY, STATE OF NEVADA  
MANAGEMENT'S DISCUSSION AND ANALYSIS**

---

**Long Term Debt.** The following table represents the long term debt of the county for June 30, 2022 and June 30, 2021:

STOREY COUNTY NEVADA  
LONG TERM DEBT  
JUNE 30, 2022 AND 2021

	Balance <u>June 30, 2022</u>	Balance <u>June 30, 2021</u>
<u>Governmental</u>		
Virginia City Rail Bond-Series 2010A	-	448,000
Virginia City Rail Bond-Series 2010B	-	443,000
Storey County Fire District USDA Loan	1,396,825	1,485,008
Leases payable	53,750	71,976
Compensated Absences	779,093	766,643
TRI-Construction repayment	40,842,347	38,342,347
 <u>Business Type Activities</u>		
Water Revenue Bonds	3,054,906	3,118,716
Sewer Revenue Bonds	6,540,387	6,678,842

**Economic Factors and Next Year's Budget**

The County reviews and includes a variety of economic related statistics in the development and monitoring the operating and capital budgets. Long and short-term plans are annually reviewed and updated to aid in the development the County's budgets, including a 5-10 year plan for the County's Capital Improvement Projects. The assumptions used in the plans are reviewed by the County Commissioners as background for decisions regarding the revenue projections and cost allocations.

The County's practice of budgeting conservatively on revenues and liberally on expenditures has resulted in a strong, fiscally responsible government. Storey County Board of Commissioners approved the 2020-2021 in May and this was approved by Nevada Dept of Taxation. The financial projections continue to include the growth of the Tahoe Regional Industrial Park which has a substantial impact on both the revenue and expenditures of the County. TRI has a significant impact on the financial stability of Storey County, however with current abatements the expenditures continue to rise without equal financial support of the area.

In FY23 Storey County will enter into negotiations with the Sheriff's union and the Fire District will enter into negotiations with the Fire Fighter Association #4227.

The County is anxiously waiting on finalization on several grants from the Federal government. If approved these grants will help fund several projects in the County's CIP, including, the Lockwood Community Center, the Lockwood Sheriff substation, the Virginia City Fire Station, upgrades to the Virginia City fairgrounds, and upgrades to the Virginia City Justice Center parking lot.



**COUNTY OF STOREY, STATE OF NEVADA**  
**MANAGEMENT'S DISCUSSION AND ANALYSIS**

---

The 2022-2023 Capital Improvement Plan include:

Water system upgrades: B Street water line, water tank rehabilitation

Continuing necessary internet infrastructure County wide, Radio/Cell towers, and various road projects  
County wide

New Lockwood Senior/Community Ctr- Currently in planning stages and expected to break ground sometime  
in the next fiscal year

Mark Twain Community Center outdoor lighting and new message board

Upgrades to the McCarren Center County offices

New siding on Fire Station 72

**Request for Information**

This financial report is designed to provide a general overview of Storey County's finances for all those with an interest in the government's finances. Questions concerning any of the information provided in this report or requests for additional financial information should be addressed to Storey County Comptroller's Office, 10 South B Street, Virginia City, Nevada 89440.

THIS PAGE INTENTIONALLY LEFT BLANK

**STOREY COUNTY, NEVADA**  
**STATEMENT OF NET POSITION**  
**JUNE 30, 2022**

	PRIMARY GOVERNMENT			COMPONENT
	GOVERNMENTAL ACTIVITIES	BUSINESS-TYPE ACTIVITIES	TOTAL	UNIT TRI GID
<b>ASSETS</b>				
Cash and investments	\$ 54,612,581	\$ 1,738,246	\$ 56,350,827	\$ 5,352,129
Accounts receivables (net allowance)	2,364,178	98,885	2,463,063	454,146
Taxes receivable	332,057	-	332,057	-
Insurance receivable	-	-	-	723,670
Prepaid expenses	52,078	-	52,078	96,519
Inventory	11,809	-	11,809	-
Lease receivable	1,121,580	-	1,121,580	301,068
Due from V&T Railroad	314,669	-	314,669	-
Capital assets - nondepreciable				-
Land	810,921	-	810,921	503,231
Water rights	-	-	-	52,414,363
Antique furniture	75,000	-	75,000	-
Construction in progress	2,930,806	14,793,141	17,723,947	-
Capital assets - net of accumulated depreciation				-
Leased assets	56,141	-	56,141	-
Buildings and improvements	8,887,817	-	8,887,817	-
Improvements other than buildings	34,905,489	-	34,905,489	-
Utility system	-	11,776,958	11,776,958	56,332,094
Machinery and equipment	7,102,093	-	7,102,093	-
<b>Total Assets</b>	<b>\$ 113,577,219</b>	<b>\$ 28,407,230</b>	<b>\$ 141,984,449</b>	<b>\$ 116,177,220</b>
<b>DEFERRED OUTFLOWS OF RESOURCES</b>				
Deferred outflows-OPEB	\$ 8,119,144	\$ -	\$ 8,119,144	\$ -
Deferred outflows-pension	10,248,977	262,794	10,511,771	960,529
<b>Total Deferred Outflows of Resources</b>	<b>\$ 18,368,121</b>	<b>\$ 262,794</b>	<b>\$ 18,630,915</b>	<b>\$ 960,529</b>
<b>LIABILITIES</b>				
Accounts payable and other current liabilities	\$ 3,980,433	\$ 110,802	\$ 4,091,235	\$ 328,465
Non-current liabilities				
Bonds, Lease, Notes payable - due within one year	109,224	-	109,224	-
- due in more than one year	33,278,934	9,595,294	42,874,228	-
Compensated absences - due in more than one year	778,272	-	778,272	-
Net OPEB obligation	31,698,789	-	31,698,789	-
Net pension liability	14,442,347	370,317	14,812,664	511,184
<b>Total Liabilities</b>	<b>\$ 84,287,999</b>	<b>\$ 10,076,413</b>	<b>\$ 94,364,412</b>	<b>\$ 839,649</b>
<b>DEFERRED INFLOWS OF RESOURCES</b>				
Deferred inflows-lease receivable	\$ 1,092,030	\$ -	\$ 1,092,030	\$ 295,787
Deferred inflows-OPEB	7,294,689	-	7,294,689	-
Deferred inflows-pension	12,388,593	317,656	12,706,249	420,708
<b>Total Deferred Inflows of Resources</b>	<b>\$ 20,775,312</b>	<b>\$ 317,656</b>	<b>\$ 21,092,968</b>	<b>\$ 716,495</b>
<b>NET POSITION</b>				
Restricted reserve	\$ 142,640	\$ 259,034	\$ 401,674	-
Invested in capital assets - net of related debt	21,323,968	16,974,805	38,298,773	109,249,688
Unrestricted	5,415,421	1,042,116	6,457,537	6,331,917
<b>Total Net Position</b>	<b>\$ 26,882,029</b>	<b>\$ 18,275,955</b>	<b>\$ 45,157,984</b>	<b>\$ 115,581,605</b>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**STATEMENT OF ACTIVITIES**  
**FOR THE YEAR ENDED JUNE 30, 2022**

<u>FUNCTIONS/PROGRAMS</u>	PROGRAM REVENUES			
	EXPENSES	CHARGES FOR SERVICES	OPERATING GRANTS AND CONTRIBUTIONS	CAPITAL GRANTS AND CONTRIBUTIONS
Primary government:				
Governmental activities:				
General government	\$ 14,845,380	\$ 7,978,835	\$ -	\$ -
Public safety	8,822,900	2,824,427	387,624	-
Judicial	1,476,334	58,331	-	-
Health and welfare	289,878	-	-	-
Culture and recreation	411,367	23,329	-	-
Community support	1,316,414	-	-	-
Highways and streets	601,638	237,752	-	-
Intergovernmental	-	-	-	-
Total Governmental Activities	27,763,911	11,122,674	387,624	-
Business type activities:				
Water	552,903	652,958	-	354,939
Sewer	821,843	452,150	-	813,243
Total Business-Type Activities	1,374,746	1,105,108	-	1,168,182
Total Primary Government	\$ 29,138,657	\$ 12,227,782	\$ 387,624	\$ 1,168,182
Component Unit:				
TRI General Improvement District	\$ 3,469,224	\$ 4,321,418	\$ -	\$ -
Total Component Unit	\$ 3,469,224	\$ 4,321,418	\$ -	\$ -

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA  
STATEMENT OF ACTIVITIES  
FOR THE YEAR ENDED JUNE 30, 2022**

FUNCTIONS/PROGRAMS	NET (EXPENSE)REVENUE AND CHANGES IN NET POSITION			COMPONET UNIT
	PRIMARY GOVERNMENT			
	BUSINESS			
	GOVERNMENTAL ACTIVITIES	TYPE ACTIVITIES	TOTAL	TRI GID
Primary government:				
Governmental activities:				
General government	\$ (6,866,545)	\$ -	\$ (6,866,545)	
Public safety	(5,610,849)	-	(5,610,849)	
Judicial	(1,418,003)	-	(1,418,003)	
Health and welfare	(289,878)	-	(289,878)	
Culture and recreation	(388,038)	-	(388,038)	
Community support	(1,316,414)	-	(1,316,414)	
Highways and streets	(363,886)	-	(363,886)	
Intergovernmental	-	-	-	
Total Governmental Activities	<u>(16,253,613)</u>	<u>-</u>	<u>(16,253,613)</u>	
Business type activities:				
Water	-	(230,026)	(230,026)	
Sewer	-	(1,151,976)	(1,151,976)	
Total Business-Type Activities	<u>-</u>	<u>(1,382,002)</u>	<u>(1,382,002)</u>	
Total Primary Government	<u>(16,253,613)</u>	<u>(1,382,002)</u>	<u>(17,635,615)</u>	
Component Unit:				
TRI General Improvement District				\$ 852,194
Total Component Unit				<u>852,194</u>
General revenues:				
Property taxes	20,347,868	-	20,347,868	-
Various state collected pass-through revenues	8,925,398	-	8,925,398	-
Investment earnings	(1,135,311)	103,238	(1,032,073)	5,800
Bond proceeds	-	-	-	-
Miscellaneous revenue	2,411,129	17,400	2,428,529	320,174
Capital contributions and grants	-	1,168,182	1,168,182	205,740
Total General Revenues	<u>30,549,084</u>	<u>1,288,820</u>	<u>31,837,904</u>	<u>531,714</u>
Change in Net Position	14,295,471	(93,182)	14,202,289	1,383,908
Net Position, July 1	<u>12,586,558</u>	<u>18,369,137</u>	<u>30,955,695</u>	<u>114,197,697</u>
Net Position, June 30	<u>\$ 26,882,029</u>	<u>\$ 18,275,955</u>	<u>\$ 45,157,984</u>	<u>\$ 115,581,605</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA  
GOVERNMENTAL FUNDS  
BALANCE SHEET  
JUNE 30, 2022**

	GENERAL	ROAD FUND	474 FIRE PROTECTION DISTRICT FUND	TRI-PAYBACK FUND	USDA BOND FUND
<b>ASSETS</b>					
Cash	\$ 30,199,375	\$ 1,533,396	\$ 4,457,413	\$ 1,487,278	\$ 29,726
Accounts receivable (net allowance)	736,719	223,834	883,167	85,124	-
Taxes receivable	247,576	-	76,097	-	-
Prepaid expenses	11,078	-	-	-	-
Lease receivable	1,121,580	-	-	-	-
Due from V&T road	314,669	-	-	-	-
Inventory	-	-	-	-	-
<b>Total Assets</b>	<u>\$ 32,630,997</u>	<u>\$ 1,757,230</u>	<u>\$ 5,416,677</u>	<u>\$ 1,572,402</u>	<u>\$ 29,726</u>
<b>LIABILITIES AND FUND BALANCES</b>					
<b>Liabilities</b>					
Accounts payable	\$ 887,377	\$ 19,425	\$ 51,828	\$ -	\$ -
Accrued expenses and deposits	337,305	15,812	210,404	-	-
Unearned income	-	-	-	-	-
Account payable - Tesla	1,799,987	-	-	-	-
<b>Total Liabilities</b>	<u>3,024,669</u>	<u>35,237</u>	<u>262,232</u>	<u>-</u>	<u>-</u>
<b>DEFERRED INFLOWS OF RESOURCES</b>					
Unavailable resources property taxes	45,758	-	480,823	-	-
Deferred lease income	1,092,030	-	-	-	-
	<u>1,137,788</u>	<u>-</u>	<u>480,823</u>	<u>-</u>	<u>-</u>
<b>FUND BALANCES</b>					
Nonspendable	11,078	-	-	-	-
Reserved - debt service	-	-	142,640	-	-
Unassigned reported in:					
General fund	28,457,462	-	-	-	-
Capital projects funds	-	-	-	-	-
Special revenue funds	-	1,721,993	4,530,982	1,572,402	29,726
<b>Total Fund Balances</b>	<u>28,468,540</u>	<u>1,721,993</u>	<u>4,673,622</u>	<u>1,572,402</u>	<u>29,726</u>
<b>Total Liabilities, Deferred Inflows of Resources and Fund Balances</b>	<u>\$ 32,630,997</u>	<u>\$ 1,757,230</u>	<u>\$ 5,416,677</u>	<u>\$ 1,572,402</u>	<u>\$ 29,726</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA  
BALANCE SHEET  
GOVERNMENTAL FUNDS  
JUNE 30, 2022**

	<u>VCTC FUND</u>	<u>OTHER GOVERNMENTAL FUNDS</u>	<u>TOTAL GOVERNMENTAL FUNDS</u>
<b><u>ASSETS</u></b>			
Cash	\$ 1,288,722	\$ 15,616,671	\$ 54,612,581
Accounts receivable (net allowance)	145,021	290,313	2,364,178
Taxes receivable	-	8,384	332,057
Prepaid expenses	40,000	1,000	52,078
Lease receivable	-	-	1,121,580
Due from V&T road	-	-	314,669
Inventory	11,809	-	11,809
Total Assets	\$ 1,485,552	\$ 15,916,368	\$ 58,808,952
 <b>LIABILITIES AND FUND BALANCES</b>			
<b><u>Liabilities</u></b>			
Accounts payable	\$ 43,833	\$ 569,024	\$ 1,571,487
Acerued expenses and deposits	13,528	-	577,049
Unearned income	9,000	22,910	31,910
Account payable - Tesla	-	-	1,799,987
Total Liabilities	66,361	591,934	3,980,433
 <b>DEFERRED INFLOWS OF RESOURCES</b>			
Unavailable resources property taxes	-	1,555	528,136
Deferred lease income	-	-	1,092,030
	-	1,555	1,620,166
 <b><u>FUND BALANCES</u></b>			
Nonspendable	51,809	-	62,887
Reserved - debt service	-	-	142,640
Unassigned reported in:			
General fund	1,367,382	-	29,824,844
Capital projects funds	-	7,903,513	7,903,513
Special revenue funds	-	7,419,366	15,274,469
Total Fund Balances	1,419,191	15,322,879	53,208,353
Total Liabilities, Deferred Inflows of Resources and Fund Balances	\$ 1,485,552	\$ 15,916,368	\$ 58,808,952

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
RECONCILIATION OF GOVERNMENTAL FUNDS BALANCE SHEET  
TO THE STATEMENT OF NET POSITION  
JUNE 30, 2022

Total Fund Balance - government funds - page 16	\$ 53,208,353
Amounts reported for governmental activities in the statement of net assets are different because:	
Capital assets net of related depreciation are not reported in the Governmental Funds financial statements because they are not current financial resources, but they are reported in the statement of net assets	54,768,267
Deferred outflows of resources for OPEB	8,119,144
Deferred outflows of resources for pensions	10,248,977
Property taxes receivable that are not available to pay current period expenditures and therefore are reported as unearned in the funds	528,136
Long term liabilities are not due and payable in the current period and therefore are not reported in the funds.	(33,388,158)
Pension liabilities are not due and payable in the current period and therefore not reported in funds	(46,141,136)
Compensated absences are not due and payable in the current period and therefore are not reported in the funds.	(778,272)
Deferred inflows of resources for OPEB	(7,294,689)
Deferred inflows of resources for pensions	<u>(12,388,593)</u>
Total Net Position - governmental activities - page 12	<u>\$ 26,882,029</u>



**STOREY COUNTY, NEVADA**  
**STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES**  
**GOVERNMENTAL FUNDS**  
**FOR THE YEAR ENDED JUNE 30, 2022**

	GENERAL	ROAD FUND	474 FIRE PROTECTION DISTRICT FUND	TRI- PAYBACK FUND	USDA BOND FUND
<b>REVENUES</b>					
Taxes	\$ 14,586,167	\$ -	\$ 4,466,424	\$ -	\$ -
Licenses and permits	4,315,289	-	-	-	-
Intergovernmental	2,784,013	1,344,577	1,747,355	-	-
Charges for services	2,542,046	237,752	2,900,545	-	-
Fines and forfeitures	213,866	-	-	-	-
Equipment sales	-	18,571	-	-	-
Miscellaneous	(830,986)	19,080	755,815	259,312	-
<b>Total Revenues</b>	<b>23,610,395</b>	<b>1,619,980</b>	<b>9,870,139</b>	<b>259,312</b>	<b>-</b>
<b>EXPENDITURES</b>					
Current:					
General government	5,549,248	-	-	2,404,764	-
Public safety	5,947,730	-	6,896,049	-	-
Judicial	1,458,868	-	-	-	-
Health and welfare	123,904	-	-	-	-
Culture and recreation	115,955	-	-	-	-
Community service	1,243,816	-	-	-	-
Highways and streets	-	1,089,870	-	-	-
Intergovernmental	-	-	-	-	-
<b>Total Expenditures</b>	<b>14,439,521</b>	<b>1,089,870</b>	<b>6,896,049</b>	<b>2,404,764</b>	<b>-</b>
Excess (Deficiency) of Revenues over Expenditures	9,170,874	530,110	2,974,090	(2,145,452)	-
<b>OTHER FINANCING SOURCES (USES)</b>					
Transfers in	-	400,000	-	1,308,500	142,640
Transfers out	(3,588,000)	-	(425,140)	-	-
Transfers to proprietary funds	-	-	-	-	357,636
Federal grants	-	-	-	-	-
Loan (payments) proceeds	(18,380)	-	-	-	(290,383)
Bond proceeds	-	-	-	-	-
Bond interest	-	-	-	-	(209,884)
<b>Total Other Financing Sources (Uses)</b>	<b>(3,606,380)</b>	<b>400,000</b>	<b>(425,140)</b>	<b>1,308,500</b>	<b>9</b>
<b>Net Change in Fund Balance</b>	<b>5,564,494</b>	<b>930,110</b>	<b>2,548,950</b>	<b>(836,952)</b>	<b>9</b>
Fund Balance, July 1	22,904,046	791,883	2,124,672	2,409,354	29,717
Fund Balance, June 30	\$ 28,468,540	\$ 1,721,993	\$ 4,673,622	\$ 1,572,402	\$ 29,726

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES**  
**GOVERNMENTAL FUNDS**  
**FOR THE YEAR ENDED JUNE 30, 2022**

	VCTC FUND	OTHER GOVERNMENTAL FUNDS	TOTAL GOVERNMENTAL FUNDS
<u>REVENUES</u>			
Taxes	\$ -	\$ 1,402,826	\$ 20,455,417
Licenses and permits	51,201	-	4,366,490
Intergovernmental	1,238,430	1,912,061	9,026,436
Charges for services	551,961	333,252	6,565,556
Fines and forfeitures	-	52,880	266,746
Equipment sales	-	-	18,571
Miscellaneous	110,781	1,023,000	1,337,002
	<u>1,952,373</u>	<u>4,724,019</u>	<u>42,036,218</u>
Total Revenues			
<u>EXPENDITURES</u>			
Current:			
General government	1,535,782	1,832,143	11,321,937
Public safety	-	1,819,553	14,663,332
Judicial	-	25,760	1,484,628
Health and welfare	-	165,974	289,878
Culture and recreation	-	270,212	386,167
Community service	-	-	1,243,816
Highways and streets	-	-	1,089,870
Intergovernmental	-	-	-
	<u>1,535,782</u>	<u>4,113,642</u>	<u>30,479,628</u>
Total Expenditures			
Excess (Deficiency) of Revenues over Expenditures	<u>416,591</u>	<u>610,377</u>	<u>11,556,590</u>
<u>OTHER FINANCING SOURCES (USES)</u>			
Transfers in	-	55,000	1,906,140
Transfers out	-	2,107,000	(1,906,140)
Transfers to proprietary funds	-	-	357,636
Federal Grants	-	-	-
Loan (payments) proceeds	-	(897,927)	(1,206,690)
Bond proceeds	-	-	-
Bond interest	-	-	(209,884)
	<u>-</u>	<u>1,264,073</u>	<u>(1,058,938)</u>
Total Other Financing Sources (Uses)			
Net Change in Fund Balance	416,591	1,874,450	10,497,652
Fund Balance, July 1	<u>1,002,600</u>	<u>13,448,429</u>	<u>42,710,701</u>
Fund Balance, June 30	<u>\$ 1,419,191</u>	<u>\$ 15,322,879</u>	<u>\$ 53,208,353</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**RECONCILIATION OF THE STATEMENT OF REVENUES, EXPENDITURES AND**  
**CHANGES IN FUND BALANCES OF GOVERNMENTAL FUNDS**  
**TO THE STATEMENT OF ACTIVITIES**  
**FOR THE YEAR ENDED JUNE 30, 2022**

Net change in fund balances - governmental funds, page 19 \$ 10,497,652

Amounts reported for governmental activities in the statement of activities are different because:

Capital outlays to purchase capital assets are reported in governmental funds as expenditures. However, those costs are shown in the statement of net assets and allocated over their estimated useful lives as depreciation expense in the statement of activities. This is the amount by which capital outlays exceeded depreciation. (1,535,478)

Net long-term receipts and payments reported in governmental funds as expenditures 7,402,173

Compensated absences are reported as expenses in the statement of activities but do not require the use of current financial resources and therefore are not reported as expenditures in governmental funds (11,629)

Revenue from taxes in the statement of activities that does not provide current financial resources is not reported as revenue in the funds 102,919

Total OPEB benefits are reported as expenses in the statement of activities but do not require the use of current financial resources and therefore are not reported as expenditures in governmental funds (3,499,437)

Total pension benefits are reported as expenses in the statement of activities but do not require the use of current financial resources and therefore are not reported as expenditures in governmental funds 1,339,271

Change in net assets of governmental activities, page 14 \$ 14,295,471

**STOREY COUNTY, NEVADA**  
**GENERAL FUND**  
**STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES**  
**BUDGET AND ACTUAL**  
**FOR THE YEAR ENDED JUNE 30, 2022**

<u>REVENUES</u>	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<b>Taxes:</b>				
Property	\$ 12,189,843	\$ 12,189,843	\$ 14,547,654	\$ 2,357,811
Youth services	32,613	32,613	38,513	5,900
Total Taxes	<u>12,222,456</u>	<u>12,222,456</u>	<u>14,586,167</u>	<u>2,363,711</u>
<b>Licenses and Permits</b>				
Merchandise licenses	218,450	218,450	285,963	67,513
County gaming licenses	3,000	3,000	2,790	(210)
Utility licenses	400,000	400,000	758,265	358,265
Franchise tax	350,000	350,000	437,944	87,944
Building permits and study	499,780	499,780	2,830,327	2,330,547
Total Licenses and Permits	<u>1,471,230</u>	<u>1,471,230</u>	<u>4,315,289</u>	<u>2,844,059</u>
<b>Intergovernmental</b>				
Federal and state grants	-	-	14,739	14,739
Payment in lieu of taxes	30,000	30,000	42,508	12,508
<b>State shared revenues</b>				
Cigarette tax	11,627	11,627	11,597	(30)
Liquor tax	4,834	4,834	6,394	1,560
Gaming licenses	105,000	105,000	115,173	10,173
Basic CCRT	693,224	693,224	917,178	223,954
Supplemental CCRT	741,833	741,833	980,540	238,707
Motor vehicle privilege tax	281,254	281,254	424,819	143,565
Real property transfer tax	147,553	147,553	271,065	123,512
Total Intergovernmental	<u>2,015,325</u>	<u>2,015,325</u>	<u>2,784,013</u>	<u>768,688</u>
<b>Charges for Services</b>				
Clerk fees	31,100	31,100	47,674	16,574
Recorder fees	54,500	54,500	60,543	6,043
Assessor fees/commissions	150,000	150,000	600,081	450,081
Building department fees	6,500	6,500	18,619	12,119
District court fees	16,500	16,500	22,035	5,535
Justice court fees	14,400	14,400	36,296	21,896
Sheriffs fees	39,300	39,300	72,266	32,966
Swimming pool admissions/lessons	-	-	18,679	18,679
Park facilities fees	-	-	1,400	1,400
Import tonnage fees	700,000	700,000	828,117	128,117
IT fees	26,000	26,000	32,718	6,718
Other fees - Tesla	770,966	770,966	803,618	32,652
BIA housing	55,000	55,000	-	(55,000)
Total Charges for Services	<u>1,864,266</u>	<u>1,864,266</u>	<u>2,542,046</u>	<u>677,780</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**GENERAL FUND**  
**STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES**  
**BUDGET AND ACTUAL**  
**FOR THE YEAR ENDED JUNE 30, 2022**

	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUES (cont'd.)</u>				
Fines and Forfeits:				
District fine	300	300	-	(300)
Juvenile fines/assessments	2,400	2,400	2,928	528
Chemical analysis fees	1,000	1,000	3,003	2,003
Jail Court Fines	120,000	120,000	207,935	87,935
Total Fines and Forfeits	<u>123,700</u>	<u>123,700</u>	<u>213,866</u>	<u>90,166</u>
Miscellaneous:				
Rents	60,000	60,000	109,666	49,666
Penalties -taxes	82,000	82,000	157,585	75,585
Penalties - business licenses	750	750	11,015	10,265
Investment earnings	56,000	56,000	(1,227,393)	(1,283,393)
Tax settlement and sales	-	-	-	-
Other	29,100	29,100	118,141	89,041
Total Miscellaneous	<u>227,850</u>	<u>227,850</u>	<u>(830,986)</u>	<u>(1,058,836)</u>
Total Revenues	<u>17,924,827</u>	<u>17,924,827</u>	<u>23,610,395</u>	<u>5,685,568</u>
<u>EXPENDITURES</u>				
General Government				
Commissioners:				
Salaries and wages	334,850	334,850	291,550	43,300
Employee benefits	202,348	202,348	163,277	39,071
Services and supplies	758,181	758,181	607,124	151,057
Capital outlay	-	-	-	-
	<u>1,295,379</u>	<u>1,295,379</u>	<u>1,061,951</u>	<u>233,428</u>
Clerk Treasurer:				
Salaries and wages	244,215	244,215	235,431	8,784
Employee benefits	161,927	161,927	127,832	34,095
Services and supplies	180,165	280,165	172,687	107,478
Capital outlay	-	-	2,584	(2,584)
	<u>586,307</u>	<u>686,307</u>	<u>538,534</u>	<u>147,773</u>
Recorder:				
Salaries and wages	168,334	168,334	147,957	20,377
Employee benefits	94,362	94,362	71,914	22,448
Services and supplies	47,900	47,900	29,090	18,810
Capital outlay	-	-	-	-
	<u>310,596</u>	<u>310,596</u>	<u>248,961</u>	<u>61,635</u>
Assessor:				
Salaries and wages	241,749	241,749	202,531	39,218
Employee benefits	156,668	156,668	104,127	52,541
Services and supplies	87,710	87,710	68,563	19,147
Capital outlay	-	-	-	-
	<u>486,127</u>	<u>486,127</u>	<u>375,221</u>	<u>110,906</u>
Administrative:				
Salaries and wages	185,458	210,458	200,632	9,826
Employee benefits	280,838	280,838	256,708	24,130
Services and supplies	297,410	297,410	121,803	175,607
Capital outlay	-	-	-	-
	<u>763,706</u>	<u>788,706</u>	<u>579,143</u>	<u>209,563</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**GENERAL FUND**  
**STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES**  
**BUDGET AND ACTUAL**  
**FOR THE YEAR ENDED JUNE 30, 2022**

<u>EXPENDITURES</u>	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>General Government (contd.)</u>				
<u>Building and Grounds:</u>				
Salaries and wages	254,206	254,206	242,868	11,338
Employee benefits	142,859	142,859	133,662	9,197
Services and supplies	283,394	323,394	316,282	7,112
Capital outlay	6,000	6,000	-	6,000
	<u>686,459</u>	<u>726,459</u>	<u>692,812</u>	<u>33,647</u>
<u>Service:</u>				
Salaries and wages	247,703	247,703	228,142	19,561
Employee benefits	143,890	143,890	119,380	24,510
Services and supplies	86,740	86,740	87,580	(840)
Capital outlay	20,000	20,000	18,850	1,150
	<u>498,333</u>	<u>498,333</u>	<u>453,952</u>	<u>44,381</u>
<u>Information technology:</u>				
Salaries and wages	371,787	371,787	353,632	18,155
Employees benefits	243,001	243,001	202,502	40,499
Services and supplies	391,950	391,950	308,193	83,757
Capital outlay	19,380	19,380	12,480	6,900
	<u>1,026,118</u>	<u>1,026,118</u>	<u>876,807</u>	<u>149,311</u>
<u>Comptroller:</u>				
Salaries and wages	239,012	239,012	238,040	972
Employee benefits	148,144	148,144	139,221	8,923
Services and supplies	123,925	123,925	103,505	20,420
Capital outlay	-	-	-	-
	<u>511,081</u>	<u>511,081</u>	<u>480,766</u>	<u>30,315</u>
<u>Planning Commission:</u>				
Salaries and wages	214,141	214,141	151,994	62,147
Employee benefits	114,146	114,146	78,327	35,819
Services and supplies	162,100	162,100	10,780	151,320
	<u>490,387</u>	<u>490,387</u>	<u>241,101</u>	<u>249,286</u>
Total General Government	<u>6,654,493</u>	<u>6,819,493</u>	<u>5,549,248</u>	<u>1,270,245</u>
<u>Judicial:</u>				
<u>District Attorney:</u>				
Salaries and wages	406,756	406,756	398,470	8,286
Employee benefits	216,312	216,312	198,126	18,186
Services and supplies	419,750	419,750	207,061	212,689
Capital outlay	-	-	-	-
	<u>1,042,818</u>	<u>1,042,818</u>	<u>803,657</u>	<u>239,161</u>
<u>District Court:</u>				
Services and supplies	195,565	217,565	214,602	2,963
	<u>195,565</u>	<u>217,565</u>	<u>214,602</u>	<u>2,963</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA  
GENERAL FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022**

	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>EXPENDITURES</u>				
Judicial (contd.)				
Justice of the Peace:				
Salaries and wages	282,517	282,517	266,945	15,572
Employee benefits	170,724	170,724	140,426	30,298
Services and supplies	47,600	47,600	33,238	14,362
Capital outlay	-	-	-	-
	<u>500,841</u>	<u>500,841</u>	<u>440,609</u>	<u>60,232</u>
Total Judicial	<u>1,739,224</u>	<u>1,761,224</u>	<u>1,458,868</u>	<u>302,356</u>
Public Safety:				
Sheriff:				
Salaries and wages	2,544,331	2,544,331	2,208,229	336,102
Employee benefits	1,748,951	1,748,951	1,358,797	390,154
Services and supplies	549,085	549,085	529,539	19,546
Capital outlay	-	-	-	-
	<u>4,842,367</u>	<u>4,842,367</u>	<u>4,096,565</u>	<u>745,802</u>
Communications				
Salaries and wages	705,654	705,654	654,289	51,365
Employee benefits	358,974	358,974	325,383	33,591
Services and supplies	153,130	153,130	123,370	29,760
Capital outlay	5,000	5,000	4,498	502
	<u>1,222,758</u>	<u>1,222,758</u>	<u>1,107,540</u>	<u>115,218</u>
Emergency Management:				
Salaries and wages	76,050	76,050	58,909	17,141
Employee benefits	34,065	34,065	20,654	13,411
Services and supplies	67,350	67,350	57,725	9,625
Capital outlay	-	-	-	-
	<u>177,465</u>	<u>177,465</u>	<u>137,288</u>	<u>40,177</u>
Community Development				
Salaries and wages	537,428	537,428	357,435	179,993
Employee benefits	296,887	296,887	165,144	131,743
Services and supplies	149,953	149,953	83,758	66,195
Capital outlay	-	-	-	-
	<u>984,268</u>	<u>984,268</u>	<u>606,337</u>	<u>377,931</u>
Total Public Safety	<u>7,226,858</u>	<u>7,226,858</u>	<u>5,947,730</u>	<u>1,279,128</u>
Health and Human Service				
Salaries and wages	4,574	9,574	8,608	966
Employee benefits	2,642	5,642	5,161	481
Services and supplies	160,387	160,387	110,135	50,252
	<u>167,603</u>	<u>175,603</u>	<u>123,904</u>	<u>51,699</u>
Culture and Recreation:				
Swimming Pools and Parks				
Salaries and wages	77,560	77,560	70,517	7,043
Employee benefits	21,453	21,453	17,157	4,296
Services and supplies	35,472	35,472	28,281	7,191
Capital outlay	-	-	-	-
	<u>134,485</u>	<u>134,485</u>	<u>115,955</u>	<u>18,530</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
GENERAL FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
Community Support				
Salaries and wages	152,400	152,400	126,938	25,462
Employee benefits	54,395	54,395	52,013	2,382
Services and supplies	<u>1,152,870</u>	<u>1,152,870</u>	<u>1,064,865</u>	<u>88,005</u>
Total Community Support	<u>1,359,665</u>	<u>1,359,665</u>	<u>1,243,816</u>	<u>115,849</u>
Debt Service:				
Principle	-	-	18,226	(18,226)
Interest	-	-	154	(154)
Total Debt Service	<u>-</u>	<u>-</u>	<u>18,380</u>	<u>(18,380)</u>
Total Expenditures	<u>17,282,328</u>	<u>17,477,328</u>	<u>14,457,901</u>	<u>3,019,427</u>
Excess (Deficiency) of Revenue over Expenditures	<u>642,499</u>	<u>447,499</u>	<u>9,152,494</u>	<u>8,704,995</u>
<u>OTHER FINANCING SOURCES (USES)</u>				
Transfers out	(3,633,000)	(3,633,000)	(3,588,000)	45,000
Contingency	<u>(518,470)</u>	<u>(423,470)</u>	<u>-</u>	<u>423,470</u>
Total Other Financing Sources (Uses)	<u>(4,151,470)</u>	<u>(4,056,470)</u>	<u>(3,588,000)</u>	<u>468,470</u>
Net Change in Fund Balance	(3,508,971)	(3,608,971)	5,564,494	9,173,465
Fund Balance, July 1	<u>18,313,471</u>	<u>18,313,471</u>	<u>22,904,046</u>	<u>4,590,575</u>
Fund Balance, June 30	<u>\$ 14,804,500</u>	<u>\$ 14,704,500</u>	<u>\$ 28,468,540</u>	<u>\$ 13,764,040</u>

The notes to the financial statements are an integral part of this statement



STOREY COUNTY, NEVADA  
ROADS FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>				
Intergovernmental				
Gasoline tax	\$ 401,132	\$ 401,132	\$ 650,775	\$ 249,643
Supplemental CCRT	469,827	469,827	693,802	223,975
Charges for services				
Import tonnage fees	225,000	225,000	233,572	8,572
Excavation	1,000	1,000	4,180	3,180
Other revenue				
Interest	36,000	36,000	16,999	(19,001)
Equipment sales	-	-	18,571	18,571
Miscellaneous	-	-	2,081	2,081
Total Revenue	<u>1,132,959</u>	<u>1,132,959</u>	<u>1,619,980</u>	<u>487,021</u>
<u>EXPENDITURES</u>				
Highways and Streets				
Salaries and wages	376,642	384,742	379,420	5,322
Employec benefits	211,460	239,460	232,652	6,808
Services and supplies	224,408	224,408	188,750	35,658
Capital outlay	1,008,604	972,504	289,048	683,456
Total Expenditures	<u>1,821,114</u>	<u>1,821,114</u>	<u>1,089,870</u>	<u>731,244</u>
Excess (Deficiency) of Revenues over Expenditures	(688,155)	(688,155)	530,110	1,218,265
<u>OTHER FINANCING SOURCES (USES)</u>				
Transfers in	<u>400,000</u>	<u>400,000</u>	<u>400,000</u>	<u>-</u>
Fund Balance, July 1	<u>481,040</u>	<u>481,040</u>	<u>791,883</u>	<u>310,843</u>
Fund Balance, June 30	<u>\$ 192,885</u>	<u>\$ 192,885</u>	<u>\$ 1,721,993</u>	<u>\$ 1,529,108</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**474 FIRE PROTECTION DISTRICT FUND**  
**STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES**  
**BUDGET AND ACTUAL**  
**FOR THE YEAR ENDED JUNE 30, 2022**

	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>				
Taxes				
Property	\$ 3,407,219	\$ 3,407,219	\$ 4,466,424	\$ 1,059,205
Intergovernmental revenues				
Supplemental CCRT	1,261,115	1,261,115	1,747,355	486,240
Charges for services				
Fire/ambulance fees	356,000	356,000	450,869	94,869
Transport/accident recovery	25,000	25,000	358,694	333,694
Other fees-Tesla	2,178,151	2,178,151	2,089,678	(88,473)
Special events	5,000	5,000	1,304	(3,696)
Other revenue				
Interest income	61,000	61,000	44,075	(16,925)
Miscellaneous - other	300	300	711,740	711,440
Total Revenues	<u>7,293,785</u>	<u>7,293,785</u>	<u>9,870,139</u>	<u>2,576,354</u>
<u>EXPENDITURES</u>				
Public Safety				
Salaries and wages	4,022,653	4,162,653	4,145,279	17,374
Employee benefits	2,116,283	2,116,283	1,974,895	141,388
Services and supplies	720,640	720,640	724,284	(3,644)
Capital outlay	44,538	51,638	51,591	47
Contingency	-	-	-	-
Total Expenditures	<u>6,904,114</u>	<u>7,051,214</u>	<u>6,896,049</u>	<u>155,165</u>
Excess (Deficiency) of Revenue over Expenditures	389,671	242,571	2,974,090	2,731,519
<u>OTHER FINANCING SOURCES (USES)</u>				
Contingency	(209,463)	(4,363)	-	4,363
Transfers	(425,139)	(425,140)	(425,140)	-
Total Other Financing Sources (Uses)	<u>(634,602)</u>	<u>(429,503)</u>	<u>(425,140)</u>	<u>4,363</u>
Excess (Deficiency) of Revenue and Other Financing Sources (Uses) over Expenditures	(244,931)	(186,932)	2,548,950	2,735,882
Fund Balance, July 1	<u>780,911</u>	<u>780,911</u>	<u>2,124,672</u>	<u>1,343,761</u>
Fund Balance, June 30	<u>\$ 535,980</u>	<u>\$ 593,979</u>	<u>\$ 4,673,622</u>	<u>\$ 4,079,643</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 TRI PAYBACK FUND  
 STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCES  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUES</u>			
Intergovernmental			
474 Fire District	\$ 248,000	\$ 259,312	\$ (11,312)
<u>EXPENDITURES</u>			
General Government			
Tri Payback	3,000,000	2,404,764	595,236
Excess (Deficiency) of Revenue over Expenditures	(2,752,000)	(2,145,452)	(606,548)
<u>OTHER FINANCING SOURCES (USES)</u>			
Transfers in	1,026,000	1,308,500	(282,500)
Excess (Deficiency) of Revenue and Other Financing Sources (Uses) over Expenditures	(1,726,000)	(836,952)	(889,048)
Fund Balance, July 1	2,409,354	2,409,354	-
Fund Balance, June 30	<u>\$ 683,354</u>	<u>\$ 1,572,402</u>	<u>\$ 889,048</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 USDA BOND FUND  
 STATEMENT OF REVENUES, EXPENDITURES  
 AND CHANGES IN FUND BALANCES  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUES</u>			
Intergovernmental			
Grants	\$ -	\$ -	\$ -
Bonds	-	-	-
Miscellaneous revenue	-	-	-
Total revenues	-	-	-
<u>EXPENDITURES</u>			
Public safety			
Capital outlay	-	-	-
Excess (Deficiency) of Revenue over Expenditures	-	-	-
<u>OTHER FINANCING SOURCES (USES)</u>			
Bond proceeds	-	-	-
Debt service	(290,382)	(290,383)	1
Interest	(209,884)	(209,884)	-
Transfer in	500,286	500,276	10
Excess (Deficiency) of Revenue and Other Financing Sources (Uses) over Expenditures	20	9	(1)
Fund Balance, July 1	5,247,507	29,717	(5,217,790)
Fund Balance, June 30	\$ 5,247,527	\$ 29,726	\$ (5,217,791)

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 VIRGINIA CITY TOURISM COMMISSION FUND  
 STATEMENT OF REVENUES, EXPENDITURES  
 AND CHANGES IN FUND BALANCES  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUES</u>				
Licenses and permits				
Licenses - permits	\$ 42,000	\$ 42,000	\$ 51,201	\$ 9,201
Intergovernmental				
Grant revenue	22,000	22,000	-	(22,000)
State licenses	2,000	2,000	2,027	27
Room tax	315,000	315,000	484,143	169,143
Tourism tax	500,000	500,000	752,260	252,260
Charges for services				
Special events	308,800	308,800	403,875	95,075
CAP service charge (net)	110,000	110,000	148,086	38,086
Miscellaneous				
Interest	1,500	1,500	170	(1,330)
Contributions	5,000	5,000	6,349	1,349
Miscellaneous	99,700	99,700	104,262	4,562
Total Revenues	<u>1,406,000</u>	<u>1,406,000</u>	<u>1,952,373</u>	<u>546,373</u>
<u>EXPENDITURES</u>				
General government				
Salaries and wages	307,135	337,135	328,650	8,485
Benefits	139,153	154,153	136,755	17,398
Services and supplies	932,779	932,779	965,016	(32,237)
Capital outlay	326,000	281,000	105,361	175,639
Total Expenditures	<u>1,705,067</u>	<u>1,705,067</u>	<u>1,535,782</u>	<u>169,285</u>
Excess (Deficiency) of Revenues over Expenditures	(299,067)	(299,067)	416,591	715,658
Fund Balance, July 1	<u>771,474</u>	<u>771,474</u>	<u>1,002,600</u>	<u>231,126</u>
Fund Balance, June 30	<u>\$ 472,407</u>	<u>\$ 472,407</u>	<u>\$ 1,419,191</u>	<u>\$ 946,784</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 PROPRIETARY FUNDS  
 STATEMENT OF NET POSITION  
 JUNE 30, 2022

	BUSINESS-TYPE ENTERPRISE FUNDS		
	WATER SYSTEM	VIRGINIA DIVIDE SEWER	TOTAL
<u>ASSETS</u>			
Current Assets			
Cash	\$ 1,537,894	\$ 200,352	\$ 1,738,246
Accounts receivable (net allowance)	51,994	46,891	98,885
Total Current Assets	<u>1,589,888</u>	<u>247,243</u>	<u>1,837,131</u>
Noncurrent Assets			
Capital assets - net of accumulated depreciation	<u>8,156,657</u>	<u>18,413,442</u>	<u>26,570,099</u>
Total Assets	<u>\$ 9,746,545</u>	<u>\$ 18,660,685</u>	<u>\$ 28,407,230</u>
<u>DEFERRED OUTFLOWS OF RESOURCES</u>			
Deferred outflows-pension	<u>\$ 147,429</u>	<u>\$ 115,365</u>	<u>\$ 262,794</u>
<u>LIABILITIES</u>			
Current Liabilities			
Accounts payable	\$ 49,096	\$ 12,988	\$ 62,084
Refundable deposits	23,795	-	23,795
Due to general fund	-	-	-
Bonds payable - current portion	-	-	-
Accrued expenses	<u>13,345</u>	<u>11,578</u>	<u>24,923</u>
Total Current Liabilities	<u>86,236</u>	<u>24,566</u>	<u>110,802</u>
Long Term Liabilities			
Bonds payable - net of current portion	3,054,906	6,540,388	9,595,294
Net pension liability	<u>301,115</u>	<u>69,202</u>	<u>370,317</u>
Total Long Term Liabilities	<u>3,356,021</u>	<u>6,609,590</u>	<u>9,965,611</u>
Total Liabilities	<u>3,442,257</u>	<u>6,634,156</u>	<u>10,076,413</u>
<u>DEFERRED INFLOWS OF RESOURCES</u>			
Deferred inflows-pension	<u>\$ 173,958</u>	<u>\$ 143,698</u>	<u>\$ 317,656</u>
<u>NET POSITION</u>			
Restricted reserve	139,365	119,669	259,034
Reserved - short lived assets replacement	-	56,271	56,271
Invested in capital assets - net of related debt	5,101,751	11,873,054	16,974,805
Unassigned	<u>1,036,643</u>	<u>(50,798)</u>	<u>985,845</u>
Total Net Position	<u>\$ 6,277,759</u>	<u>\$ 11,998,196</u>	<u>\$ 18,275,955</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA  
PROPRIETARY FUNDS  
STATEMENT OF REVENUES, EXPENDITURES,  
AND CHANGES IN FUND BALANCES  
FOR THE YEAR ENDED JUNE 30, 2022**

	BUSINESS-TYPE ENTERPRISE FUNDS		
	WATER SYSTEM	VIRGINIA DIVIDE SEWER	TOTAL
<b>OPERATING REVENUES</b>			
Charges for services	\$ 652,958	\$ 452,150	\$ 1,105,108
<b>OPERATING EXPENSES</b>			
Salaries and wages	138,230	138,758	276,988
Benefits	46,863	43,585	90,448
Services and supplies	263,509	15,934	279,443
Capital outlay	-	-	-
Depreciation	104,301	502,962	607,263
Total Operating Expense	552,903	701,239	1,254,142
Operating Income (Loss)	100,055	(249,089)	(149,034)
<b>NONOPERATING REVENUES (EXPENSES)</b>			
Rent and miscellaneous	12,000	-	12,000
Interest income	37,485	65,753	103,238
Interest expense	-	(120,604)	(120,604)
Miscellaneous	5,400	-	5,400
Capital outlay	(330,081)	(782,283)	(1,112,364)
Grants and capital contributions	354,939	813,243	1,168,182
Total Nonoperating Revenues (Expenses)	79,743	(23,891)	55,852
Change in net position	179,798	(272,980)	(93,182)
Net Position, July 1	6,097,961	12,271,176	18,369,137
Net Position, June 30	\$ 6,277,759	\$ 11,998,196	\$ 18,275,955

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA  
PROPRIETARY FUNDS  
STATEMENT OF CASH FLOWS  
FOR THE YEAR ENDED JUNE 30, 2022**

	<u>BUSINESS-TYPE ENTERPRISE FUNDS</u>		
	<u>WATER SYSTEM</u>	<u>VIRGINIA DIVIDE SEWER</u>	<u>TOTAL</u>
<u>CASH FLOWS FROM OPERATING ACTIVITIES</u>			
Cash Inflows			
Sales of water/sewer fees	\$ 660,529	\$ 444,454	\$ 1,104,983
Miscellaneous income	5,400	-	5,400
Cash Outflows			
Salaries and wages	(140,425)	(137,064)	(277,489)
Benefits	(51,745)	(46,318)	(98,063)
Services and supplies	(240,003)	(7,663)	(247,666)
Net Cash Provided (Used) by Operating Activities	<u>233,756</u>	<u>253,409</u>	<u>487,165</u>
<u>CASH FLOWS FROM NON-CAPITAL FINANCING ACTIVITIES</u>			
Cash Inflows			
Rent	12,000	-	12,000
Customer deposits	150	-	150
Capital outlay	-	(782,283)	(782,283)
Net Cash Provided (Used) by Non-Capital Financing Activities	<u>12,150</u>	<u>(782,283)</u>	<u>(770,133)</u>
<u>CASH FLOWS FROM CAPITAL AND RELATED FINANCING ACTIVITIES</u>			
Cash Inflows			
Other Revenue	-	-	-
Capital contributions	354,939	813,243	1,168,182
Transfer from funds	-	-	-
Debt service	-	-	-
Cash Outflows			
Capital outlay and grant match	-	-	(138,455)
Debt service	(63,810)	(138,455)	(184,414)
Interest expense	-	(120,604)	-
Net Cash Provided (Used) by Capital and Related Financing Activities	<u>291,129</u>	<u>554,184</u>	<u>845,313</u>
<u>CASH FLOWS FROM INVESTING ACTIVITIES</u>			
Cash Inflows			
Interest earnings	<u>37,485</u>	<u>65,753</u>	<u>103,238</u>
Net Increase (Decrease) in Cash	574,520	91,063	665,583
Cash, July 1	<u>1,418,308</u>	<u>213,338</u>	<u>1,631,646</u>
Cash, June 30	<u>\$ 1,992,828</u>	<u>\$ 304,401</u>	<u>\$ 2,297,229</u>

The notes to the financial statements are an integral part of this statement



STOREY COUNTY, NEVADA  
STATEMENT OF FIDUCIARY NET POSITION-FIDUCIARY FUNDS  
FIDUCIARY FUNDS  
JUNE 30, 2022

	CUSTODIAL FUNDS
<u>ASSETS</u>	
Cash and cash equivalents	\$ 346,625
Taxes receivable for other governments	\$ 268,439
Total Assets	\$ 615,064
 <u>LIABILITIES</u>	
Accounts payable and other liabilities	\$ 375,815
Due to other governments	239,249
Total Liabilities	615,064
Net Position	-
Total Liabilities and Net Position	\$ 239,249

CASH FLOWS FROM NON-CAPITAL  
STATEMENT OF CHANGES IN FIDUCIARY NET POSITION  
FIDUCIARY FUNDS  
JUNE 30, 2022

	CUSTODIAL FUNDS
<u>Additions</u>	
Taxes and fees collected for other governments	\$ 10,404,046
 <u>Deductions</u>	
Payments of taxes and fees to other governments or organizations/individuals	\$ 10,404,046
Net Position, Beginning of Year	\$ -
Net Position, End of Year	\$ -

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
NOTES TO FINANCIAL STATEMENTS  
JUNE 30, 2022

**I. SUMMARY OF SIGNIFICANT ACCOUNTING POLICIES**

**A. REPORTING ENTITY**

Storey County, Nevada, a local government created under the provisions of Nevada Revised Statutes 243.110, is governed by an elected three-member board of commissioners. As required by generally accepted accounting principles, these financial statements present the government and its component units, entities for which the government is considered to be financially accountable. Blended component units, although legally separate entities, are in substance, part of the government's operations and so data from these units are combined with data of the primary government.

*Blended Component Units* - The Virginia Divide Sewer Improvement District is under the direct oversight of the Storey County Board of Commissioners. The rates for users charges and bond issuance authorizations are approved by the County Commissioners, and the legal liability for the Virginia Divide Sewer District's debt remains with Storey County. The District is reported as an enterprise fund.

Effective July 1, 2014, the Storey County Fire Protection District 474 was created by the Storey County Board of Commissioners. This entity supersedes the Fire, and Fire District Special Revenue Funds. The governing body of the new Fire Protection District 474 is the Board of Fire Commissioners and it can impose its will and will be reported as a Special Revenue Fund.

The Board of County Commissioners directly appoints the governing board of the Virginia City Tourism Commission (VCTC). The county personnel provide essentially all services, accounting, budgeting and other record keeping for the commission. The VCTC has elected to be reported as a major fund (Special Revenue) in the County financial statements.

TRI General Improvement District (TRI GID) is a discretely presented component unit. Storey County's Board of Commissioners is also the board for TRI GID, and thus could impose their will on TRI GID. However, the County does not have a financial benefit or burden relationship with TRI GID.

Excluded from the reporting entity - Storey County Schools, Storey County Senior Center, and Canyon General Improvement District.

These potential component units have separate elected or appointed boards and provide services to residents, generally within the geographic boundaries of the government. These potential component units are excluded from the reporting entity because the government does not have the ability to exercise influence over their daily operations, approve budgets, or provide funding.

**B. GOVERNMENT-WIDE AND FUND FINANCIAL STATEMENTS**

The government-wide financial statements (i.e., the Statement of Net Position and the Statement of Activities) report information on all of the nonfiduciary activities of the primary government and its component units. For the most part the effect of interfund activity has been removed from these statements. *Governmental activities*, which normally are supported by taxes and intergovernmental revenues, are reported, separately from *business-type activities*, which rely to a significant extent on fees and charges for support.

The statement of activities demonstrates the degrees to which the direct expenses of a given function or segment are offset by program revenues. *Direct expenses* are those that are clearly identifiable with a specific function or segment. *Program revenues* include 1) charges to customers or applicants who purchase, use, or directly benefit from goods, services, or privileges provided by a given function or segment and 2) grants and contributions that are restricted to meeting the operational or capital requirements of a particular function or segment. Taxes and other items not properly included among program revenues are reported instead as general revenues.

STOREY COUNTY, NEVADA  
NOTES TO FINANCIAL STATEMENTS  
JUNE 30, 2022

**C. MEASUREMENT FOCUS, BASIS OF ACCOUNTING, AND FINANCIAL STATEMENT PRESENTATION**

The government-wide financial statements are reported using the economic resources measurement focus and the accrual basis of accounting, as are proprietary fund and fiduciary fund financial statements. Revenues are recorded when earned and expenses are recorded when a liability is incurred, regardless of the timing of related cash flows. Property taxes are recognized as revenue in the year for which they are levied. Grants and similar items are recognized as revenue as soon as all eligibility requirements imposed by the provider have been met.

Governmental fund financial statements are reported using the current financial resources measurement focus and the modified accrual basis of accounting. Revenues are recognized as soon as they are both measurable and available. Gross receipts and sales taxes are considered "measurable when in the hands of intermediary collecting agents or governments." Revenues are considered available when they are collectible within the current period or soon enough thereafter to pay liabilities of the current period. For this purpose, the county considers revenues to be available if they are collected within 60 days after the end of the current fiscal period. Anticipated refunds of taxes are recorded as liabilities and reductions of revenue when they are measurable and the payment seems certain. Expenditures are generally recorded when a liability is incurred, as under accrual accounting. However, debt service expenditures, as well as expenditures related to compensated absences and claims and judgments, are recorded only when payment is due.

Property taxes, franchise taxes, licenses, and interest associated with the current fiscal period are all considered to be susceptible to accrual and so have been recognized as revenues of the current fiscal period. All other revenue items are considered to be measurable and available only when cash is received by the County.

The government reports the following major governmental funds:

The *General Fund* is the County's primary operating fund. It accounts for all financial resources of the general government, except those required to be accounted for in another fund.

The *Fire Protection District 474 Special Revenue Fund* accounts for money received primarily from intergovernmental sources. Expenditures are for County fire protection including the purchase of machinery and equipment to provide such services.

The *Tri Payback Fund* accounts for monies which shall be required to be paid back to the developers of the Tahoe-Reno Industrial Center as detailed in Note XV.

The *Road Special Revenue Fund* accounts for money received primarily from gasoline taxes and other intergovernmental sources. Expenditures are for the construction and maintenance of County roads and bridges and other road related infrastructure and the purchase of machinery and equipment required to do such work. (Elected to be reported as a major fund.)

The *USDA Bond Special Revenue Fund* accounts for money received from USDA Bonds to improve water and waste disposal in Storey County and purchase additional fire and ambulance equipment for the Fire Protection District 474.

The *Virginia City Tourism Commission Special Revenue Fund* promotes tourism for Storey County and Virginia City through advertising and promotion of special events and attractions located within the County. (Elected to be reported as a major fund.)

The government reports the following major proprietary funds:

The *Water System Fund* accounts for the activities of the Virginia City/Gold Hill water distribution system.

The *Virginia Divide Sewer System Fund* accounts for the operations of the sewage treatment plant, pumping stations, and collection systems.

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

As a general rule, the effect of inter-fund activity has been eliminated from the government-wide financial statements. Exceptions to this general rule are charges between the government's water and sewer functions. Eliminations of these charges would distort the direct costs and program revenues reported for the various functions concerned.

Amounts reported as *Program Revenues* include 1) charges to customers or applicants for goods, services, or privileges provided; 2) operating grants and contributions; and 3) capital grants and contributions. Internally dedicated resources are reported as *General Revenues* rather than as program revenues. Likewise, general revenues include all taxes.

Proprietary funds distinguish operating revenues and expenses from non-operating items. Operating revenues and expenses generally result from providing services or producing and delivering goods in connection with the proprietary funds' principal ongoing operations. Revenues and expenses not meeting this definition are reported as non-operating revenues and expenses.

**D. ASSETS, LIABILITIES, AND NET ASSETS OR EQUITY**

1. DEPOSITS AND INVESTMENTS

The government's cash and cash equivalents are considered to be cash on hand, demand deposits, short term investments with original maturities of three months or less from the date of acquisition, and the State Treasurer's investment pool. Investments are reported at fair value.

2. RECEIVABLES AND PAYABLES

Activity between funds that is representative of lending/borrowing arrangements outstanding at the end of the fiscal year is referred to as "due to/from other funds."

All trade receivables are shown net of an allowance for uncollectible. No allowance is recorded for property tax receivables. Property taxes are levied as of July 1 on property values assessed on the same date. The tax levy may be paid in four installments by the third Monday in August and the first Monday in October, January, and March. There is a ten day grace period allowed for each installment. Penalties and interest are assessed on all delinquent collections. Liens are filed on the property at one year's delinquency.

3. INVENTORIES AND PREPAID ITEMS

No inventories are maintained by the government for either operating or office supplies. These items are recorded as expenditures when purchased, rather than when consumed. The VCTC maintains an inventory of resale souvenir items which are presented at cost.

Certain payments to vendors reflect costs applicable to future accounting periods and are recorded as prepaid items.

4. RESTRICTED ASSETS AND RESERVED FUNDS

At June 30, 2022, the County had the following restricted fund balances: a) 474 Fire Protection District Fund - \$142,640; b) Virginia Divide Sewer Improvement District - \$119,669; and c) Water System Fund - \$139,365.

STOREY COUNTY, NEVADA  
 NOTES TO FINANCIAL STATEMENTS  
 JUNE 30, 2022

5. CAPITAL ASSETS

Capital assets, which include property, plant, equipment, and infrastructure (i.e., roads, bridges, sidewalks, storm drains, and similar items), are reported in the applicable governmental or business-type activities columns in the government-wide financial statements. Capital assets are defined by the government as assets with an initial, individual cost of more than \$2,500 (amount not rounded) and an estimated useful life in excess of two years. Such assets are recorded at historical cost or estimated historical cost if purchased or constructed. Donated capital assets are recorded at estimated fair market value at the date of donation.

The cost or normal maintenance and repairs that do not add to the value of the asset or materially extend assets lives are not capitalized.

<u>Asset</u>	<u>Years</u>
Public and System Infrastructure	20-100
Vehicles	5-10
Office Equipment	5-10
Equipment	10-20
Buildings	75-100
Building Improvements	35-50
Computer Equipment	5
Furniture and Fixtures	7-10

6. COMPENSATED ABSENCE

It is the government's policy to permit employees to accumulate earned but unused vacation and sick pay benefits. Vested or accumulated vacation pay that is expected to be liquidated with expendable available financial resources is reported as expenditure and a fund liability of the fund that will pay it. Amounts of vested or accumulated vacation pay that are not expected to be liquidated with expendable available financial resources are reported as long term debt. No expenditure is reported for these amounts. No liability is recorded for non-vesting accumulating rights to receive sick pay benefits. However a liability is recognized for that portion of accumulated sick leave benefits that is required to be paid upon termination. All employees with a minimum accrued sick leave of 360 hours to a maximum of 960 hours (except for fire department – no maximum) shall be paid at retirement or termination of service, other than involuntary termination as follows:

<u>Years of Continuous Service</u>	<u>Other Employees Rate of Pay</u>	<u>Fire Department Rate of Pay</u>
5 years but less than 10 years	12.5¢ on the Dollar	20.0¢ on the Dollar
10 years but less than 15 years	25.0¢ on the Dollar	
10 years but less than 20 years		35.0¢ on the Dollar
15 years but less than 20 years	40.0¢ on the Dollar	
20 years or more	50.0¢ on the Dollar	50.0¢ on the Dollar

The maximum sick leave paid upon termination shall be \$5,000 for all employees except law enforcement and firemen

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

Payment for Sick Leave at Termination: Upon an employee's end of service through PERS retirement or termination from service (other than involuntary termination) with total accrued hours of three hundred sixty (360) or more, the Employee shall be paid for unused sick leave at the following rate:

- a. 10 to 15 years of service shall be paid at a rate of 20% of their base rate of pay for each hour, not to exceed \$2,500 cash or \$3,125 toward the purchase of PERS.
- b. 15 to 20 years of service shall be paid at a rate of 40% of their base rate of pay for each hour, not to exceed \$3,500 cash or \$4,375 toward the purchase of PERS.
- c. More than 20 years of service shall be paid at a rate of 60% of their base rate of pay for each hour, not to exceed \$5,000 cash or \$6,250 toward the purchase of PERS.

7. DEFERRED OUTFLOWS/INFLOWS OF RESOURCES

In addition to assets, the Statement of Net Position and the Balance Sheet will sometimes report a separate section for deferred outflows of resources. This separate financial statement element represents a consumption of net position that applies to a future period(s) and will not be recognized as an outflow of resources (expense/expenditure) until then. The County reports an amount related to pensions on the government-wide financial statements.

In addition to liabilities, the Statement of Net Position and the Balance Sheet will sometimes report a separate section for deferred inflows of resources. This separate financial statement element represents an acquisition of net position that applies to a future period(s) and will not be recognized as an inflow of resources (revenue) until that time. The County reports amounts related to pensions on the government wide financial statement. These amounts are deferred and recognized as an inflow of resources in the period that the amounts become available.

8. LONG-TERM OBLIGATIONS

In the government-wide financial statements, and proprietary fund types in the fund financial statements, long-term debt and other long-term obligations are reported as liabilities in the governmental activities, business-type activities, or proprietary fund type statement of net assets.

The County currently has no long term bonds payable in the governmental funds. The revenue bonds reported in the proprietary fund types incurred no bond premiums or discounts and therefore have no deferred charges or amortization.

The County has a long-term obligation relating to the Tahoe-Reno Industrial Center (TRI) – see Note XVII for details.

9. NET POSITION

In the government-wide and proprietary fund financial statements, net position is reported as net investment in capital assets, restricted, or unrestricted. Net position is reported as restricted when constraints placed on it are either imposed by external parties (such as creditors, grantors, contributors or other governments) or imposed by law through a constitutional provision or enabling legislation.

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

10. FUND BALANCE

Fund balances of the governmental funds are classified in accordance with GASB Statement No. 54, *Fund Balance Reporting and Governmental Fund Type Definitions*, as follows:

Nonspendable fund balances include items that cannot be spent, such as amounts that are not in a spendable form (for example, inventories and prepaid items) and amounts that are legally or contractually required to remain intact, such as a permanent fund principal balance.

Restricted fund balances have constraints placed upon the use of the resources either by external parties (such as creditors, grantors, contributors or other governments) or imposed by law through a constitutional provision or enabling legislation.

Committed fund balances can be used only for specific purposes pursuant to constraints imposed by an ordinance of the County Commission, which is the County's highest level of decision-making authority. These constraints remain binding unless removed or changed in the same manner used to create the constraints.

11. ESTIMATES

Timely preparation of financial statements in conformity with accounting principles generally accepted in the United States requires management to make estimates that affect reported amounts. Accordingly, these estimates may require revision in future periods. Significant estimates include compensated absences, pension and other postemployment benefits, collectability of receivables, and useful lives of capital assets.

**II. STEWARDSHIP, COMPLIANCE, AND ACCOUNTABILITY**

**A. BUDGETARY INFORMATION**

Annual budgets are adopted on a basis consistent with generally accepted accounting principles for all governmental funds.

The County follows these procedures in establishing the budgetary date reflected in the financial statements:

1. Prior to April 15, the County budget officer submits to the County Commissioners the tentative operating budgets for the fiscal years commencing the following July 1. The operating budgets include proposed expenditures and the means of financing them.
2. The tentative budgets are filed with the State Department of Taxation by April 15.
3. A public hearing is conducted at the County Court House to obtain taxpayers comments (3rd Monday in May).
4. The final budgets are adopted and filed with the State Department of Taxation. Final budgets must be certified by a majority of all members of the governing body. The final budgets must be adopted on or before June 1.
5. Budget amounts may be transferred within funds if the governing body is advised and the action is recorded in the official minutes of the next meeting. Revisions that alter the total expenditures of any fund must be approved by the County Commissioners. Budget revisions must also be filed with the State Department of Taxation.

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

6. Budgets for the General, Special Revenues, Debt Service, Proprietary, and Capital Projects Funds are adopted on a basis consistent with generally accepted accounting principles (GAAP).
7. Budget augmentations were prepared for the general, various special revenue funds and enterprise funds during the fiscal year ended June 30, 2022
8. All budget appropriations lapse at the end of each fiscal year.

In accordance with state statute, actual expenditures may not exceed budgetary appropriations of the various governmental programs of the General Fund or total appropriations of the Special Revenue and Capital Projects Funds, except as expressly authorized by law.

**B. EXCESS EXPENDITURES OVER APPROPRIATIONS**

For the year ended June 30, 2022, expenditures exceeded appropriations as follows:

	Expenditures	Appropriations
Indigent Accident Special Revenue Fund	\$ 122,671	\$ 116,000
Virginia City Rail Capital Projects Fund	270,212	250,000
Water System Enterprise Fund	552,903	572,587
Virginia Divide Sewer Improvement District	701,239	325,421

**C. COMPLIANCE – NRS 354.624**

Storey County has two enterprise funds: The Water System Enterprise Fund and the Virginia-Divide Sewer Improvement District Enterprise Fund. Storey County also maintains agency funds as follows: State of Nevada Fund Storey County School District Fund, Storey County School District Debt Service Fund. The County maintains no internal service funds, self-insurance funds, or funds whose balance is required by law to be used for a specific purpose other than the payment of compensation to a bargaining unit as defined in NRS 288.028 or carried forward to the succeeding fiscal year in any designated amount.

All enterprise and agency funds maintained by Storey County:

- a) are being used in accordance with NRS 354.624.
- b) are being administered in accordance with generally accepted accounting procedures.
- c) all reserves in the funds are reasonable and necessary to carry out the purposes of the funds.
- d) reflect the sources of revenues available for the fund during the fiscal year – including transfers from other funds.
- e) are following the statutory and regulatory requirements applicable to the funds
- f) reflect the balance and retained earnings of the funds.

Storey County has \$401,674 restricted and reserved in all funds.



**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

**III. CASH AND INVESTMENTS**

In accordance with Nevada Revised Statutes (NRS), the County's cash is deposited with insured banks and those deposits that are not within the limits of insurance must be secured by collateral. At year end, the County's carrying amount of deposits was \$6,563,968 and the bank balance was \$6,592,604. The difference between the carrying amount and bank balance results from outstanding checks and deposits not yet reflected in the bank records

**Custodial Risk-** All deposits are subject to custodial credit risk, which is the risk that the County's deposits may not be returned to it in the event of a bank failure. Bank balances were covered by Federal Depository Insurance, the Securities Investor Protection Corporation, collateral held by the County's agent in the County's name or by collateral held by depositories in the name of the Nevada Collateral Pool, and were not exposed to custodial credit risk. The County does not have a formal policy relating to custodial credit risk, but follows NRS. According to NRS 356.020, all monies deposited by a county treasurer that are not within the limits of insurance provided by an instrumentality of the United States must be secured by collateral composed of the same types of securities allowed for investments which are identified below. The County participates in the State of Nevada Collateral Pool which requires depositories to maintain as collateral acceptable securities having a fair market value of at least 102 percent of the amount of the uninsured balances of the public money held by the depository. Under NRS 356.360, the State Treasurer manages and monitors all collateral for all public monies deposited by members of the pool.

**Interest Rate Risk-** Interest rate risk is the risk of possible reduction in the value of a security, especially a bond, resulting from a rise in interest rates. As noted above, the County does not have a formal investment policy that limits investment maturities as a means of managing its exposure to fair value losses arising from increasing interest rates beyond those specified in the statute. The County restricts notes, bonds, and other unconditional obligations at the time of purchase to have a remaining term to maturity of not more than 10 years as described by Nevada state law.

**Credit Risk-** NRS allows investments in obligations of the U.S. Treasury and U.S. agencies, municipal bonds issued by local governments of the State, corporate bonds rated "A" or better by a nationally recognized rating service, commercial paper rated "A-1," "P-1" or better by a nationally recognized rating service, repurchase agreements, certificates of deposit, money market mutual funds rated "AAA" by a nationally recognized rating service or other securities in which banking institutions may legally invest.

At June 30, 2022, the County's investments are rated as follows

	Reported <u>Fair Value</u>	Quality <u>Rating</u>
Money Market Mutual Fund	\$ 318,218	AAA
Certificates of Deposit	401,733	AA-
Certificates of Deposit	221,160	A+
Certificates of Deposit	718,645	A
Certificates of Deposit	667,148	AA-
Certificates of Deposit	730,948	A-
Certificates of Deposit-fdic guaranteed	4,818,444	Unrated
Us Treasury Securities	15,563,778	AAA
US Agency Bonds	6,476,098	AAA
US Agency Bonds	159,121	A
Corporate Bonds	1,615,037	A+
Corporate Bonds	6,019,910	A
Corporate Bonds	299,403	A-
Corporate Bonds	1,232,792	AA-
Corporate Bonds	680,642	Unrated
State of Nevada Local Investment Pool	<u>2,483,629</u>	Unrated
	\$ 42,406,706	

The County categorizes the fair value measurements of its investments based on the hierarchy established by generally accepted accounting principles. The fair value hierarchy, which has three levels, is based on the valuation inputs used to measure an asset's fair value:

- Level 1- Inputs are quoted prices in active markets for identical assets
- Level 2- Inputs are significant other observable inputs
- Level 3- Inputs are significant unobservable inputs

The County does not have any investments that are measured using Level 3 inputs

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

Cash and investments are categorized by fund type as follows:

Governmental funds	\$ 54,612,581
Proprietary funds	1,738,246
Custodial funds	346,625
Component Unit	<u>5,352,129</u>
	<u>\$ 62,049,581</u>

As of June 30, 2022, the County had the following recurring fair value measurements below:

<u>Investment Type</u>	<u>Total</u>	<u>Fair Value Measurements Using</u>	
		<u>Level 1 Inputs</u>	<u>Level 2 Inputs</u>
Money Market Mutual Fund	\$ 318,218	\$ 318,218	\$ -
Certificates of Deposit	7,558,078	7,558,078	-
Us Treasury Securities	15,563,778	15,563,778	-
US Agency Bonds	6,635,219	6,635,219	-
Corporate Bonds	<u>9,847,784</u>	<u>-</u>	<u>9,847,784</u>
Total investments by fair value level	<u>\$ 39,923,077</u>	<u>\$ 30,075,293</u>	<u>\$ 9,847,784</u>

Investments not required to be measured at fair value

State of Nevada Investment Pool	<u>2,483,629</u>
---------------------------------	------------------

Total Investments	<u>\$ 42,406,706</u>
-------------------	----------------------

At year end the County had the following investments and maturities

<u>Investment Type</u>	<u>Total</u>	<u>Investment Maturities in Years</u>		
		<u>Less Than 1</u>	<u>1-5</u>	<u>More than 5 years</u>
Money Market Mutual Fund	\$ 318,218	\$ 318,218	\$ -	-
Certificates of Deposit	7,558,078	3,960,088	3,597,990	-
Us Treasury Securities	15,563,778	2,954,855	12,608,923	-
US Agency Bonds	6,635,219	-	1,057,834	5,577,385
Corporate Bonds	9,847,784	1,889,956	7,957,828	-
State of Nevada Investment Pool	<u>2,483,629</u>	<u>2,483,629</u>	<u>-</u>	<u>-</u>
Total Investments	42,406,706	<u>\$ 11,606,746</u>	<u>\$ 25,222,575</u>	<u>\$ 5,577,385</u>
Total cash and cash equivalents	<u>19,584,799</u>			
Total cash, cash equivalents and investments	<u>\$ 62,049,581</u>			

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

**IV. RECEIVABLES**

Receivables as of year-end for the government's individual major funds and non-major funds in the aggregate, including the applicable allowances for uncollectible accounts, are as follows:

	<u>General</u>	<u>Roads</u>	<u>474 Fire District</u>	<u>Tri Payback</u>	<u>VCTC</u>	<u>Non-Major Funds</u>	<u>Proprietary Funds</u>	<u>Total</u>
Receivables:								
Taxes	\$ 247,576	\$ -	\$ 76,097	\$ -	\$ -	\$ 8,384	\$ -	\$ 332,057
Accounts	<u>736,719</u>	<u>223,834</u>	<u>883,167</u>	<u>85,124</u>	<u>145,021</u>	<u>290,313</u>	<u>98,886</u>	<u>2,463,064</u>
Gross Receivables	<u>984,295</u>	<u>223,834</u>	<u>959,264</u>	<u>85,124</u>	<u>145,021</u>	<u>298,697</u>	<u>98,886</u>	<u>2,795,121</u>

The delinquent taxes receivable account represents the past three years of uncollected tax levies. No allowance for uncollectible has been recorded by the County. Taxes received after 60 days of the year end are recorded as deferred revenue.

Accounts receivable include intergovernmental receivables. All accounts receivable, with the exception of the enterprise fund, were collected within a 60 day period, therefore no allowance for uncollectible was recorded in those funds.

Governmental funds report *deferred revenue* in connection with receivables for revenues that are not considered to be available to liquidate liabilities of the current period. At the end of the current fiscal year the various components of *deferred revenue* reported in the governmental funds were as follows:

General Fund-Delinquent property taxes receivable:	\$ 45,758
454 Fire District Fund-Delinquent property taxes receivable:	14,099
454 Fire District Fund-Ambulance receivable	466,724
Non-major funds-Delinquent property taxes receivable:	<u>1,555</u>
Total	<u>\$ 528,136</u>

**V. INTER-FUND ASSETS/LIABILITIES**

Interfund transfers are used to (1) move revenues from the fund that statute or budget requires to collect them to the fund that statute or budget requires to expend them or, (2) move receipts restricted to debt service from the funds collecting the receipts to the Debt Service Fund as debt service payments become due or, (3) use unrestricted revenues collected in the General Fund to finance various programs accounted for in other funds in accordance with budgetary authorizations.

The following are transfers that meet one of the three descriptions above:

<u>From</u>	<u>To</u>	
General Fund	Roads Fund	\$ 400,000
General Fund	TRI Payback	1,000,000
General Fund	Emergency Mitigation	78,000
General Fund	Pipers	110,000
General Fund	Capital Projects	2,000,000
Fire District 474	TRI Payback	282,000
Fire District 474	USDA	142,640
Virginia Divide Sewer	USDA	259,068
Water System	usa	98,568
Equipment Acquisition	TRI Payback	26,000
Mutual Aid	Fire District 474	500,000
Fire District 474	Fire Emergency	42,859
Fire District 474	Stabilization	407,141
Fire District 474	Fire Grant	50,000

STOREY COUNTY, NEVADA  
NOTES TO FINANCIAL STATEMENTS  
JUNE 30, 2022

**VI. PROPERTY TAXES**

Property taxes attach as an enforceable lien as of July 1. The tax is levied for the fiscal year beginning July 1 after the Nevada Tax Commission has certified the combined tax rate for the County on May 25.

Taxes on the property are due on the third Monday in July. Taxes may be paid in quarterly installments, due on the third Monday of July and the first Monday in October, January, and March. Penalties are added if the installments are not made within ten (10) days of the due date.

**VII. CONTINGENT LIABILITIES**

The County receives grant funds from Federal and State agencies. The grant programs are subject to audit by agents of the granting authority. The purpose of the audits is to ensure compliance with conditions precedent to the granting of the funds. Management does not anticipate any liability in the event of an audit.

**VIII. RISK MANAGEMENT**

Storey County is exposed to various risks of loss related to torts; theft of, damage to, and destruction of assets; errors and omissions; injuries to employees; and natural disasters. Storey County has joined together with other counties in the state to form Nevada Public Agency Insurance Pool, a public entity risk pool currently operating as a common risk management and insurance program for 41 governmental entities. The county pays an annual premium to Ingalls and Associates for its general insurance coverage through PENCO. The Agreement for Formation of the NPAIP program provides that NPAIP will be self-sustaining through member premiums and will reinsure through commercial companies for claims in excess of \$500,000 for Property and Crime and \$150,000 for Casualty for each insured event.

The County continues to carry commercial insurance for all other risks or loss, including workers' compensation and employee health and accident insurance. Settled claims resulting from these risks have not exceeded commercial insurance coverage in any of the past three fiscal years.

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

**IX. CAPITAL ASSETS**

	Beginning Balance	Increases	Decreases	Ending Balance
Primary Government				
Governmental Activities				
Capital Assets not being depreciated				
Land	\$ 810,921	\$ -	\$ -	\$ 810,921
Antique Furniture	75,000	-	-	75,000
Construction in progress	3,769,420	183,080	1,021,694	2,930,806
Total Capital Assets not being depreciated	4,655,341	183,080	1,021,694	3,816,727
Capital Assets being depreciated				
Leased assets	\$ 71,976	\$ -	\$ -	\$ 71,976
Buildings	12,840,363	-	-	12,840,363
Improvements other than buildings	49,810,005	653,562	-	50,463,567
Machinery and equipment	17,515,862	1,588,682	59,813	19,044,731
Total Capital Assets being depreciated	80,238,206	2,242,244	59,813	82,420,637
Less accumulated depreciation for:				
Leased assets amortization	-	15,835	-	15,835
Buildings	3,685,488	267,058	-	3,952,546
Improvements other than buildings	14,150,217	1,407,861	-	15,558,078
Machinery and equipment	10,754,097	1,248,354	59,813	11,942,638
Total accumulated depreciation	28,589,802	2,923,273	59,813	31,453,262
Governmental activities capital assets - net	\$ 56,303,745	\$ (497,949)	\$ 1,021,694	\$ 54,784,102
Business type activities				
Capital Assets not being depreciated				
Construction in progress	\$ 4,635,056	\$ -	\$ 972,529	\$ 3,662,527
Capital assets being depreciated				
Water and sewer system	26,578,621	972,529	-	27,551,150
Machinery and equipment	726,987	-	-	726,987
Total Capital assets being depreciated	27,305,608	972,529	-	28,278,137
Less accumulated depreciation for:				
Water and sewer systems	4,220,986	582,950	-	4,803,936
Machinery and equipment	636,485	14,896	-	651,381
Total accumulated depreciation	4,857,471	597,846	-	5,455,317
Business type activities capital assets - net	\$ 27,083,193	\$ 374,683	\$ 972,529	\$ 26,485,347
Net capital assets at June 30,2022, for the discretely presented component unit were:				<u>TRJ GID</u>
Net Capital assets				
Capital assets not being depreciated				\$ 52,917,594
Capital assets being depreciated				56,332,094
Capital assets Net				\$ 109,249,688

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

Depreciation expense was charged to functions programs of the primary government as follows:

Governmental activities:	
General government	\$ 1,992,630
Public safety	658,034
Highways and streets, including depreciation of general infrastructure assets	165,330
Judicial	9,481
Community support	72,598
Culture and recreation	25,200
Total depreciation expense - Governmental activities	<u>\$ 2,923,273</u>
Business type activities:	
Water	\$ 94,884
Sewer	502,962
Total depreciation expense - Business type activities	<u>\$ 597,846</u>

**X. LONG-TERM OBLIGATIONS**

The following is a summary of the Long-Term Obligations of the County:

	<u>Date</u> <u>Issue</u>	<u>Maturity</u> <u>Date</u>	<u>Original</u> <u>Note/issue</u>	<u>Interest</u> <u>Rate</u>	<u>Balance</u> <u>6/30/2022</u>
<u>Revenue Bonds</u>					
<u>Governmental</u>					
Virginia City Rail Bond-Series 2010A	12/28/2010	12/1/2027	\$ 890,000	8.000%	\$ -
Virginia City Rail Bond-Series 2010B	12/28/2010	12/1/2027	859,000	5.000%	-
Storey County Fire District USDA Loan	1/8/2015	7/8/2034	2,000,000	3.750%	1,396,825
			<u>2,000,000</u>		<u>\$ 1,396,825</u>
<u>Business Type Activities</u>					
Sewer Revenue Bonds	5/20/2015	5/12/2055	3,002,000	2.500%	2,663,305
Sewer Revenue Bonds	12/20/2016	12/20/2056	4,058,000	1.375%	3,623,157
Sewer Revenue Bonds	9/23/2020	9/23/2060	264,000	1.125%	253,925
Water Revenue Bond	9/23/2020	9/23/2060	2,126,000	1.125%	2,051,463
Water Revenue Bond	9/23/2020	9/23/2060	701,001	1.125%	674,080
Water Revenue Bond	9/23/2020	9/23/2060	344,000	1.125%	329,363
			<u>\$ 10,495,001</u>		<u>\$ 9,595,293</u>

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

The following represents the current activity in the Long-Term Obligations of the County:

	Balance 6/30/2021	Additions	Retired	Balance 6/30/2022	Principle Due 22-23
<u>Revenue Bonds</u>					
Governmental					
Virginia City Rail Bond-Series 2010A	\$ 448,000	\$ -	\$ 448,000	\$ -	\$ -
Virginia City Rail Bond-Series 2010B	443,000	-	443,000	-	-
Storey County Fire District USDA Loan	1,485,008	-	88,183	1,396,825	91,536
	<u>\$ 2,376,008</u>	<u>\$ -</u>	<u>\$ 979,183</u>	<u>\$ 1,396,825</u>	<u>\$ 91,536</u>
<u>Business Type Activities</u>					
Sewer Revenue Bonds	\$ 2,714,903	\$ -	\$ 51,598	\$ 2,663,305	\$ 52,902
Sewer Revenue Bonds	3,704,695	-	81,538	3,623,157	82,666
Sewer Revenue Bonds	259,244	-	5,319	253,925	5,379
Water Revenue Bond	2,094,207	-	42,744	2,051,463	43,227
Water Revenue Bond	688,202	-	14,122	674,080	14,282
Water Revenue Bond	336,307	-	6,944	329,363	7,023
	<u>\$ 9,797,558</u>	<u>\$ -</u>	<u>\$ 202,265</u>	<u>\$ 9,595,293</u>	<u>\$ 205,479</u>
Leases-Body cameras	\$ 71,976	\$ -	\$ 18,226	\$ 53,750	\$ 17,688
<u>Long-Term Liabilities</u>					
Compensated Absences	\$ 766,643	\$ 11,629	\$ -	\$ 778,272	\$ -
TRI-Construction repayment	38,342,347	-	6,404,764	31,937,583	-
	<u>\$ 39,108,990</u>	<u>\$ 11,629</u>	<u>\$ 6,404,764</u>	<u>\$ 32,715,855</u>	<u>\$ -</u>

The annual requirements to amortize the outstanding revenue bonds are as follows:

Year Ended June 30	Governmental Activities		Business Type Activities	
	Principal	Interest	Principal	Interest
2023	\$ 91,536	\$ 51,104	\$ 205,479	\$ 152,147
2024	95,017	47,623	208,343	149,283
2025	98,631	44,009	212,075	145,552
2026	102,382	40,258	215,465	142,161
2027	106,276	36,364	218,916	138,710
2028-2032	595,168	118,032	1,147,847	640,283
2033-2037	307,815	14,665	1,244,385	543,746
2038-2042	-	-	1,349,706	438,424
2043-2047	-	-	1,465,156	322,974
2048-2052	-	-	1,591,753	196,378
2053-2057	-	-	1,408,104	66,368
2058-2062	-	-	328,064	5,974
Total	<u>\$ 1,396,825</u>	<u>\$ 352,055</u>	<u>\$ 9,595,293</u>	<u>\$ 2,942,000</u>

Year Ended June 30	Leases	
	Principal	Interest
2023	\$ 17,688	\$ 692
2024	17,916	464
2025	18,146	234
Total	<u>53,750</u>	<u>40,258</u>

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

**X1. SEGMENT INFORMATION – PROPRIETARY FUNDS**

Summary information for the Proprietary funds is presented below:

	Water Fund	Virginia Divide Sewer Fund
<b>CONDENSED STATEMENT OF NET ASSETS</b>		
<b>ASSETS</b>		
Current assets	\$ 1,589,888	\$ 247,243
Capital assets (net accumulated depreciation)	8,156,657	18,413,442
Total Assets	9,746,545	18,660,685
<b>DEFERRED OUTFLOWS OF RESOURCES</b>		
Deferred outflows-pension	147,429	115,365
<b>LIABILITIES</b>		
Current liabilities	86,236	24,566
Non-current liabilities	3,356,021	6,609,590
Total Liabilities	3,442,257	6,634,156
<b>DEFERRED INFLOWS OF RESOURCES</b>		
Deferred inflows-pension	173,958	143,698
<b>NET POSITION</b>		
Restricted reserve	139,365	119,669
Reserved - Short lived asset replacement	-	56,271
Invested in capital assets - net of related debt	5,101,751	11,873,054
Unrestricted	1,036,643	(50,798)
Total Net Position	\$ 6,277,759	\$ 11,998,196
<b>CONDENSED STATEMENT OF REVENUES AND EXPENSES</b>		
Operating revenue	\$ 652,958	\$ 452,150
Depreciation	(104,301)	(502,962)
Other operating expenses	(448,602)	(198,277)
Operating income (loss)	100,055	(249,089)
<b>Non-operating revenues (expenses)</b>		
Rent and miscellaneous	12,000	-
Interest income	37,485	65,753
Interest expense	-	(120,604)
Miscellaneous	5,400	-
Transfers from capital projects funds	62,806	210,097
Grants and capital contributions	354,939	813,243
Change in net assets	\$ 572,685	\$ 719,400
<b>CONDENSED STATEMENTS OF CASH FLOWS</b>		
Net cash provided (used) by		
Operating activities	\$ 233,756	\$ 253,409
Non-capital financing activities	12,150	(782,283)
Capital and related financing activities	291,129	554,184
Investing Activities	37,485	65,753
Net increase (decrease) in cash	574,520	91,063
Cash - beginning	1,418,308	213,338
Cash - ending	\$ 1,992,828	\$ 304,401



STOREY COUNTY, NEVADA  
NOTES TO FINANCIAL STATEMENTS  
JUNE 30, 2022

**XII. DEFINED BENEFITS PLAN**

General Information about the Pension Plan

*Plan Description* : All permanent, full-time employees are provided pensions through the Public Employees Retirement Plan (PERS). The plan is a multiple-employer defined benefit pension plan administered by the Public Employees' Retirement System of Nevada. Chapter 286 of the Nevada Revised Statutes (NRS) establishes a governing board, appointed by the Governor, that is responsible for managing the System, including arranging for a biennial actuarial valuation and adoption of actuarial tables and formulas prepared and recommended by the actuary.

*Benefits Provided* : Benefits, as required by the Nevada Revised Statutes (NRS or statute), are determined by the number of years of accredited service at time of retirement and the member's highest average compensation in any 36 consecutive months with special provisions for members entering the System on or after January 1, 2010. Benefit payments to which participants or their beneficiaries may be entitled under the plan include pension benefits, disability benefits, and survivor benefits.

Monthly Benefit allowances for members are computed at 2.5% of average compensation for each accredited year of service prior to July 1, 2001. For service earned on and after July 1, 2001, this multiplier is 2.67% of average compensation. For members entering the System on or after January 1, 2010, there is a 2.5% multiplier. The System offers several alternatives to the unmodified service retirement allowance which, in general, allow the retired employee to accept a reduced service retirement allowance payable monthly during his or her lifetime and various optional monthly payments to a named beneficiary after his or her death. Post-retirement increases are provided by the authority of NRS 286.575-.579

Regular members are eligible for retirement at age 65 with five years of service, at age 60 with ten years of service, or at any age with thirty years of service. Regular members entering the System on or after January 1, 2010, are eligible for retirement at age 65 with five years of service, at age 62 with ten years of service, or at any age with thirty years of service.

Police/Fire members are eligible for retirement at age 65 with five years of service, at age 55 with ten years of service, at age 50 with twenty years of service, or at any age with twenty-five years of service. Police/Fire members entering the System on or after January 1, 2010, are eligible for retirement at age 65 with five years of service, at age 60 with ten years of service, at age 50 with twenty years of service, or at any age with thirty years of service. Only service performed in a position as a police officer or firefighter may be counted towards eligibility for retirement as Police/Fire accredited service.

The normal ceiling limitation on monthly benefit allowances is 75% of average compensation. However, a member who has an effective date of membership before July 1, 1985, is entitled to a benefit of up to 90% of average compensation. Both Regular and Police/Fire members become fully vested as to benefits upon completion of five years of service.

STOREY COUNTY, NEVADA  
NOTES TO FINANCIAL STATEMENTS  
JUNE 30, 2022

*Contributions:* The authority for establishing and amending the obligation to make contributions, and member contribution rates, is set by statute. The contribution rates are based on biennial actuarial valuations and expected to finance the costs of benefits earned by employees during the year, with an additional amount to finance any unfunded accrued liability. New hires in agencies which did not elect the Employer-Pay Contribution (EPC) plan prior to July 1, 1983, have the option of selecting one of two contribution plans. One plan provides for matching employee and employer contributions, while the other plan provides for employer-pay contributions only. Under the matching Employee/Employer Contribution plan a member may, upon termination of service for which contribution is required, withdraw employee contributions which have been credited to their account. All membership rights and active service credit in the System are canceled upon withdrawal of contributions from the member's account. If EPC was elected, the member cannot convert to the Employee/Employer Contribution plan.

The County's contributions to the plan totaled \$1,855,184 for the year ended June 30, 2022

Pension Liabilities, Expense, and Deferred Outflows/ Inflows of Resources Related to Pensions

At June 30, 2022, the County reported a liability of \$14,812,664 for its proportionate share of the net pension liability. The net pension liability was measured as of June 30, 2021, and the total pension liability used to calculate the net pension liability was determined by an actuarial valuation as of that date. The County's proportion of the plan's net pension liability was based on the County's combined employer and member contributions to the pension plan relative to the contributions of all participating entities for the year ended June 30, 2021. At June 30, 2021, the County's proportion share was .16244% in year 2021, while year 2020 was .15285%.

For the year ended June 30, 2022, the County recognized pension expense of \$394,961. At June 30, 2022, the County reported deferred outflows of resources and deferred inflows of resources related to pensions from the following sources:

	Deferred Outflows of Resources	Deferred Inflows of Resources
Difference between expected and actual experience	\$ 1,640,793	\$ 104,247
Changes in assumptions or other inputs	4,918,060	-
Net difference between projected and actual earnings on pension plan investments	-	12,086,662
Changes in the employer's proportion and differences between the employer's contributions and the employer's proportionate contributions	2,097,734	515,340
County contributions subsequent to the measurement date	1,855,184	-
	\$ 10,511,771	\$ 12,706,249

STOREY COUNTY, NEVADA  
NOTES TO FINANCIAL STATEMENTS  
JUNE 30, 2022

Other amounts reported as deferred outflows of resources and deferred inflows of resources related to pensions will be recognized in pension expense as follows:

2023	\$	(1,464,109)
2024		(1,674,103)
2025		(1,718,158)
2026		(1,592,098)
2027		1,140,592
2028		1,103,697
Thereafter		154,517
	\$	(4,049,662)

In addition, \$1,855,184 is reported as deferred outflows of resources related to pensions and represents County's contributions subsequent to the measurement date. The amount will be recognized as a reduction of the net pension liability in the year ended June 30, 2022.

*Actuarial Assumptions:* When measuring the total pension liability, GASB uses the same actuarial cost method, all actuarial assumptions, and the same type of discount rate as PERS uses for funding.

The total pension liability in the June 30, 2021, actuarial valuation was determined using the following actuarial assumptions applied to all periods included in the measurement:

Inflation Rate	2.50%
Investment Rate of Return	7.25%
Productivity Pay Increases	0.5%
Projected Salary Increases	Regular: 4.20% to 9.10%, depending on service Police/Fire: 4.60% to 14.5%, depending on service Rates include inflation and productivity increases
Other Assumptions	Same as those used in the June 30, 2021 funding actuarial valuation

The Board evaluates and establishes expected real rates of return (expected returns, net of investment expenses and inflation) for each asset class. The Board reviews these capital market expectations annually. The PERS' current long-term geometric expected real rates of return for each asset class included in the plan's investment portfolio as of June 30, 2021, are included in the following table:

Asset Class	Target Allocation	Long-Term Geometric Expected Real Rate of Return*
Domestic Equity	42%	5.50%
International Equity	18%	5.5
Domestic Fixed Income	28%	.75
Private Markets	12%	6.65

\*As of June 30, 2021, PERS' long-term inflation assumption was 2.50%.

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

*Discount Rate* : The discount rate used to measure the total pension liability was 7.25% as of June 30, 2021. The projection of cash flows used to determine the discount rate assumed plan contributions will be made in amounts

consistent with statutory provisions and recognizing the plan's current funding policy and cost-sharing mechanism between employers and members. For this purpose, all contributions that are intended to fund benefits for all plan members and their beneficiaries are included, except that project contributions that are intended to fund the service costs for future plan members and their beneficiaries are not included.

*Sensitivity of the County's Proportionate Share of the Net Pension Liability to Changes in the Discount Rate* : The following presents the County's proportionate share of the net pension liability calculated using the discount rate of 7.25%, as well as what the County's proportionate share of the net pension liability would be if it were calculated using a discount rate that is 1 percentage point lower (6.25%) or 1 percentage point higher (8.25%) than the current rate:

1% Decrease (6.25%)	Discount Rate (7.25%)	1% Increase (8.25%)
\$ 29,492,977	\$ 14,812,664	\$ 2,703,925

*Additional Information* : Additional information supporting the Schedule of Employer Allocations and the Schedule of Pension Amounts by Employer is located in the PERS Comprehensive Annual Financial Report (CAFR) available on the PERS website at [www.nvpers.org](http://www.nvpers.org) under Quick Links – Publications.

**Discretely Presented Component Units**

At June 30, 2022, the Component unit reported a liability of \$511,184 for its proportionate share of the net pension liability. The net pension liability was measured as of June 30, 2021, and the total pension liability used to calculate the net pension liability was determined by an actuarial valuation as of that date. The Component units' proportion of the plan's net pension liability was based on the County's combined employer and member contributions to the pension plan relative to the contributions of all participating entities for the year ended June 30, 2021. At June 30, 2021, the County's proportion share was .00561% in year 2021, while year 2020 was .00240%.

For the year ended June 30, 2022, TRIGID recognized pension expense of \$115,455. At June 30, 2022, TRIGID reported deferred outflows of resources and deferred inflows of resources related to pensions from the following sources:

	Deferred Outflows of Resources	Deferred Inflows of Resources
Difference between expected and actual experience	\$ 56,624	\$ 3,598
Changes in assumptions or other inputs	169,722	-
Net difference between projected and actual earnings on pension plan investments	-	417,110
Changes in the employer's proportion and differences between the employer's contributions and the employer's proportionate contributions	591,129	-
TRIGID contributions subsequent to the measurement date	143,054	-
	\$ 960,529	\$ 420,708

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

The following presents the net pension liability of TRIGID as of June 30, 2022 calculated using the discount rate of 7.25%, as well as what the net pension liability would be if it were calculated using a discount rate that is 1-percentage point lower(7.25%) or 1 percentage point higher(8.25%) than the discount rate

1% Decrease (6.25%)	Discount Rate (7.25%)	1% Increase (8.25%)
\$ 1,018,564	\$ 511,184	\$ 93,382

Other amounts reported as deferred outflows of resources and deferred inflows of resources related to pensions will be recognized in pension expense as follows:

2023	\$ 63,625
2024	63,625
2025	63,625
2026	67,863
2027	123,326
2028	14,703
Thereafter	396,767

**XIII. POST-EMPLOYMENT BENEFITS OTHER THAN PENSIONS (OPEB):**

The County recognizes two different health programs for retirees. Retirees had the option to participate in the County's regular health insurance plan or to join the Nevada Public Employees' Benefits Plan (PEBP). Each plan includes medical, dental and vision benefits for the retiree and the ability for the retiree to cover their spouse at their own cost. The legislature eliminated the option to join PEBP for County employees who retire after November 29, 2008.

Retirees may choose to stay on the County's regular health insurance plan. The retiree is required to pay the full amount of their coverage. However, the coverage rates are the same regardless of age, so the County contributes an implicit subsidy for retirees. The County renegotiates their health insurance plan on a regular basis, and may make plan modifications on rates or coverages accordingly

The County contributes to PEBP, an agent multiple employer defined healthcare plan. PEBP is administered by State and established pursuant to NRS 287.023. This plan is subject to amendment by the State of Nevada each biennium when the legislature is in session. Local governments are required to pay the same portion of cost of coverage for those persons joining PEBP that the State of Nevada pays for those persons retired from state service who have continued to participate in the plan

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

Storey County's total OPEB liability of \$31,698,789 was measured as of June 30, 2022, and was determined by an actuarial valuation as of that date.

Actuarial assumptions and other inputs. The total OPEB liability in the June 30, 2020 actuarial valuation was determined using the following actuarial assumptions and other inputs, applied to all periods included in the measurement, unless otherwise specified:

Inflation	2.50%
Salary Increases	3.00%
Discount rate	2.16%

The discount rate was based on the applicable municipal bond index

Mortality rates were based on MacLeod Watts Scale 2020

Changes in Total OPEB Liability

	PEBP	County	Total
Balance 6/30/21	\$ 502,414	\$ 27,225,688	\$ 27,728,102
Changes for the year			
Service Cost	-	3,253,831	\$ 3,253,831
Interest	10,857	670,635	\$ 681,492
Changes of benefit terms	-	-	\$ -
Differences between expected and actual experience	-	-	-
Changes in assumptions or other inputs	2,946	322,862	\$ 325,808
Benefit Payments	<u>(22,334)</u>	<u>(268,110)</u>	<u>\$ (290,444)</u>
Net changes	<u>\$ (8,531)</u>	<u>\$ 3,979,218</u>	<u>\$ 3,970,687</u>
Balance 6/30/22	<u>\$ 493,883</u>	<u>\$ 31,204,906</u>	<u>\$ 31,698,789</u>

*Sensitivity of the County's Proportionate Share of the OPEB Liability to Changes in the Discount Rate:* The following presents the County's proportionate share of the net pension liability calculated using the discount rate of 2.16%, as well as what the County's proportionate share of the net pension liability would be if it were calculated using a discount rate that is 1 percentage point lower (1.16%) or 1 percentage point higher (3.16%) than the current rate:

	<u>1% Decrease</u> <u>(1.16%)</u>	<u>Discount Rate</u> <u>(2.16%)</u>	<u>1% Increase</u> <u>(3.16%)</u>
Net OPEB liability	\$ 39,259,346	\$ 31,698,789	\$ 25,949,737

*Sensitivity of the County's Proportionate Share of the OPEB Liability to Changes in the Healthcare Cost Trend Rate:*

	<u>1% Decrease</u>	<u>Discount Rate</u> <u>Current Trend</u>	<u>1% Increase</u>
Net OPEB liability	\$ 25,038,087	\$ 31,698,789	\$ 40,833,591

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

For the year ended June 30, 2022, the County recognized OPEB expense of \$23,812,799. At June 30, 2022 the County reported deferred outflows of resources and deferred inflows of resources related to OPEB from the following sources

	Deferred Outflows of Resources	Deferred Inflows of Resources
Changes of assumptions or other inputs	\$ 7,805,782	\$ 1,986,323
Difference between expected and actual experience	-	5,308,366
Deferred contributions	<u>313,362</u>	<u>-</u>
Total	<u>\$ 8,119,144</u>	<u>\$ 7,294,689</u>

Amounts reported as deferred outflows of resources and deferred inflows of resources related to OPEB will be recognized in OPEB expense as follows

2023	\$ (125,470)
2024	(125,470)
2025	(125,470)
2026	(125,470)
2027	(125,470)
Thereafter	<u>1,138,443</u>
	<u>\$ 511,093</u>

**XIV. RELATED PARTY**

The County utilizes a marketing and public relations company, RAD Strategies, whose sole owner is married to the Director of Tourism. Safe guards have been put in to make sure the transactions are transparent. The VCTC board continues to hear and approve the payments in its annual budget. All monthly retainers fees and sent directly to the County Manager for approval before payment.

During the year ended June 30, 2022 the County paid the RAD Strategies \$86,912.

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

**XV. TAHOE-RENO INDUSTRIAL CENTER**

On February 2, 2000, Storey County, Nevada entered into a development agreement with the Tahoe-Reno Industrial Center LLC along with DP Operating Partnership, LP for the purposes of completing structures, including grading, infrastructure, and all public facilities related to the property owned by TRI, which consists of approximately 102,000 acres, of which approximately 9,000 acres is zoned for industrial usage within Storey County. The development agreement represents the commitment between Storey County and TRI to fund the capital infrastructure costs and local community services required by the project.

According to the agreements, TRI is responsible for the construction of the project public infrastructure, which shall be dedicated to and maintained by Storey County. Such infrastructure includes streets, sidewalks and streetlights, flood control, drainage channels, storm drains, basins, and other related facilities and County building complexes including fire stations, police stations, public works maintenance yards, and administrative offices. The County is not responsible for the construction, operation, and maintenance of the project private infrastructure such as community water and sewer facilities, railroad track and related facilities, landscaping of common areas, or private trails and parks and other property not dedicated to the County. The County is responsible for separately recording certain revenue and expenses directly attributable to the TRI project, approving reimbursable costs, and determining the net annual revenue reimbursement to TRI.

The agreements establish a revenue threshold that represents the annual fiscal year in which the TRI net revenue exceeds \$5,000,000. The revenue threshold must be met before any reimbursements are made to TRI for project related infrastructure costs. Once the revenue threshold is met, the County is responsible for reimbursing TRI for approved project vouchers up to 35% of annual net revenue. Such reimbursements are also limited to 5% of the project assessed valuation at the end of each year. The revenue threshold has been met.

The term of this agreement shall commence upon the effective date and shall expire fifty (50) years after the effective date, unless extended by written amendment executed by the County and Developer. A special revenue fund was established as of July 1, 2009, to provide payment to our TRI partners. A payment of \$2,500,000 was made by the TRI Payback Fund during the fiscal year.

Future allocations into the TRI Payback Fund will be a percentage of revenues directly attributed to TRI to include property taxes, business licenses, permits, inspection fees, and real property transfer taxes.



**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

**XVI. TESLA MOTORS**

On September 11, 2014, the Nevada State Legislature passed unanimously Senate Bill 1 which gave Tesla Motors \$1.25 billion dollars in tax abatements in exchange for Tesla investing \$3.5 billion dollars in the state within the first 10 years of the agreement. Under Section 13-3, transferable credits will be approved:

- (a) In the amount of \$12,500 for each qualified employee, up to a maximum of 6,000 qualified employees.
- (b) In the amount equal to 5% of the first \$1 billion of new capital investment in this State made collectively by the participants in the qualified project.
- (c) In an amount equal to 2.8% of the next \$2.5 billion on new capital investment in this State made collectively by the participants in the qualified project.

Section 15-2 provides abatement of 100% for the following:

- (a) For property taxes, for a duration of not more than 10 years after the date of which application is submitted and in an amount that equals the amount of the property taxes that would otherwise be owed by each participant for the qualified project;
- (b) For employer excise taxes, be for a duration of not more than 10 years after the date on which the application is submitted and in an amount that equals the amount of the employer excise taxes that would otherwise be owed by each participant for employees employed by the participant for the qualified project; and
- (c) For local sales and use tax, be for a duration of not more than 20 years after the date on which the application is submitted and in an amount that equals the amount of the local sales and use taxes that would otherwise be owed by each participant in the qualified project.

Under Section 25-36, the governing body of a county or city in which a qualified project is or is expected to be located to create an economic diversification district that includes with its boundaries the qualified project.

Section 35 notes "the governing body of the municipality may enter into an agreement with one or more of the owners of any interest in the property within a district, pursuant to which that owner would agree to make payments to the municipality or to another local government that provides services in the district, or to both, to defray, in whole or in part, the cost of local governmental services during the term of the use of any money pledged pursuant to Section 31 of this act. Such an agreement must specify the amount to be paid by the owner of the property interest, which may be stated as a specified amount per year or as an amount based upon any formula upon which the municipality and owner agree."

Subsequently, Ordinance No. 14-260 creating the Storey County Economic Diversification District No. 1 was signed by the County Commissioners on December 2, 2014, and Ordinance 15-263 providing partial abatements of permitting or licensing fees was signed by the County Commissioners was passed on June 16, 2015. Additional provisions of Senate Bill 1 also provided the ability to "abate" partially or in full permit fees and business license fees within the Economic Diversification District. Tesla and the County mutually negotiated a partial abatement of permit fees but no business license fees. These actions were codified into Ordinance 15-263. See separate schedule relating to additional tax abatements.

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

**XVII. Leases**

Storey County implemented "GASB 87 – Leases" in the fiscal year ended June 30, 2022. There was no restatement of fund balance required. Storey County has five material leases, with four having Storey County as lessor and one having Storey County as the lessee. All leases are accounted for in the General Fund. The County is a party to various other immaterial leases, which are not required to be disclosed in the financial statements

Verizon Cell Tower Site Lease

Storey County leases property for a cell tower site to Mobilitie Investment, LLC. The lease is a five-year lease, which commenced on October 1, 2008, with four optional five-year renewals and the final renewal term expiring on October 1, 2033. The monthly payment by increases by three percent upon each year. The County estimates that the lease will continue until October 1, 2033

Monthly lease payments were \$2,407 as of July 1, 2021 with an increase to \$2,479 in November 2021. Total lease payments received were \$27,055 for the fiscal year 2022. The lease payment has been amortized over the life of the lease including the optional renewals and lease payment increases with imputed interest at 1.28%. A lease receivable asset and the corresponding deferred inflow of resources at June 30, 2022 was \$372,878 and \$365,824, respectively. Interest income of \$4,520 was recognized in regards to this lease payment in the fiscal year ended June 30, 2022.

AT&T Cell Tower Site Lease

Storey County leases property for a cell tower site to New Cingular Wireless PSC, LLC. The lease is a five-year lease, which commenced on March 1, 2021, with four optional five-year renewals and the final renewal term expiring on March 1, 2046. The monthly payment by increases by three percent upon each year. The County estimates that the lease will continue until March 1, 2046

Monthly lease payments were \$1,900 as of July 1, 2021 with an increase to \$1,957 in April 2022. Total lease payments received were \$22,971 for the fiscal year 2022. The lease payment has been amortized over the life of the lease including the optional renewals and lease payment increases with imputed interest at 1.28%. A lease receivable asset and the corresponding deferred inflow of resources at June 30, 2022 was \$679,643 and \$657,512, respectively. Interest income of \$8,059 was recognized in regards to this lease payment in the fiscal year ended June 30, 2022.

Corner Bar Lease

Storey County leases property to VC Ponderosa Saloon LLC. The lease is a three-year lease, which commenced on January 1, 2019, with an optional two-year renewal and the final renewal term expiring on December 31, 2023. The monthly payment is \$1,800. The County estimates that the lease will continue until December 31, 2023

Monthly lease payments were \$1,800 as of July 1, 2021. Total lease payments received were \$21,600 for the fiscal year 2022. The lease payment has been amortized over the life of the lease including the optional renewals and lease payment increases with imputed interest at 1.28%. A lease receivable asset and the corresponding deferred inflow of resources at June 30, 2022 was \$32,074 and \$31,904, respectively. Interest income of \$500 was recognized in regards to this lease payment in the fiscal year ended June 30, 2022.

**STOREY COUNTY, NEVADA**  
**NOTES TO FINANCIAL STATEMENTS**  
**JUNE 30, 2022**

**XVII. Leases**

Corner Bar Lease

Storey County leases property to Divide LLC. The lease is a two-year lease, which commenced on August 6, 2020, with an optional two-year renewal and the final renewal term expiring on August 6, 2024. The monthly payment is \$1,500. The County estimates that the lease will continue until August 6, 2024.

Monthly lease payments were \$1,500 as of July 1, 2021. Total lease payments received were \$18,000 for the fiscal year 2022. The lease payment has been amortized over the life of the lease including the optional renewals and lease payment increases with imputed interest at 1.28%. A lease receivable asset and the corresponding deferred inflow of resources at June 30, 2022 was \$36,985 and \$36,790, respectively. Interest income of \$536 was recognized in regards to this lease payment in the fiscal year ended June 30, 2022.

Body Camera Lease

Storey County leases body worn cameras from FEI-Lenslock, Inc.. The lease is a five-year lease, which commenced on September 1, 2020, with an optional one-year renewal. The annual payment is \$18,380. The County estimates that the lease will continue until August 31, 2025.

Annual lease payments were \$18,380 as of July 1, 2021. Total lease payments received were \$18,380 for the fiscal year 2022. The lease payment has been amortized over the life of the lease including the optional renewals and lease payment increases with imputed interest at 1.28%. A lease payable and the corresponding capital assets at June 30, 2022 was \$53,750 and \$56,142, respectively. Interest expense of \$154 was recognized in regards to this lease payment in the fiscal year ended June 30, 2022.

Discretely Presented Component Untis

TRIGID leases property for a cell tower site to Verizon Wireless. The lease is a five-year lease, which commenced on November 1, 2017, with four optional five-year renewals and the final renewal term expiring on November 1, 2042. The monthly payment by increases by three percent upon each year. The County estimates that the lease will continue until March 1, 2046.

Monthly lease payments were \$1,050 as of July 1, 2021 with an increase to \$1,078 in April 2022. Total lease payments received were \$12,791 for the fiscal year 2022. The lease payment has been amortized over the life of the lease including the optional renewals and lease payment increases with imputed interest at 1.28%. A lease receivable asset and the corresponding deferred inflow of resources at June 30, 2022 was \$301,068 and \$295,787, respectively. Interest income of \$9,206 was recognized in regards to this lease payment in the fiscal year ended June 30, 2022.

**XVIII Subsequent Event**

After several years of litigation in the bankruptcy matter, in April 2022 a settlement conference was conducted by a sitting Bankruptcy Judge. Storey actively participated in the settlement process. A settlement was reached between and among Storey, the Bankruptcy Estate and the Purchasers. As of June 30, 2022, the terms of the settlement had been agreed upon; however, it was not approved by the Bankruptcy Court until after June 30, 2022. The Settlement required a payment by Storey County in the amount of \$75,000, which payment was made after June 30, 2022.

STOREY COUNTY, NEVADA  
 NOTES TO FINANCIAL STATEMENTS  
 JUNE 30, 2022

XIX. **TAX ABATEMENTS**

Storey County has agreements with businesses within the Industrial Park for property tax, sales tax, plan review and permit fee abatement agreements. These agreements range from 5 years to 20 years depending on the individual abatement. The following is a list of those abatements.

**State of Nevada Governor's Office on Economic Development (GOED)**

Chapter 271B of the Nevada Revised Statutes created an Economic Diversification District for which Storey County is a participant. Tesla filed as a Lead participant within the Statue and was granted full abatements on Property Tax for 10 years and Sales and Use Tax for 20 years. The effect of this abatement is as follows:

**PERSONAL PROPERTY TAX**

<u>ASSESSED VALUE</u>	<u>ABATEMENT</u>	<u>TOTAL ABATEMENT</u>
\$872,836,012	100%	\$872,836,012

**REAL PROPERTY TAX**

<u>ASSESSED VALUE</u>	<u>ABATEMENT</u>	<u>TOTAL ABATEMENT</u>
\$212,762,006	100%	\$212,762,006

In addition, GOED has permitted several companies to abate a certain portion of their personal and Real Property

**PERSONAL PROPERTY TAX**

<u>ASSESSED VALUE</u>	<u>ABATEMENT</u>	<u>TOTAL ABATEMENT</u>
\$13,246,887	64%	\$8,470,413

**REAL PROPERTY TAX**

<u>ASSESSED VALUE</u>	<u>ABATEMENT</u>	<u>TOTAL ABATEMENT</u>
\$421,963	50%	\$210,981

**Nevada Governor's Office of Energy (GOE)**

The GOE administers the green building tax abatement program based on criteria set forth in the LEED of Green Globes rating system and certification from the U.S. Green Building Council. This abatement is as follows:

**LEED ABATEMENTS**

**PRE-ABATEMENT**

<u>TAX AMOUNT</u>	<u>ABATEMENT</u>	<u>TOTAL ABATEMENT</u>
\$284,165	18%	\$49,151

**STOREY COUNTY, NEVADA  
COMBINING BALANCE SHEET  
NONMAJOR GOVERNMENTAL FUNDS  
JUNE 30, 2022**

	SPECIAL REVENUE						
	EQUIPMENT ACQUISITION	JUSTICE COURT	DRUG COURT	INDIGENT MEDICAL	PARK TAX	MUTUAL AID	EMERGENCY MITIGATION
<b>ASSETS</b>							
Cash	\$ 3,484,187	\$ 233,697	\$ 50	\$ 562,760	\$ 92,243	\$ 1,000,141	\$ 493,288
Property taxes receivable	6,986	-	-	1,398	-	-	-
Accounts receivable	-	-	-	-	-	-	-
Prepaid expenses	-	-	-	-	-	-	-
<b>Total Assets</b>	<u>\$ 3,491,173</u>	<u>\$ 233,697</u>	<u>\$ 50</u>	<u>\$ 564,158</u>	<u>\$ 92,243</u>	<u>\$ 1,000,141</u>	<u>\$ 493,288</u>
<b>LIABILITIES</b>							
Accounts payable	\$ 110,591	\$ 186,983	\$ 20	\$ 2,880	\$ -	\$ 9,502	\$ 19
Unearned revenue	-	-	-	-	-	-	-
<b>Total Liabilities</b>	<u>\$ 110,591</u>	<u>\$ 186,983</u>	<u>\$ 20</u>	<u>\$ 2,880</u>	<u>\$ -</u>	<u>\$ 9,502</u>	<u>\$ 19</u>
<b>DEFERRED INFLOWS OF RESOURCES</b>							
Unavailable resources property taxes	\$ 260	\$ -	\$ -	\$ 1,295	\$ -	\$ -	\$ -
<b>FUND BALANCE</b>							
Nonspendable	-	-	-	-	-	-	-
Unassigned	3,380,322	46,714	30	559,983	92,243	990,639	493,269
<b>Total Fund Balance</b>	<u>3,380,322</u>	<u>46,714</u>	<u>30</u>	<u>559,983</u>	<u>92,243</u>	<u>990,639</u>	<u>493,269</u>
<b>Total Liabilities, Deferred Inflows of Resources and Fund Balances</b>	<u>\$ 3,491,173</u>	<u>\$ 233,697</u>	<u>\$ 50</u>	<u>\$ 564,158</u>	<u>\$ 92,243</u>	<u>\$ 1,000,141</u>	<u>\$ 493,288</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA  
COMBINING BALANCE SHEET  
NONMAJOR GOVERNMENTAL FUNDS  
JUNE 30, 2022**

	SPECIAL REVENUE						
	INDIGENT ACCIDENT	TECHNOLOGY	FEDERAL AND STATE GRANTS	FIRE EMERGENCY	STABILISATION FUND	GENERIC MARKER TESTING FUND	PIPER'S OPERA HOUSE
<u>ASSETS</u>							
Cash	\$ 94,023	\$ 456,130	\$ 72,219	250,000	\$ 1,000,000	\$ 78,655	\$ 139,637
Property taxes receivable	-	-	-	-	-	-	-
Accounts receivable	-	-	-	-	-	-	-
Prepaid expenses	-	-	-	-	-	-	1,000
Total Assets	<u>\$ 94,023</u>	<u>\$ 456,130</u>	<u>\$ 72,219</u>	<u>\$ 250,000</u>	<u>\$ 1,000,000</u>	<u>\$ 78,655</u>	<u>\$ 140,637</u>
<u>LIABILITIES</u>							
Accounts payable	\$ 20,402	\$ 3,310	\$ 160	\$ -	\$ -	\$ 318	8,968
Unearned revenue	-	-	-	-	-	-	22,910
Total Liabilities	<u>20,402</u>	<u>3,310</u>	<u>160</u>	<u>-</u>	<u>-</u>	<u>318</u>	<u>31,878</u>
<u>DEFERRED INFLOWS OF RESOURCES</u>							
Unavailable resources property taxes	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
<u>FUND BALANCE</u>							
Nonspendable	-	-	-	-	-	-	-
Unassigned	73,621	452,820	72,059	250,000	1,000,000	78,337	108,759
Total Fund Balance	<u>73,621</u>	<u>452,820</u>	<u>72,059</u>	<u>250,000</u>	<u>1,000,000</u>	<u>78,337</u>	<u>108,759</u>
Total Liabilities, Deferred Inflows of Resources and Fund Balances	<u>\$ 94,023</u>	<u>\$ 456,130</u>	<u>\$ 72,219</u>	<u>\$ 250,000</u>	<u>\$ 1,000,000</u>	<u>\$ 78,655</u>	<u>\$ 140,637</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA  
COMBINING BALANCE SHEET  
NONMAJOR GOVERNMENTAL FUNDS  
JUNE 30, 2022**

	SPECIAL REVENUE		CAPITAL PROJECTS			TOTAL
	FIRE GRANTS	CAPITAL PROJECTS	INFRASTRUCTURE FUND	VIRGINIA CITY RAIL PROJECT	FIRE CAP PROJECTS	
<b>ASSETS</b>						
Cash	\$ 46,441	\$ 2,797,192	\$ 2,493,271	\$ 1,662,535	\$ 660,202	\$ 15,616,671
Property taxes receivable	-	-	-	-	-	8,384
Accounts receivable	-	-	145,292	145,021	-	290,313
Prepaid expenses	-	-	-	-	-	1,000
<b>Total Assets</b>	<b>\$ 46,441</b>	<b>\$ 2,797,192</b>	<b>\$ 2,638,563</b>	<b>\$ 1,807,556</b>	<b>\$ 660,202</b>	<b>\$ 15,916,368</b>
<b>LIABILITIES</b>						
Accounts payable	\$ 37,881	\$ 35,365	\$ 148,238	\$ 3,848	\$ 539	\$ 569,024
Unearned revenue	-	-	-	-	-	22,910
<b>Total Liabilities</b>	<b>\$ 37,881</b>	<b>\$ 35,365</b>	<b>\$ 148,238</b>	<b>\$ 3,848</b>	<b>\$ 539</b>	<b>\$ 591,934</b>
<b>DEFERRED INFLOWS OF RESOURCES</b>						
Unavailable resources property taxes	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,555
<b>FUND BALANCE</b>						
Nonspendable	-	-	-	-	-	-
Unassigned	8,560	2,761,827	2,490,325	1,803,708	659,663	15,322,879
<b>Total Fund Balance</b>	<b>8,560</b>	<b>2,761,827</b>	<b>2,490,325</b>	<b>1,803,708</b>	<b>659,663</b>	<b>15,322,879</b>
<b>Total Liabilities, Deferred Inflows of Resources and Fund Balances</b>	<b>\$ 46,441</b>	<b>\$ 2,797,192</b>	<b>\$ 2,638,563</b>	<b>\$ 1,807,556</b>	<b>\$ 660,202</b>	<b>\$ 15,916,368</b>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**COMBINING STATEMENT OF REVENUES, EXPENDITURES AND**  
**CHANGES IN FUND BALANCE**  
**NONMAJOR GOVERNMENTAL FUNDS**  
**FOR THE YEAR ENDED JUNE 30, 2022**

	SPECIAL REVENUE						
	EQUIPMENT ACQUISITION	JUSTICE COURT	DRUG COURT	INDIGENT MEDICAL	PARK TAX	MUTUAL AID	EMERGENCY MITIGATION
<b><u>REVENUE</u></b>							
Taxes	\$ 411,100	\$ -	\$ -	\$ 84,660	\$ -	\$ -	\$ -
Intergovernmental	-	-	-	-	-	-	-
Charges for services	-	-	-	-	3,250	-	-
Fine and forfeitures	-	41,356	440	-	-	-	-
Other revenues	75,494	-	-	-	468	406,936	412,302
Total Revenues	<u>486,594</u>	<u>41,356</u>	<u>440</u>	<u>84,660</u>	<u>3,718</u>	<u>406,936</u>	<u>412,302</u>
<b><u>EXPENDITURES</u></b>							
Current							
General government	234,919	-	-	-	-	-	-
Public safety	-	-	-	-	-	464,669	30,576
Judicial	-	21,121	440	-	-	-	-
Culture and recreation	-	-	-	-	-	-	-
Welfare	-	-	-	43,303	-	-	-
Intergovernmental	-	-	-	-	-	-	-
Total Expenditures	<u>234,919</u>	<u>21,121</u>	<u>440</u>	<u>43,303</u>	<u>-</u>	<u>464,669</u>	<u>30,576</u>
Excess (deficiency) of revenues over expenditures	251,675	20,235	-	41,357	3,718	(57,733)	381,726
<b><u>OTHER FINANCIAL SOURCES (USES)</u></b>							
Transfers	(26,000)	-	-	-	-	(500,000)	78,000
Transfers to proprietary funds	-	-	-	-	-	-	-
Debt service	-	-	-	-	-	-	-
Bond proceeds	-	-	-	-	-	-	-
Total Other Financing Sources (Uses)	<u>(26,000)</u>	<u>-</u>	<u>-</u>	<u>-</u>	<u>-</u>	<u>(500,000)</u>	<u>78,000</u>
Excess (deficiency) of revenue and other Financing Sources (Uses) over Expenditures	225,675	20,235	-	41,357	3,718	(557,733)	459,726
Fund Balance, July 1	<u>3,154,647</u>	<u>26,479</u>	<u>30</u>	<u>518,626</u>	<u>88,525</u>	<u>1,548,372</u>	<u>33,543</u>
Fund Balance, June 30	<u>\$ 3,380,322</u>	<u>\$ 46,714</u>	<u>\$ 30</u>	<u>\$ 559,983</u>	<u>\$ 92,243</u>	<u>\$ 990,639</u>	<u>\$ 493,269</u>

The notes to the financial statements are an integral part of this statement



STOREY COUNTY, NEVADA  
 COMBINING STATEMENT OF REVENUES, EXPENDITURES AND  
 CHANGES IN FUND BALANCE  
 NONMAJOR GOVERNMENTAL FUNDS  
 FOR THE YEAR ENDED JUNE 30, 2022

	SPECIAL REVENUE						
	INDIGENT ACCIDENT	TECHNOLOGY	FEDERAL AND STATE GRANTS	FIRE EMERGENCY	STABILIZATION FUND	GENERIC MARKER TESTING FUND	PIPER'S OPERA HOUSE
<u>REVENUE</u>							
Taxes	\$ 128,377	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Intergovernmental	-	-	101,038	-	-	-	3,000
Charges for services	-	220,112	-	-	-	-	109,890
Fine and forfeitures	-	-	-	-	-	11,084	-
Other revenues	-	2,318	-	-	-	-	22,460
Total Revenues	<u>128,377</u>	<u>222,430</u>	<u>101,038</u>	<u>-</u>	<u>-</u>	<u>11,084</u>	<u>135,350</u>
<u>EXPENDITURES</u>							
Current							
General government	-	65,567	-	-	-	-	223,307
Public safety	-	-	133,711	-	-	-	-
Judicial	-	-	-	-	-	4,199	-
Culture and recreation	-	-	-	-	-	-	-
Welfare	122,671	-	-	-	-	-	-
Intergovernmental	-	-	-	-	-	-	-
Total Expenditures	<u>122,671</u>	<u>65,567</u>	<u>133,711</u>	<u>-</u>	<u>-</u>	<u>4,199</u>	<u>223,307</u>
Excess (deficiency) of revenues over expenditures	5,706	156,863	(32,673)	-	-	6,885	(87,957)
<u>OTHER FINANCIAL SOURCES (USES)</u>							
Transfers	-	-	-	42,859	-	-	110,000
Transfers to proprietary funds	-	-	-	-	-	-	-
Debt service	-	-	-	-	-	-	-
Bond proceeds	-	-	-	-	-	-	-
Total Other Financing Sources (Uses)	<u>-</u>	<u>-</u>	<u>-</u>	<u>42,859</u>	<u>-</u>	<u>-</u>	<u>110,000</u>
Excess (deficiency) of revenue and other financing Sources (Uses) over Expenditures	5,706	156,863	(32,673)	42,859	-	6,885	22,043
Fund Balance, July 1	<u>67,915</u>	<u>295,957</u>	<u>104,732</u>	<u>207,141</u>	<u>1,000,000</u>	<u>71,452</u>	<u>86,716</u>
Fund Balance, June 30	<u>\$ 73,621</u>	<u>\$ 452,820</u>	<u>\$ 72,059</u>	<u>\$ 250,000</u>	<u>\$ 1,000,000</u>	<u>\$ 78,337</u>	<u>\$ 108,759</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**COMBINING STATEMENT OF REVENUES, EXPENDITURES AND**  
**CHANGES IN FUND BALANCE**  
**NONMAJOR GOVERNMENTAL FUNDS**  
**FOR THE YEAR ENDED JUNE 30, 2022**

	SPECIAL REVENUE		CAPITAL PROJECTS			TOTAL
	FIRE GRANTS	CAPITAL PROJECTS	INFRASTRUCTURE FUND	VIRGINIA CITY RAIL PROJECT	FIRE CAP PROJECTS	
<b>REVENUE</b>						
Taxes	\$ -	\$ -	\$ -	\$ 778,689	\$ -	\$ 1,402,826
Intergovernmental	1,055,473	-	752,550	-	-	1,912,061
Charges for services	-	-	-	-	-	333,252
Fine and forfeitures	-	-	-	-	-	52,880
Other revenues	-	93,733	-	-	9,289	1,023,000
<b>Total Revenues</b>	<b>1,055,473</b>	<b>93,733</b>	<b>752,550</b>	<b>778,689</b>	<b>9,289</b>	<b>4,724,019</b>
<b>EXPENDITURES</b>						
Current						
General government	-	781,255	527,095	-	-	1,832,143
Public safety	1,096,913	-	-	-	93,684	1,819,553
Judicial	-	-	-	-	-	25,760
Culture and recreation	-	-	-	270,212	-	270,212
Welfare	-	-	-	-	-	165,974
Intergovernmental	-	-	-	-	-	-
<b>Total Expenditures</b>	<b>1,096,913</b>	<b>781,255</b>	<b>527,095</b>	<b>270,212</b>	<b>93,684</b>	<b>4,113,642</b>
Excess (deficiency) of revenues over expenditures	(41,440)	(687,522)	225,455	508,477	(84,395)	610,377
<b>OTHER FINANCIAL SOURCES (USES)</b>						
Transfers	50,000	2,000,000	-	-	407,141	2,162,000
Transfers to proprietary funds	-	-	-	-	-	-
Debt service	-	-	-	(897,927)	-	(897,927)
Bond proceeds	-	-	-	-	-	-
<b>Total Other Financing Sources (Uses)</b>	<b>50,000</b>	<b>2,000,000</b>	<b>-</b>	<b>(897,927)</b>	<b>407,141</b>	<b>1,264,073</b>
Excess (deficiency) of revenue and other financing Sources (Uses) over Expenditures	8,560	1,312,478	225,455	(389,450)	322,746	1,874,450
Fund Balance, July 1	-	1,449,349	2,264,870	2,193,158	336,917	13,448,429
Fund Balance, June 30	\$ 8,560	\$ 2,761,827	\$ 2,490,325	\$ 1,803,708	\$ 659,663	\$ 15,322,879

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
EQUIPMENT ACQUISITION SPECIAL REVENUE FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

<u>REVENUE</u>	<u>ORIGINAL AND FINAL BUDGETED AMOUNTS</u>	<u>ACTUAL AMOUNTS</u>	<u>VARIANCE TO FINAL BUDGET</u>
Taxes			
Property taxes	\$ 324,922	\$ 411,100	\$ 86,178
Other revenues			
Equipment sales		20,586	
Insurance claims		36,145	
Interest	<u>3,700</u>	<u>18,763</u>	<u>15,063</u>
Total Revenues	<u>328,622</u>	<u>486,594</u>	<u>101,241</u>
<u>EXPENDITURES</u>			
General government			
Capital outlay	<u>257,720</u>	<u>234,919</u>	<u>22,801</u>
Total Expenditures	<u>257,720</u>	<u>234,919</u>	<u>22,801</u>
Excess (Deficiency) of Revenues over Expenditures	<u>70,902</u>	<u>251,675</u>	<u>180,773</u>
<u>OTHER FINANCING SOURCES (USES)</u>			
Transfer out - Tri Payback	<u>(26,000)</u>	<u>(26,000)</u>	<u>-</u>
Excess (Deficiency) of Revenues and Other Financing Sources (Uses) over Expenditures	44,902	225,675	180,773
Fund Balance, July 1	<u>2,995,329</u>	<u>3,154,647</u>	<u>159,318</u>
Fund Balance, June 30	<u>\$ 3,040,231</u>	<u>\$ 3,380,322</u>	<u>\$ 340,091</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
JUSTICE COURT SPECIAL REVENUE FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
Fines			
Justice court fines	\$ 67,000	\$ 41,356	\$ (25,644)
<u>EXPENDITURES</u>			
Judicial			
Services and supplies	68,500	21,121	47,379
Capital outlay	-	-	-
Total Expenditures	<u>68,500</u>	<u>21,121</u>	<u>47,379</u>
Excess (Deficiency) of Revenues over Expenditures	<u>(1,500)</u>	<u>20,235</u>	<u>21,735</u>
Fund Balance, July 1	<u>19,969</u>	<u>26,479</u>	<u>6,510</u>
Fund Balance, June 30	<u>\$ 18,469</u>	<u>\$ 46,714</u>	<u>\$ 28,245</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**DRUG COURT SPECIAL REVENUE FUND**  
**STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE**  
**BUDGET AND ACTUAL**  
**FOR THE YEAR ENDED JUNE 30, 2022**

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
Fines and forfeits			
Drug court fees	\$ 400	\$ 440	\$ 40
 <u>EXPENDITURES</u>			
Judicial			
Services and supplies	400	440	(40)
Excess (Deficiency) of Revenues over Expenditures	-	-	-
Fund Balance, July 1	30	30	-
Fund Balance, June 30	\$ 30	\$ 30	\$ -

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
INDIGENT MEDICAL SPECIAL REVENUE FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

<u>REVENUE</u>	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
Taxes			
Property taxes	\$ 65,164	\$ 84,660	\$ 19,496
<u>EXPENDITURES</u>			
Welfare			
Services and supplies	200,000	43,303	156,697
Excess (Deficiency) of Revenues over Expenditures	(134,836)	41,357	176,193
Fund Balance, July 1	390,300	518,626	128,326
Fund Balance, June 30	\$ 255,464	\$ 559,983	\$ 304,519

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
PARK TAX SPECIAL REVENUE FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

<u>REVENUE</u>	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
Charges for services			
Park fees	\$ 1,500	\$ 3,250	\$ 1,750
Other revenues			
Interest	100	468	368
Total Revenues	<u>1,600</u>	<u>3,718</u>	<u>2,118</u>
<u>EXPENDITURES</u>			
Culture and recreation			
Services and supplies	<u>15,000</u>	-	<u>15,000</u>
Excess (Deficiency) of Revenues over Expenditures	<u>(13,400)</u>	<u>3,718</u>	<u>17,118</u>
Fund Balance, July 1	<u>85,737</u>	<u>88,525</u>	<u>2,788</u>
Fund Balance, June 30	<u>\$ 72,337</u>	<u>\$ 92,243</u>	<u>\$ 19,906</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
MUTUAL AID SPECIAL REVENUE FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

<u>REVENUE</u>	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
Other revenues				
Fire suppression	\$ 485,600	\$ 485,600	\$ 406,936	\$ (78,664)
Total Revenues	<u>485,600</u>	<u>485,600</u>	<u>406,936</u>	<u>(78,664)</u>
 <u>EXPENDITURES</u>				
Public safety				
Salaries and wages	345,000	345,000	294,055	50,945
Benefits	30,300	88,300	76,957	11,343
Services and supplies	75,800	75,800	71,481	4,319
Capital outlay	34,500	34,500	22,176	12,324
Total Expenditures	<u>485,600</u>	<u>543,600</u>	<u>464,669</u>	<u>78,931</u>
Excess (Deficiency) of Revenues over Expenditures	<u>-</u>	<u>(58,000)</u>	<u>(57,733)</u>	<u>267</u>
 <u>OTHER FINANCING SOURCES (USES)</u>				
Transfers out	<u>(500,000)</u>	<u>(500,000)</u>	<u>(500,000)</u>	<u>-</u>
Excess(Deficiency) of Revenues and Other Financing Sources (Uses) over Expenditures	<u>(500,000)</u>	<u>(558,000)</u>	<u>(557,733)</u>	<u>267</u>
Fund Balance, July 1	<u>1,179,240</u>	<u>1,179,240</u>	<u>1,548,372</u>	<u>369,132</u>
Fund Balance, June 30	<u>\$ 679,240</u>	<u>\$ 621,240</u>	<u>\$ 990,639</u>	<u>\$ 311,399</u>

The notes to the financial statements are an integral part of this statement



STOREY COUNTY, NEVADA  
EMERGENCY MITIGATION SPECIAL REVENUE FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
Grants	\$ -	\$ 412,302	\$ 412,302
<u>EXPENDITURES</u>			
Public Safety			
Services and supplies	<u>78,000</u>	<u>30,576</u>	<u>47,424</u>
Excess (Deficiency) of Revenues over Expenditures	<u>(78,000)</u>	<u>381,726</u>	<u>459,726</u>
<u>OTHER FINANCING SOURCES (USES)</u>			
Transfers in	<u>78,000</u>	<u>78,000</u>	<u>-</u>
Excess(Deficiency) of Revenues and Other Financing Sources (Uses) over Expenditures	<u>-</u>	<u>459,726</u>	<u>459,726</u>
Fund Balance, July 1	<u>31,194</u>	<u>33,543</u>	<u>2,349</u>
Fund Balance, June 30	<u>\$ 31,194</u>	<u>\$ 493,269</u>	<u>\$ 462,075</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
INDIGENT ACCIDENT SPECIAL REVENUE FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

<u>REVENUE</u>	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
Taxes				
Property taxes	\$ 89,297	\$ 89,297	\$ 128,377	\$ 39,080
<u>EXPENDITURES</u>				
Welfare				
Services and supplies	80,000	116,000	122,671	(6,671)
Excess (Deficiency) of Revenues over Expenditures	9,297	(26,703)	5,706	32,409
Fund Balance, July 1	26,802	26,802	67,915	41,113
Fund Balance, June 30	\$ 36,099	\$ 99	\$ 73,621	\$ 73,522

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 TECHNOLOGY SPECIAL REVENUE FUND  
 STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

<u>REVENUE</u>	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
Charges for services			
Technology fees	\$ 57,100	\$ 220,112	\$ 163,012
Other revenues			
Interest income	-	2,318	2,318
Total Revenues	<u>57,100</u>	<u>222,430</u>	<u>165,330</u>
<u>EXPENDITURES</u>			
General government			
Services and supplies	<u>105,000</u>	<u>65,567</u>	<u>39,433</u>
Excess (Deficiency) of Revenues over Expenditures	<u>(47,900)</u>	<u>156,863</u>	<u>204,763</u>
Fund Balance, July 1	<u>196,343</u>	<u>295,957</u>	<u>99,614</u>
Fund Balance, June 30	<u>\$ 148,443</u>	<u>\$ 452,820</u>	<u>\$ 304,377</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 FEDERAL/STATE GRANT SPECIAL REVENUE FUND  
 STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

<u>REVENUE</u>	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
Intergovernmental			
Federal grants	\$ 136,227	\$ 41,461	\$ (94,766)
State grants	256,591	59,577	(197,014)
Total Revenues	<u>392,818</u>	<u>101,038</u>	<u>(291,780)</u>
 <u>EXPENDITURES</u>			
Culture and recreation			
Services and supplies	-	-	-
Public safety			
Salaries and wages	-	-	-
Employee benefits	-	-	-
Services and supplies	496,724	133,711	363,013
Intergovernmental - State			
Services and supplies	-	-	-
Total Expenditures	<u>496,724</u>	<u>133,711</u>	<u>363,013</u>
Excess (Deficiency) of Revenues over Expenditures	<u>(103,906)</u>	<u>(32,673)</u>	<u>71,233</u>
 Fund Balance, July 1	 <u>119,625</u>	 <u>104,732</u>	 <u>(14,893)</u>
Fund Balance, June 30	<u>\$ 15,719</u>	<u>\$ 72,059</u>	<u>\$ 56,340</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 FIRE EMERGENCY SPECIAL REVENUE FUND  
 STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
Charges for services	\$ -	\$ -	\$ -
<u>EXPENDITURES</u>			
Public Safety			
Services and supplies	250,000	-	250,000
Excess (Deficiency) of Revenues over Expenditures	(250,000)	-	250,000
<u>OTHER FINANCING SOURCES (USES)</u>			
Transfers in	42,859	42,859	78,000
Excess(Deficiency) of Revenues and Other Financing Sources (Uses) over Expenditures	(207,141)	42,859	328,000
Fund Balance, July 1	207,141	207,141	-
Fund Balance, June 30	\$ -	\$ 250,000	\$ 250,000

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 STABILIZATION SPECIAL REVENUE FUND  
 STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
None	\$ -	\$ -	\$ -
<u>EXPENDITURES</u>			
Capital outlay	400,000	-	400,000
Excess (Deficiency) of Revenues over Expenditures	(400,000)	-	400,000
Fund Balance, July 1	600,000	1,000,000	400,000
Fund Balance, June 30	<u>\$ 200,000</u>	<u>\$ 1,000,000</u>	<u>\$ 800,000</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
GENETIC MARKER TESTING SPECIAL REVENUE FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
Fines and forfeitures	\$ 11,100	\$ 11,084	\$ (16)
<u>EXPENDITURES</u>			
Judicial			
Services and supplies	6,000	4,199	1,801
Excess (Deficiency) of Revenues over Expenditures	<u>5,100</u>	<u>6,885</u>	<u>1,785</u>
Fund Balance, July 1	<u>65,655</u>	<u>71,452</u>	<u>5,797</u>
Fund Balance, June 30	<u>\$ 70,755</u>	<u>\$ 78,337</u>	<u>\$ 7,582</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 PIPER'S OPERA HOUSE  
 STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

<u>REVENUE</u>	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
Intergovernmental			
State grants	\$ 10,000	\$ 3,000	\$ (7,000)
Charges for services			
Cap ticket sales	122,000	109,890	(12,110)
Other revenues			
Contributions	1,000	2,026	1,026
Rents	20,000	20,350	350
Merchandise sales	3,000	84	(2,916)
Total Revenues	<u>156,000</u>	<u>135,350</u>	<u>(20,650)</u>
<u>EXPENDITURES</u>			
General government			
Salaries and wages	109,343	85,651	23,692
Employee benefits	51,091	40,320	10,771
Services and supplies	121,223	97,336	23,887
Capital outlay	-	-	-
Total Expenditures	<u>281,657</u>	<u>223,307</u>	<u>58,350</u>
Excess (Deficiency) of Revenues over Expenditures	<u>(125,657)</u>	<u>(87,957)</u>	<u>37,700</u>
<u>OTHER FINANCING SOURCES (USES)</u>			
Transfers in	110,000	110,000	-
Excess(Deficiency) of Revenues and Other Financing Sources (Uses) over Expenditures	(15,657)	22,043	(37,700)
Fund Balance, July 1	<u>31,272</u>	<u>86,716</u>	<u>55,444</u>
Fund Balance, June 30	<u>\$ 15,615</u>	<u>\$ 108,759</u>	<u>\$ 93,144</u>

The notes to the financial statements are an integral part of this statement



STOREY COUNTY, NEVADA  
 FIRE GRANT SPECIAL REVENUE FUND  
 STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

<u>REVENUE</u>	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
Intergovernmental				
Federal grants	\$ 74,950	\$ 74,950	\$ -	\$ (74,950)
State grants	<u>267,188</u>	<u>267,188</u>	<u>65,633</u>	<u>(201,555)</u>
Total Revenues	<u>342,138</u>	<u>342,138</u>	<u>65,633</u>	<u>(276,505)</u>
 <u>EXPENDITURES</u>				
Public safety				
Salaries and wages	300,876	406,876	365,921	40,955
Employee benefits	170,581	223,581	189,550	34,031
Services and supplies	781,860	377,860	297,375	80,485
Capital outlay	-	245,000	244,067	933
Total Expenditures	<u>1,253,317</u>	<u>1,253,317</u>	<u>1,096,913</u>	<u>156,404</u>
Excess (Deficiency) of Revenues over Expenditures	<u>(911,179)</u>	<u>(911,179)</u>	<u>(1,031,280)</u>	<u>(120,101)</u>
 <u>OTHER FINANCING SOURCES (USES)</u>				
Other grants	883,487	883,487	989,840	106,353
Transfers in	<u>50,000</u>	<u>50,000</u>	<u>50,000</u>	<u>-</u>
Excess(Deficiency) of Revenues and Other Financing Sources (Uses) over Expenditures	22,308	22,308	8,560	(13,748)
Fund Balance, July 1	<u>-</u>	<u>-</u>	<u>-</u>	<u>-</u>
Fund Balance, June 30	<u>\$ 22,308</u>	<u>\$ 22,308</u>	<u>\$ 8,560</u>	<u>\$ (120,101)</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
CAPITAL PROJECTS FUND  
STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
Capital outlay reimbursement	\$ 93,000	\$ 93,733	\$ 733
Other	-	-	-
Total revenue	93,000	93,733	733
<u>EXPENDITURES</u>			
General Government			
Capital outlay	1,876,000	781,255	1,094,745
Debt service	-	-	-
Interest expense	-	-	-
Total Expenditures	1,876,000	781,255	1,094,745
Excess (Deficiency) of Revenues over Expenditures	(1,783,000)	(687,522)	(1,094,012)
<u>OTHER FINANCING SOURCES (USES)</u>			
Transfers to proprietary funds	-	-	-
Infrastructure capital projects fund	-	-	-
Roads fund	-	-	-
General government - Other	2,000,000	2,000,000	-
Excess (Deficiency) of Revenues and Other Financing Sources (Uses) over Expenditures	217,000	1,312,478	1,095,478
Fund Balance, July 1	1,946,033	1,449,349	(496,684)
Fund Balance, June 30	\$ 2,163,033	\$ 2,761,827	\$ 598,794

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 INFRASTRUCTURE CAPITAL PROJECTS FUND  
 STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
Intergovernmental			
1/4% Optional sales tax	\$ 500,000	\$ 752,550	\$ 252,550
Other revenues			
Interest income	-	-	3,801
Total Revenues	<u>500,000</u>	<u>752,550</u>	<u>88,200</u>
<u>EXPENDITURES</u>			
General government			
Capital outlay	<u>1,219,228</u>	<u>527,095</u>	<u>692,133</u>
Excess (Deficiency) of Revenues over Expenditures	<u>(719,228)</u>	<u>225,455</u>	<u>944,683</u>
<u>OTHER FINANCING SOURCES (USES)</u>			
Transfers to Capital projects funds	-	-	-
Excess (Deficiency) of Revenues and Other Financing Sources (Uses) over Expenditures	<u>(719,228)</u>	<u>225,455</u>	<u>944,683</u>
Fund Balance, July 1	<u>2,193,804</u>	<u>2,264,870</u>	<u>71,066</u>
Fund Balance, June 30	<u>\$ 1,474,576</u>	<u>\$ 2,490,325</u>	<u>\$ 1,015,749</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 VIRGINIA CITY RAIL CAPITAL PROJECTS FUND  
 STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
VC rail tax	\$ 350,000	\$ 778,689	\$ 428,689
<u>EXPENDITURES</u>			
Culture and Recreation			
Capital outlay	-	20,212	(20,212)
Interlock support	250,000	250,000	-
Excess (Deficiency) of Revenues over Expenditures	100,000	508,477	448,901
<u>OTHER FINANCING SOURCES (USES)</u>			
Bond proceeds	-	-	-
Debt service			
Principal	(891,000)	(891,000)	-
Interest	(2,416)	(6,927)	4,511
Excess (Deficiency) of Revenues and Other Financing			
Sources (Uses) over Expenditures	(793,416)	(389,450)	453,412
Fund Balance, July 1	1,909,824	2,193,158	283,334
Fund Balance, June 30	\$ 1,116,408	\$ 1,803,708	\$ 687,300

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**FIRE CAPITAL PROJECT FUND**  
**STATEMENT OF REVENUES, EXPENDITURES AND CHANGES IN FUND BALANCE**  
**BUDGET AND ACTUAL**  
**FOR THE YEAR ENDED JUNE 30, 2022**

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>REVENUE</u>			
Federal grants	\$ -	\$ -	\$ -
Other revenues			
Interest	12,500	9,289	
	<u>12,500</u>	<u>9,289</u>	<u>-</u>
<u>EXPENDITURES</u>			
Capital outlay	<u>366,514</u>	<u>93,684</u>	<u>272,830</u>
Excess (Deficiency) of Revenues over Expenditures	<u>(354,014)</u>	<u>(84,395)</u>	<u>(272,830)</u>
<u>OTHER FINANCING SOURCES (USES)</u>			
Transfers in	<u>407,141</u>	<u>407,141</u>	<u>-</u>
Excess(Deficiency) of Revenues and Other Financing Sources (Uses) over Expenditures	<u>53,127</u>	<u>322,746</u>	<u>269,619</u>
Fund Balance, July 1	<u>346,530</u>	<u>336,917</u>	<u>(9,613)</u>
Fund Balance, June 30	<u>\$ 399,657</u>	<u>\$ 659,663</u>	<u>\$ 260,006</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
WATER SYSTEM ENTERPRISE FUND  
STATEMENT OF REVENUE AND EXPENSE  
BUDGET AND ACTUAL  
FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>OPERATING REVENUES</u>			
Sales of water	\$ 591,000	\$ 652,958	\$ 61,958
<u>OPERATING EXPENSES</u>			
Salaries and wages	169,455	138,230	31,225
Benefits	78,192	46,863	31,329
Services and supplies	324,940	263,509	61,431
Capital outlay	-	-	-
Depreciation	-	104,301	(104,301)
Total operating expenses	<u>572,587</u>	<u>552,903</u>	<u>19,684</u>
Operating income (loss)	<u>18,413</u>	<u>100,055</u>	<u>81,642</u>
<u>NON-OPERATING REVENUE (EXPENSES)</u>			
Interest earnings	78,000	37,485	(40,515)
Rents	12,000	12,000	-
Interest Expense	-	-	-
Miscellaneous	-	5,400	5,400
Transfers out	(98,568)	-	98,568
Capital outlay	-	(330,081)	(330,081)
Grants and capital contributions	<u>9,100</u>	<u>354,939</u>	<u>345,839</u>
Net Income (loss)	<u>\$ 18,945</u>	<u>\$ 179,798</u>	<u>\$ 160,853</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA  
WATER SYSTEM ENTERPRISE FUND  
STATEMENT OF CASH FLOWS  
FOR THE YEAR ENDED JUNE 30, 2022**

	ORIGINAL AND FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>CASH FLOWS FROM OPERATING ACTIVITIES</u>			
Cash In flows			
Sales of water	\$ 492,300	\$ 660,529	\$ 168,229
Miscellaneous income	-	5,400	5,400
Cash Out flows			
Salaries and wages	(169,455)	(140,425)	29,030
Benefits	(78,192)	(51,745)	26,447
Services and supplies	(324,948)	(240,003)	84,945
Net Cash Provided by Operating Activities	<u>(80,295)</u>	<u>233,756</u>	<u>314,051</u>
<u>CASH FLOWS FROM NON-CAPITAL FINANCING ACTIVITIES</u>			
Cash In flows			
Rent	12,000	12,000	-
Capital outlay	-	-	-
Customer deposits	-	150	150
Net Cash Provided by Non Capital Financing Activities	<u>12,000</u>	<u>12,150</u>	<u>150</u>
<u>CASH FLOWS FROM CAPITAL AND RELATED ACTIVITIES</u>			
Cash In flows			
Grants	9,100	354,939	345,839
Debt service	-	-	-
Transfer from funds	-	-	-
Cash Out flows			
Capital outlay	-	-	-
Debt service	(98,568)	(63,810)	34,758
Interfund loan	-	-	-
Interest expense	-	-	-
Net Cash (Used) by Capital Related Activities	<u>(89,468)</u>	<u>291,129</u>	<u>380,597</u>
<u>CASH FLOWS FROM INVESTING ACTIVITIES</u>			
Interest earnings	78,000	37,485	(40,515)
Net Increase (Decrease) in Cash	<u>(79,763)</u>	<u>574,520</u>	<u>654,283</u>
Cash, July 1	<u>1,689,221</u>	<u>1,418,308</u>	<u>(270,913)</u>
Cash, June 30	<u>\$ 1,609,458</u>	<u>\$ 1,992,828</u>	<u>\$ 383,370</u>

The notes to the financial statements are an integral part of this statement

STOREY COUNTY, NEVADA  
 VIRGINIA DIVIDE SEWER IMPROVEMENT DISTRICT ENTERPRISE FUND  
 STATEMENT OF REVENUE AND EXPENSE  
 BUDGET AND ACTUAL  
 FOR THE YEAR ENDED JUNE 30, 2022

	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>OPERATING REVENUES</u>				
Sales of water	\$ 433,900	\$ 433,900	\$ 452,150	\$ 18,250
<u>OPERATING EXPENSES</u>				
Salaries and wages	133,136	143,636	138,758	4,878
Benefits	80,073	80,073	43,585	36,488
Services and supplies	112,212	101,712	15,934	85,778
Capital Outlay	-	-	-	-
Depreciation	-	-	502,962	(502,962)
Total operating expenses	<u>325,421</u>	<u>325,421</u>	<u>701,239</u>	<u>(375,818)</u>
Operating income (loss)	<u>108,479</u>	<u>108,479</u>	<u>(249,089)</u>	<u>(357,568)</u>
<u>NON-OPERATING REVENUE (EXPENSES)</u>				
Interest income	(120,613)	(120,613)	65,753	186,366
Interest expense	26,800	26,800	(120,604)	(147,404)
Transfer from capital projects	-	-	-	-
Transfer to USDA	-	-	-	-
Grants and contributions	600,000	600,000	813,243	213,243
Capital outlay	(600,000)	(600,000)	(782,283)	(182,283)
Other income	-	-	-	-
Net Income (loss)	<u>\$ 14,666</u>	<u>\$ 14,666</u>	<u>\$ (272,980)</u>	<u>\$ (287,646)</u>

The notes to the financial statements are an integral part of this statement



**STOREY COUNTY, NEVADA**  
**VIRGINIA DIVIDE SEWER IMPROVEMENT DISTRICT ENTERPRISE FUND**  
**STATEMENT OF CASH FLOWS**  
**FOR THE YEAR ENDED JUNE 30, 2022**

	ORIGINAL BUDGETED AMOUNTS	FINAL BUDGETED AMOUNTS	ACTUAL AMOUNTS	VARIANCE TO FINAL BUDGET
<u>CASH FLOWS FROM OPERATING ACTIVITIES</u>				
Cash In flows				
Sewer Fees	\$ 433,900	\$ 433,900	\$ 444,454	\$ 10,554
Cash Out flows				
Salaries and wages	(133,136)	(143,636)	(137,064)	6,572
Benefits	(80,073)	(80,073)	(46,318)	33,755
Services and supplies	(112,212)	(101,712)	(7,663)	94,049
Net Cash Provided by Operating Activities	<u>108,479</u>	<u>108,479</u>	<u>253,409</u>	<u>144,930</u>
<u>CASH FLOWS FROM NON-CAPITAL FINANCING ACTIVITIES</u>				
Cash In flows				
Bonds	600,000	600,000	-	(600,000)
Cash Out flows				
Capital outlay	(600,000)	(600,000)	(782,283)	(182,283)
Net Cash (Used) by Non Capital Financing Activities	<u>-</u>	<u>-</u>	<u>(782,283)</u>	<u>(782,283)</u>
<u>CASH FLOWS FROM CAPITAL AND RELATED ACTIVITIES</u>				
Cash In flows				
Other income				
Grants	-	-	813,243	813,243
Debt service	-	-	-	-
Cash Out flows				
Debt service	(120,613)	(120,613)	(138,455)	(17,842)
Interest expense	(138,445)	(138,445)	(120,604)	17,841
Net Cash (Used) by Capital Related Activities	<u>(259,058)</u>	<u>(259,058)</u>	<u>554,184</u>	<u>813,242</u>
<u>CASH FLOWS FROM INVESTING ACTIVITIES</u>				
Transfers from general			-	-
Interest earnings	26,800	26,800	65,753	38,953
Net Cash Provided by Capital Related Activities	<u>26,800</u>	<u>26,800</u>	<u>65,753</u>	<u>38,953</u>
Net Increase (Decrease) in Cash	(123,779)	(123,779)	91,063	214,842
Cash, July 1	<u>(33,367)</u>	<u>(33,367)</u>	<u>213,338</u>	<u>246,705</u>
Cash, June 30	<u>\$ (157,146)</u>	<u>\$ (157,146)</u>	<u>\$ 304,401</u>	<u>\$ 461,547</u>

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**SCHEDULE OF CHANGES IN THE TOTAL OPEB LIABILITY AND RELATED RATIOS**  
**JUNE 30, 2022**

	2018	2019	2020	2021	2022
Total OPEB liability					
Service cost	\$ 2,020,652	\$ 1,753,249	\$ 1,837,336	\$ 2,098,098	\$ 3,253,831
Interest	586,141	711,366	703,321	772,012	681,492
Changes of benefit terms	-	1,281,228	-	-	-
Differences between expected and actual experience	-	(4,548,724)	-	(3,100,780)	-
Changes of assumptions or other inputs	(2,542,189)	(1,038,960)	1,285,244	8,214,844	325,808.00
Benefit payments	<u>(208,173)</u>	<u>(214,872)</u>	<u>(226,280)</u>	<u>(305,190)</u>	<u>(290,444)</u>
Net change in total OPEB liability	\$ (143,569)	\$ (2,056,713)	\$ 3,599,621	\$ 7,678,984	\$ 3,970,687
Total OPEB liability-beginning	<u>\$ 18,649,779</u>	<u>\$ 18,506,210</u>	<u>\$ 16,449,497</u>	<u>\$ 20,049,118</u>	<u>\$ 27,728,102</u>
Total OPEB liability-ending	<u>\$ 18,506,210</u>	<u>\$ 16,449,497</u>	<u>\$ 20,049,118</u>	<u>\$ 27,728,102</u>	<u>\$ 31,698,789</u>
Covered-employee payroll	\$ 9,590,509	\$ 9,394,062	\$ 9,894,669	\$ 10,382,380	11451225
Total OPEB liability as a percentage of covered-employee payroll	192.96%	175.11%	202.63%	267.07%	276.82%

GASB Statement No. 75 requires ten years of information to be presented in this table. However, until 10 years of data is compiled, the County will present information only for those years for which information is available.

STOREY COUNTY, NEVADA  
SCHEDULE OF COUNTY'S SHARE OF NET PENSION LIABILITY  
PUBLIC EMPLOYEES' RETIREMENT SYSTEM OF NEVADA  
JUNE 30, 2022

	2021	2020	2019	2018	2017	2016	2015	2014
County's portion of the net pension liability	0.162%	0.153%	0.151%	0.147%	0.145%	0.145%	0.132%	0.129%
County's proportionate share of the net pension liability	\$ 14,812,664	\$ 21,288,635	\$ 20,642,315	\$ 19,998,860	\$ 20,601,898	\$ 19,511,455	\$ 15,126,431	\$ 16,929,912
County's covered-employee payroll	\$ 9,466,969	\$ 8,824,757	\$ 8,676,437	\$ 7,947,637	\$ 8,207,871	\$ 7,299,918	\$ 6,354,233	\$ 6,040,606
County's proportionate share of the net pension liability as a percentage of its covered-employee payroll	156.47%	241.24%	237.91%	251.63%	251.00%	267.28%	238.05%	280.27%
Plan fiduciary net position as a percentage of the total net pension liability	86.51%	77.04%	76.46%	75.24%	74.40%	72.20%	75.10%	76.30%


GASB Statement No. 68 requires ten years of information to be presented in this table. However, until 10 years of data is compiled, the County will present information only for those years for which information is available.

The notes to the financial statements are an integral part of this statement

**STOREY COUNTY, NEVADA**  
**SCHEDULE OF COUNTY'S CONTRIBUTIONS - PUBLIC EMPLOYEES' RETIREMENT SYSTEM OF NEVADA**  
**JUNE 30, 2022**

	2022	2021	2020	2019	2018	2017	2016	2015
Statutorily required contribution	\$ 1,855,184	\$ 1,696,329	\$ 1,553,718	\$ 1,568,057	\$ 1,360,192	\$ 1,390,646	\$ 1,229,299	\$ 1,018,739
Contributions in relation to the statutorily required contrib	\$ (1,855,184)	\$ (1,696,329)	\$ (1,553,718)	\$ (1,568,057)	\$ (1,360,192)	\$ (1,390,646)	\$ (1,229,299)	\$ (1,018,739)
Contribution (deficiency) excess	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
County's covered-employee payroll	10230470	\$ 9,466,969	\$ 8,824,757	\$ 8,676,437	\$ 7,947,637	\$ 8,207,871	\$ 7,299,918	\$ 6,354,233
Contributions as a percentage of covered-employee payroll	18.13%	17.92%	17.61%	18.07%	17.11%	16.94%	16.84%	16.03%

GASB Statement No. 68 requires ten years of information to be presented in this table. However, until 10 years of data is compiled, the County will present information only for those years for which information is available.



**DiPietro & Thornton**  
CERTIFIED PUBLIC ACCOUNTANTS

Joseph F. Costanza, CPA  
Scott A. Westover, CPA  
Theresa M. Westover, CPA

Of Counsel  
John E. DiPietro, CPA  
Randall D. Thornton, CPA

**REPORT ON INTERNAL CONTROL OVER FINANCIAL REPORTING AND ON  
COMPLIANCE AND OTHER MATTERS BASED ON AN AUDIT OF FINANCIAL  
STATEMENTS PERFORMED IN ACCORDANCE  
WITH GOVERNMENT AUDITING STANDARDS**

To the Honorable Board of Commissioners  
Storey County, Nevada

We have audited, in accordance with auditing standards generally accepted in the United States of America and the standards applicable to financial audits contained in Government Auditing Standards, issued by the Comptroller General of the United States, the financial statements of the governmental activities, the business-type activities, each major fund, and the aggregate remaining fund information of Storey County, Nevada, as of and for the year ended June 30, 2022, and the related notes to the financial statements, which collectively comprise the Storey County's basic financial statements and have issued our report thereon dated December 20, 2022.

**Internal Control Over Financial Reporting**

In planning and performing our audit of the financial statements, we considered Storey County, Nevada's internal control over financial reporting (internal control) to determine the audit procedures that are appropriated in the circumstances for the purpose of expressing our opinions on the financial statements, but not for the purpose of expressing an opinion on the effectiveness of Storey County, Nevada's internal control. Accordingly, we do not express an opinion on the effectiveness of the Storey County, Nevada's internal control.

A deficiency in internal control exists when the design or operation of a control does not allow management or employees, in the normal course of performing their assigned functions, to prevent or detect and correct, misstatements on a timely basis. A material weakness is a deficiency, or a combination of deficiencies, in internal control, such that there is a reasonable possibility that a material misstatement of the entity's financial statements will not be prevented, or detected and corrected on a timely basis. A significant deficiency is a deficiency, or a combination of deficiencies, in internal control that is less severe than a material weakness, yet important enough to merit attention by those charged with governance.

Our consideration of internal control over financial reporting was for the limited purpose described in the first paragraph of this section and was not designed to identify all deficiencies in internal control that might be material weaknesses or significant deficiencies and therefore, material weaknesses or significant deficiencies may exist that were not identified. We did identify certain deficiencies in internal control, described in the accompanying schedule of findings and questioned costs that we consider to be significant deficiencies.

**Compliance and Other Matters**


As part of obtaining reasonable assurance about whether Storey County, Nevada's financial statements are free from material misstatement, we performed tests of its compliance with certain provisions of laws, regulations, contracts and grants agreements, noncompliance with which could have a direct and material effect on the determination of financial statement amounts. However, providing an opinion on compliance with those provisions was not an objective of our audit and, accordingly, we do not express such an opinion. The results of our tests disclosed no instances of noncompliance that are required to be reported under Government Auditing Standards.

**Storey County's Response to Findings**


Storey County, Nevada's response to the finding identified in our audit is described in the accompanying schedule of findings and questioned costs. Storey County, Nevada's response was not subjected to the auditing procedures applied in the audit of the financial statements and, accordingly, we express no opinion on it.

**Purpose of this Report**

The purpose of this report is solely to describe the scope of our testing of internal control and compliance and the results of that testing, and not to provide an opinion on the effectiveness of the entity's internal control or on compliance. This report is an integral part of an audit performed in accordance with Government Auditing Standards in considering the entity's internal control and compliance. Accordingly, this communication is not suitable for any other purpose.



Reno, Nevada  
December 20, 2022



**DiPietro & Thornton**  
CERTIFIED PUBLIC ACCOUNTANTS

Joseph E. Costanza, CPA  
Scott A. Westover, CPA  
Theresa M. Westover, CPA

Of Counsel  
John F. DiPietro, CPA  
Randall D. Thornton, CPA

**INDEPENDENT AUDITOR'S REPORT ON COMPLIANCE FOR EACH MAJOR PROGRAM AND ON  
INTERNAL CONTROL OVER COMPLIANCE REQUIRED BY UNIFORM GUIDANCE**

To the Honorable Board of Commissioners  
Storey County, Nevada

***Report on Compliance of Each Major Federal Program Opinion of***

***Each Major Federal Program***

We have audited Story County, Nevada's compliance with the types of compliance requirements described in the *OMB Compliance Supplement* that could have a direct and material effect on each of Story County, Nevada's major federal programs for the year ended June 30, 2022. Story County, Nevada's major federal programs are identified in the summary of auditor's results section of the accompanying schedule of findings and questioned costs.

In our opinion, Story County, Nevada, complied, in all material respects, with the types of compliance requirements referred to above that could have a direct and material effect on each of its major federal programs for the year ended June 30, 2022.

***Basis for Opinion on Each Major Federal Program***

We conducted our audit of compliance in accordance with auditing standards generally accepted in the United States of America; the standards applicable to financial audits contained in *Government Auditing Standards*, issued by the Comptroller General of the United States; and the audit requirements of Title 2 U.S. Code of Federal Regulations Part 200, *Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards* (Uniform Guidance). Our responsibilities under those standards and the Uniform Guidance are further described in the Auditor's Responsibilities for the Audit of Compliance section of our report.

We are required to be independent of Story County, Nevada and to meet our other ethical responsibilities, in accordance with relevant ethical requirements relating to our audit. We believe that the audit evidence we have obtained is sufficient and appropriate to provide a basis for our opinion on compliance for each major federal program. Our audit does not provide a legal determination of Story County, Nevada's compliance with the compliance requirements referred to above.

***Responsibilities of Management for Compliance***

Management is responsible for compliance with the requirements referred to above and for the design, implementation, and maintenance of effective internal control over compliance with the requirements of laws, statutes, regulations, rules, and provisions of contracts or grant agreements applicable to Story County's federal programs.

***Auditor's Responsibilities for the Audit of Compliance***

Our objectives are to obtain reasonable assurance about whether material noncompliance with the compliance requirements referred to above occurred, whether due to fraud or error, and express an opinion on Story County, Nevada's compliance based on our audit. Reasonable assurance is a high level of assurance but is not absolute assurance and therefore is not a guarantee that an audit conducted in accordance with generally accepted auditing standards, *Government Auditing Standards*, and the Uniform Guidance will always detect material noncompliance when it exists. The risk of not detecting material noncompliance resulting from fraud is higher than for that resulting from error, as fraud may involve collusion, forgery, intentional omissions, misrepresentations, or the override of internal control. Noncompliance with the compliance requirements referred to above is considered material if there is a substantial likelihood that, individually or in the aggregate, it would influence the judgment made by a reasonable user of the report on compliance about Story County, Nevada's compliance with the requirements of each major federal program as a whole.

In performing an audit in accordance with generally accepted auditing standards, *Government Auditing Standards*, and the Uniform Guidance, we:

- Exercise professional judgment and maintain professional skepticism throughout the audit.
- Identify and assess the risks of material noncompliance, whether due to fraud or error, and design and perform audit procedures responsive to those risks. Such procedures include examining, on a test basis, evidence regarding Story County, Nevada's compliance with the compliance requirements referred to above and performing such other procedures as we considered necessary in the circumstances.
- Obtain an understanding of Story County, Nevada's internal control over compliance relevant to the audit in order to design audit procedures that are appropriate in the circumstances and to test and report on internal control over compliance in accordance with the Uniform Guidance, but not for the purpose of expressing an opinion on the effectiveness of Story

County, Nevada's internal control over compliance. Accordingly, no such opinion is expressed.

We are required to communicate with those charged with governance regarding, among other matters, the planned scope and timing of the audit and any significant deficiencies and material weaknesses in internal control over compliance that we identified during the audit.

#### **Report on Internal Control over Compliance**

*A deficiency in internal control over compliance* exists when the design or operation of a control over compliance does not allow management or employees, in the normal course of performing their assigned functions, to prevent, or detect and correct, noncompliance with a type of compliance requirement of a federal program on a timely basis. *A material weakness in internal control over compliance* is a deficiency, or a combination of deficiencies, in internal control over compliance, such that there is a reasonable possibility that material noncompliance with a type of compliance requirement of a federal program will not be prevented, or detected and corrected, on a timely basis. *A significant deficiency in internal control over compliance* is a deficiency, or a combination of deficiencies, in internal control over compliance with a type of compliance requirement of a federal program that is less severe than a material weakness in internal control over compliance, yet important enough to merit attention by those charged with governance.

Our consideration of internal control over compliance was for the limited purpose described in the Auditor's Responsibilities for the Audit of Compliance section above and was not designed to identify all deficiencies in internal control over compliance that might be material weaknesses or significant deficiencies in internal control over compliance. Given these limitations, during our audit we did not identify any deficiencies in internal control over compliance that we consider to be material weaknesses, as defined above. However, material weaknesses or significant deficiencies in internal control over compliance may exist that were not identified.

Our audit was not designed for the purpose of expressing an opinion on the effectiveness of internal control over compliance. Accordingly, no such opinion is expressed.

The purpose of this report on internal control over compliance is solely to describe the scope of our testing of internal control over compliance and the results of that testing based on the requirements of the Uniform Guidance. Accordingly, this report is not suitable for any other purpose.



Reno, Nevada  
December 20, 2022



STOREY COUNTY, NEVADA  
SCHEDULE OF EXPENDITURES OF FEDERAL AWARDS  
FOR THE YEAR ENDED JUNE 30, 2022

<u>Federal Grantor/Program/Grant Description</u>	<u>Federal CFDA Number</u>	<u>Pass-Through Entity Identifying Number</u>	<u>Expenditures</u>
<u>US Department of Agriculture</u>			
Water and Waste Disposal System for Rural Communities	10.760	N/A	\$ 813,244
Water and Waste Disposal System for Rural Communities	10.760	N/A	354,939
<u>US Department of the Interior</u>			
Direct Funding			
Historic Preservation Fund Grants-In-Aid	15.904	HPF NV-20-10015	33,880
<u>U.S. Department of Housing and Urban Development</u>			
Community Development Block Grants	14.228	CDBG-CVR2 20/PS/37	1,470
<u>U.S. Department of Transportation</u>			
Passed through Nevada State Emergency Response Commission			
Interagency Hazardous Materials Public Sector Training and Planning Grants	20.703	22-HMEP-15-01	6,638
<u>US Department of Homeland Security</u>			
Direct Funding			
Staffing for Adequate Fire and Emergency Response	97.083	N/A	330,896
Passed Through State of Nevada Department of Public Safety			
Emergency Management Performance Grant	97.042	EMPG FFY 21	<u>14,739</u>
Total Federal Financial Assistance			<u>\$ 1,555,806</u>

STOREY COUNTY, NEVADA  
NOTES TO SCHEDULE OF EXPENDITURES OF FEDERAL AWARDS  
FOR THE YEAR ENDED JUNE 30, 2022

**Note A- Basis of Presentation**

The accompanying schedule of expenditures of federal awards (the Schedule) includes the federal award activity of Storey County under programs of the federal government for the year ending June 30, 2022. The information in this Schedule is presented in accordance with the requirements of Title 2 U.S. Code of Federal Regulations Part 200, *Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards* (Uniform Guidance). Because the Schedule present only a selected portion of the operations of Storey County, it is not intended to and does not present the financial position, changes in net position, or cash flows of Storey County.

**Note B- Summary of Significant Accounting Policies**

Expenditures reported on the Schedule are reported on the modified accrual basis of accounting. Such expenditures are recognized following, as applicable, either the cost principles in OMB Circular A-87, Cost Principles for Audits of State, Local, and Indian Tribal Governments, or the cost principles contained in the Uniform Guidance wherein certain types of expenditures are not allowed or are limited as reimbursement. When applicable, negative amount shown on the Schedule represent adjustments or credits made in the normal course of business as expenditures in prior years.

Indirect Costs

The County has elected not to use the 10-percent de minimis indirect cost rate allowed under the Uniform Guidance

**Note C- Subrecipients**

Storey County did not pass any federal awards received to any other government or not-for profit agencies.

**Note D - Loans with Continuing Compliance Requirement**

Outstanding federally-funded program loans with a continuing compliance requirement, carried balance as of June 30, 2022 as follows:

<u>CFDA</u>	<u>Program Title</u>		<u>Loan Balance</u>
10.760	Water and Waste Disposal System for Rural Communities	\$	2,051,463
10.760	Water and Waste Disposal System for Rural Communities	\$	674,080
10.760	Water and Waste Disposal System for Rural Communities	\$	329,363
10.760	Water and Waste Disposal System for Rural Communities	\$	253,925

**Note E – Matching Requirements**

Certain Federal programs require Storey County to contribute non-Federal funds (matching funds) to support the Federally Funded programs. Storey County has met its matching requirements. The Schedule does not include the expenditure for non-Federal matching funds.

STOREY COUNTY, NEVADA  
 SCHEDULE OF FINDINGS AND QUESTIONS COSTS  
 FOR THE YEAR ENDED JUNE 30, 2022

**A. Summary of Auditors Results**

*Financial Statements*

Type of report the auditor issued on whether the financial Statements audited were prepared in accordance with GAAP:	Unmodified
Internal control over financial reporting:	
Material weakness identified?	Yes
Significant deficiency identified?	Yes
Noncompliance material to financial statements noted?	No

*Federal awards*

Internal control over major federal programs:	
Material weakness identified?	No
Significant deficiency identified?	No

Type of auditor's report issued on compliance for major programs	Unmodified
--	------------

Any audit findings disclosed that are required to be reported in accordance with 2 CFR 200.516(a)	No
---	----

Identification of major federal programs:

CFDA #	Name of Federal Program or Cluster
10.76	Water and Waste Disposal System for Rural Communities

Dollar threshold used to distinguish between type A and type B programs	\$ 750,000
---	------------

Auditee qualified as low-risk auditee	No
---------------------------------------	----

**B. Financial Statement Findings**

Findings Relating to The Financial Statements Reported in Accordance with GAGAS

2022-A Report Preparation  
Material Weakness

Criteria	Management of Storey County is responsible for establishing, and maintaining an effective system of internal control over financial reporting. One of the key components of an effective system, of internal control is to provide the finance staff with adequate resources available to prepare the financial, statements in accordance with generally accepted accounting principles.
Condition	In the process of completing our audit, we were requested to draft the financial statements, assist with the conversion of fund financial statements to government-wide statements, and prepare the accompanying notes, to the financial statements.
Cause	Given the daily responsibilities of management,, the resources of time, and, training necessary to prepare the County's financial statements in accordance with generally accepted accounting principles are not available. As a result the County has chosen to contract with Dipietro and Thornton to prepare the financial statements. This circumstance is not unusual in an organization of this size; due to time constraints of management and costs associated with compliance of the standards. However, management has not implemented sufficient procedures to capture the necessary information needed for the financial, statements and related disclosures to be prepared in all material respects.
Effect	The County's financial records required audit adjustments in order for the financial statements to be in, accordance with GAAP. Internally prepared financial information may not be accurate and full disclosure financial statements may not be available as timely as they would be if prepared by County personnel.
Recommendation	We recommend County staff continue to obtain training in the preparation of the financial statements and related financial statement disclosures in order to gain the knowledge needed to prepare the financial statements and related financial statement disclosures in all material respects.
Views of Responsible Officials	Management agrees with this finding

**B. Financial Statement Findings**

Findings Relating to The Financial Statements Reported in Accordance with GAGAS

2022-B F Absent or inadequate controls over the safeguarding of assets  
Significant Deficiency

Criteria	Facilitating the negotiation and execution of contracts and agreements to safeguard the County's assets
Condition	During our audit we identified a lease that was not being charged at the proper amount. The County had not charged cell phone company the proper amounts due according to the lease.
Cause	Storey County did not have adequate controls in place to ensure the correct amounts were charged for the leases.
Effect	Failure of controls over safeguarding assets can result in loss, damage or misappropriation
Recommendation	We recommend that the county revisit all leases on a yearly basis to make sure all increases contained in the lease are applied
Views of Responsible Officials	Management agrees with this finding

STOREY COUNTY, NEVADA  
STATUS OF PRIOR YEAR FINDINGS AND QUESTIONED COSTS  
FOR THE YEAR ENDED JUNE 30, 2022

A Findings relating to The Financial Statements Reported in Accordance with GAGAS

1 2021-A

We recommended that the County put in procedures to close the books each month on a timely basis

This was implemented during the year

2 2021-B

We recommended County staff continue to obtain training in the preparation of the financial statements and related financial statement disclosures in order to gain the knowledge needed to prepare the financial statements and related financial statement disclosures in all material respects.

This was not implemented and is included in the current year finding 2021-B

B. Findings and Questioned Costs- Major Federal Award Program Audit

No audit findings were reported

**CERTIFICATE OF COVERAGE**

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AMEND, EXTEND OR ALTER THE COVERAGE FORMS ISSUED TO THE COVERED MEMBER

<b>AGENT</b>  Nevada Risk Pooling, Inc. 201 S Roop St, Suite 102 Carson City, NV 89701	<b>DATE OF ISSUANCE</b>  04/22/2024
<b>COVERED MEMBER</b>  Storey County	<b>COVERAGE TO MEMBER PROVIDED BY AGREEMENT WITH:</b>  Nevada Public Agency Insurance Pool 201 S. Roop St., Suite 102 Carson City, NV 89701-4790  A POOL FORMED PURSUANT TO THE INTERLOCAL COOPERATION ACT CHAPTER 277 OF THE NEVADA REVISED STATUTES

**COVERAGES:**  
 THIS IS TO CERTIFY THAT THE COVERAGES IN EFFECT AS LISTED BELOW HAVE BEEN ISSUED TO THE POOL MEMBER NAMED ABOVE FOR THE TIME PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE OF COVERAGE MAY BE ISSUED OR MAY PERTAIN. THE COVERAGE AFFORDED BY THE COVERAGE FORMS DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH FORMS.

TYPE OF COVERAGE	COVERAGE FORM NUMBER	EFFECTIVE DATE	EXPIRATION DATE	LIMIT
LIABILITY INCLUDING AUTO LIABILITY, LAW ENFORCEMENT LIABILITY AND WRONGFUL ACTS LIABILITY	NPAIP20232024	7/1/2023	7/1/2024	\$1,000,000
PROPERTY INCLUDING ALL REAL AND PERSONAL PROPERTY, AUTOMOBILES, AND EQUIPMENT	NPAIP20232024	7/1/2023	7/1/2024	\$4,126,190
OTHER				
ADDITIONAL ASSURED per Section 1.2 of POOL COVERAGE FORM:				

**DESCRIPTION OF OPERATIONS\LOCATIONS\VEHICLES\SPECIAL ITEMS**  
 Proof of Coverage for Piper's, which has a value of \$4,126,190. Storey County has a \$5,000 Maintenance Deductible.

<b>CERTIFICATE HOLDER</b>  Proof of Coverage	<b>CANCELLATION:</b>  SHOULD ANY OF THE ABOVE DESCRIBED COVERAGE FORMS BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE PROVISIONS OF THE FORMS.
--	--

AUTHORIZED REPRESENTATIVE \_\_\_\_\_



# Sara Sturtz, M.A.

Reno, NV sturtzsara@gmail.com 775-340-5192

---

## Employment History:

- 2024 **Grants Manger, Storey County, Virginia City, Nevada**
- Manage all aspects of federal and state grants administered within the County.
  - Manage grant project timelines, work-plans, milestone tracking, deliverable schedules, and reporting requirements.
  - Research, monitor and coordinate fiscal compliance activities; maintain respective compliance requirements.
  - Review funding requests and coordinate the review process, as needed.
  - Develop, monitor and maintain grant project tracking systems to ensure timely preparation of grant reimbursement remittances and compliance with grant requirements.
  - Provide guidance to the Department/Offices or programs to include fiscal guidance, technical assistance and training to the Departments/Offices in the preparation of grant applications and in the development and implementation of proper procedures to ensure grant compliance and accountability systems; monitor the implementation of grant funded projects located throughout the County.
  - Work closely with the program staff to monitor expenditures, payments, and reports to ensure both the grant and subgrants stay on budget.
  - Assists in all audit requirements for the County and sub-grantees.
  - Conducts grant contract monitoring for County and sub-grantees.
  - Manage the county support to nonprofits and county owned historic buildings.
  - Prepare and submit Certificates of Appropriateness to the Comstock Historic District for all County owned buildings.
  - Prepare and submit Section 106 Reviews and Covenants Reviews to the SHPO
  - Identify grant funding needs and research and maintain information on available federal, state, local and private grant funding sources to maximize funding opportunities available to the County; coordinate with federal, state, local and private agency officials to ensure the County's awareness of possible grant funding sources for new and on-going projects.
  - Prepare grant applications and recommendations for new funding sources in conjunction with needs assessments and program evaluations, to better achieve Department/Office program goals and objectives.
- 2023 **Grants and Projects Analyst II, Nevada Division of State Parks, Carson City**
- Develop, implement, assess, monitor, control, and review federal grant-in-aid projects and programs administered by State agencies and assist recipients in evaluating program effectiveness.
  - Develop and maintain procedural manuals, applications, agreements, outreach materials, tracking forms, and financial spreadsheets for the Recreational Trails Program (RTP) and Land and Water Conservation Fund (LWCF) grant programs.
  - Provide technical assistance to interested parties regarding the RTP and LWCF programs including project specifications, the application process, program regulations, and grant management software.
  - Conduct inspections of RTP and LWCF projects to determine adherence to scopes of work detailed in signed agreements, request and review reimbursements and quarterly reports from grantees.
  - Ensure that projects are in compliance with 2 CFR Part 200, the National Environmental Policy Act (NEPA) and the National Historic Preservation Act (NHPA), in coordination with the Federal Highway Administration (FHWA), Nevada Department of Transportation (NDOT), and National Park Service (NPS).
  - Assist in the development of grant program policy, strategy, and schedules.



## Sara Sturtz, M.A.

**Reno, NV sturtzsara@gmail.com 775-340-5192**

- Assist in planning and delivery of annual advisory committee meetings; and research, compose, and implement required management documents including Programmatic Agreements (PA), Memorandum of Agreements (MOAs), and the State Comprehensive Outdoor Recreation Plan.

2021-2023

### **Review & Compliance Archaeologist, State Historic Preservation Office, Carson City**

- Recommended to state and federal agencies the kind and intensity of archaeological surveys, historic contexts, and background studies to be conducted.
- Reviewed and provided comments on archaeological survey reports prepared in the State of Nevada to ensure they meet federal and state standards (Section 106 of the NHPA, NRS 383.121, etc.).
- Determined the adequacy of documentation for evaluation of cultural resources discovered.
- Recommended whether or not to concur with federal agency determinations of significance and project related effects regarding Section 106 and NRS 383.
- Provided advice and technical assistance to state and federal agencies regarding the treatment and stewardship of cultural resources and historic properties.
- Educated the public on preservation issues.
- Coordinated with other state and federal agencies to set standards for report writing, evaluation, stewardship, and mitigation of cultural resources.

2020-2021

### **Associate Archaeologist, ASM Affiliates, Reno**

- Coordinated and facilitated fieldwork and prepared technical reports.
- Supervised field staff and prepared coherent field notes and forms, collected field data, conducted archival and record searches, and produced site forms.
- Assisted the lab supervisor in laboratory processing, cataloging, and analysis.

2018-2020

### **Community Engagement Assistant, Fourth Ward School Museum, Virginia City**

- Assisted the Executive Director with fundraising, donor development, marketing and development of the museum, museum programs, and special events.
- Assisted with leading, coordinating, and scheduling school and group tours.

2015-2018

### **Programs Coordinator, Terry Lee Wells Nevada Discovery Museum, Reno**

- Main point of contact for The Discovery's financial assistance program and educational programs including seasonal camps, field trips, overnights, and family science nights at The Discovery
- Managed the application process, application review, allocation of funds, tracking, and reporting for the financial assistance program
- Assisted development officers in grant writing for the financial assistance program
- Assisted the Museum Manager with training of employees on policies and procedures and act as the incident commander during emergencies

### **Education:**

M.A. 2020/Anthropology/UNR **Thesis Title:** *A Natural and Cultural History of Leonard Rockshelter, NV*

B.A. 2016/Anthropology, Archaeology, Minors: Museum Studies, Historic Preservation/UNR

### **Additional Training:**

2023 Grant Management Training , Grant Management USA

2022 Access 2016 Training Part 1 and 2, New Horizons

2022 Section 106 Agreements, Advisory Council on Historic Preservation

2021 Section 106 Essentials, Advisory Council on Historic Preservation

## Sara Sturtz, M.A.

Reno, NV sturtzsara@gmail.com 775-340-5192

### Professional Memberships:

Former Comstock Historic District Commission/Board Member  
Great Basin Anthropological Association/Member  
Nevada Archaeological Association/Member

### Awards/Commendations:

2019–2020 Herbert E. Splatt Scholarship, University of Nevada, Reno  
2018 Research Scholarship, Am-Arcs of Nevada

### Presentations and Publications:

Smith, Geoffrey M., **Sara N. Sturtz**, Anna J. Camp, Kenneth D. Adams, Elizabeth Kallenbach, Richard L. Rosencrance, and Richard E. Hughes

2022 Leonard Rockshelter Revisited: Evaluating a 70-Year-Old Claim of a Late Pleistocene Human Occupation in the Western Great Basin, *American Antiquity*, 1-18. doi:10.1017/aaq.2022.40

Sturtz, Sara N.

2021 The Natural and Cultural History of Leonard Rockshelter, NV. Presented for The Archaeological Conservancy 2021 Spring Virtual Lecture Series, Virtual Format.

Sturtz, Sara N., and Geoffrey M. Smith

2021 Renewed Investigations at Leonard Rockshelter. Presented at the 86<sup>th</sup> annual meeting of the Society for American Archaeology, Virtual Format.

Sturtz, Sara N., Geoffrey M. Smith, Nicole George, Derek Reaux, and Richard Rosencrance

2019 Leonard Rockshelter: Evaluating a 70-Year-Old Claim of a Clovis-Era Occupation. Presented at the annual meeting for the Nevada Archaeological Association, Elko, Nevada.

Sturtz, Sara N., Geoffrey M. Smith, Nicole George, Derek Reaux, and Richard Rosencrance

2018 Revisiting Leonard Rockshelter to Evaluate a 70-Year-Old Claim of a Clovis-Era Occupation. Presented at the 36<sup>th</sup> Great Basin Anthropological Conference, Salt Lake City, Utah.

# Jason Wierzbicki

Sun Valley, NV | 775-229-9920 | fishntime27@hotmail.com

## Summary

---

A seasoned Public Works Director with over 15 years of experience in supervising jobs from beginning to end and who can also effectively communicate with all trades and other construction professionals and departments to execute construction project plans and crews in a safe and timely manner for the duration of the construction task.

## Education

---

Lathrop High Vocational Tech

Aug '87-May '91

Electrical, building framing, concrete, sheetrock, mud, tape, texture, finish carpentry, roofing, flooring, Plumbing, welding, and fabrication.

## Experience

---

Storey County Public Works, Director

Dec '07-Present

Started as Facilities Maintenance Coordinator,  
Planned, ordered materials, and executed full remodels along with new construction of county facilities from concrete through finish.

Promoted to Road Supervisor along with Facilities Maintenance Coordinator,  
Organized and executed various road projects including patching, paving, and crack sealing along with the facilities duties.

Promoted to Assistant Public Works Director,  
Planned projects in Roads, Water, Sewer, Service, Parks, and B&G. Was responsible for day-to-day operations and communicating jobs to each department's supervisors.

Appointed to Public Works Director,  
Planning, execute, directing staff, budgeting, day to day operations, code compliance, certifications, work in the office and in the field as needed for projects.